

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	25 CY		
0003	0106000000-E	230	BORROW EXCAVATION	4,446 CY		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	50 TON		
0005	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	100 LF		
0006	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	50 LF		
0007	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	50 LF		
0008	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	50 LF		
0009	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0010	1245000000-E	SP	SHOULDER RECONSTRUCTION	13.68 SMI		
0011	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	6,559 SY		
0012	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	92,294 SY		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	5,914 SY		
0014	1330000000-E	607	INCIDENTAL MILLING	372 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	6,170 TON		
0016	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	15,530 TON		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,336 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	994 TON		
001E	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	646 TON		
002C	1880000000-E	SP	GENERIC PAVING ITEM PATCH EXISTING PAVEMENT (FULL DEPTH)	50 TON		
0021	1880000000-E	SP	GENERIC PAVING ITEM PATCH EXISTING PAVEMENT (MILL)	100 TON		
0022	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	78,356 LF		
0023	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	54,326 LF		
0024	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	425 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	100 LF		
0026	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0027	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	7 EA		
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	131,987 LF		
002E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	425 LF		
003C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100 LF		
0031	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	12 EA		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0032	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	7	EA	
0033	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	578	EA	
0034	6000000000-E	1605	TEMPORARY SILT FENCE	777	LF	
0035	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	194	TON	
0036	6012000000-E	1610	SEDIMENT CONTROL STONE	194	TON	
0037	6015000000-E	1615	TEMPORARY MULCHING	8	ACR	
0038	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	391	LB	
0039	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2	TON	
0040	6036000000-E	1631	MATTING FOR EROSION CONTROL	100	SY	
0041	6042000000-E	1632	1/4" HARDWARE CLOTH	389	LF	
0042	6084000000-E	1660	SEEDING & MULCHING	8	ACR	
1500/May11/Q413348.68/D132610100000/E42			Total Amount Of Bid For Entire Project :			

Contract No **C202356**

County (ies): **Sampson County**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General