

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (13+05.00)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	250 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	54 TON		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0012	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	780 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	430 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	62 TON		
0016	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0018	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
0020	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3	EA	
0021	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0022	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
0025	2556000000-E	846	SHOULDER BERM GUTTER	95	LF	
0026	3030000000-E	862	STEEL BM GUARDRAIL	475	LF	
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0028	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0030	3649000000-E	876	RIP RAP, CLASS B	5	TON	
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	830	SY	
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	373	SF	
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	231	SF	
0034	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	
0035	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,600	LF	
0036	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,600	LF	

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	760 LF		
0038	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	20 EA		
0039	5325600000-E	1510	6" WATER LINE	1,050 LF		
0040	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	80 LF		
0041	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	80 LF		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	900 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	110 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	210 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	70 LF		
0050	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0051	6029000000-E	SP	SAFETY FENCE	500 LF		
0052	6030000000-E	1630	SILT EXCAVATION	485 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,950 SY		
0054	6037000000-E	SP	COIR FIBER MAT	20 SY		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	900 SY		
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	35 LF		
0057	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0058	6071010000-E	SP	WATTLE	120 LF		
0059	6071020000-E	SP	POLYACRYLAMIDE (PAM)	45 LB		
0060	6071030000-E	SP	COIR FIBER BAFFLES	230 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0063	6087000000-E	1660	MOWING	2 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0068	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0070	6123000000-E	1670	REFORESTATION	0.1 ACR		

**STRUCTURE ITEMS**

0071	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+05.00-L-)	Lump Sum	L.S.	
0072	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	111.66 LF		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	32 LF		
0074	8113000000-N	SP	SID INSPECTION	1 EA		
0075	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0076	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	840 CY		
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	95.7 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+05.00-L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,010 LB		
0080	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,202 LB		
0081	8364000000-E	450	HP12X53 STEEL PILES	455 LF		
0082	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	365.333 LF		
0083	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	331 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	369 SY		
0085	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0086	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	2,189 LF		

0931/Apr28/Q49805.243/D407561240000/E86

Total Amount Of Bid For Entire Project :

**Contract No**     **C202123**

**County (ies):**   **Warren**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General