

County : Warren

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 77.50) | Lump Sum | L.S. | |
| 0004 | 0036000000-E | 225 | UNDERCUT EXCAVATION | 200 CY | | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0006 | 0063000000-N | SP | GRADING | Lump Sum | L.S. | |
| 0007 | 0106000000-E | 230 | BORROW EXCAVATION | 11,100 CY | | |
| 0008 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 70 CY | | |
| 0009 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 500 CY | | |
| 0010 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 200 SY | | |
| 0011 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 26 TON | | |
| 0012 | 0343000000-E | 310 | 15" SIDE DRAIN PIPE | 16 LF | | |
| 0013 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 72 LF | | |
| 0014 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 68 LF | | |
| 0015 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 4 EA | | |
| 0016 | 0995000000-E | 340 | PIPE REMOVAL | 21 LF | | |
| 0017 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 160 TON | | |
| 0018 | 1245000000-E | SP | SHOULDER RECONSTRUCTION | 5.4 SMI | | |

County : Warren

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0019 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 960 TON | | |
| 0020 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 580 TON | | |
| 0021 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 5,810 TON | | |
| 0022 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 450 TON | | |
| 0023 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 8 EA | | |
| 0024 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 4 EA | | |
| 0025 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 4 EA | | |
| 0026 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 875 LF | | |
| 0027 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 1,325 LF | | |
| 0028 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0029 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0030 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 4 EA | | |
| 0031 | 3635000000-E | 876 | RIP RAP, CLASS II | 3,000 TON | | |
| 0032 | 3649000000-E | 876 | RIP RAP, CLASS B | 170 TON | | |
| 0033 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 2,350 SY | | |
| 0034 | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 27 LF | | |
| 0035 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 2 EA | | |
| 0036 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL | 8 EA | | |

County : Warren

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0037 | 4158000000-N | 907 | DISPOSAL OF SIGN SYSTEM, WOOD | 2 EA | | |
| 0038 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 566 SF | | |
| 0039 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 288 SF | | |
| 0040 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |
| 0041 | 4435000000-N | 1135 | CONES | 30 EA | | |
| 0042 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 64 LF | | |
| 0043 | 4455000000-N | 1150 | FLAGGER | 28 MD | | |
| 0044 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 35,503 LF | | |
| 0045 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 35,502 LF | | |
| 0046 | 4710000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 40 LF | | |
| 0047 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 221 EA | | |
| 0048 | 5325600000-E | 1510 | 6" WATER LINE | 100 LF | | |
| 0049 | 5540000000-E | 1515 | 6" VALVE | 1 EA | | |
| 0050 | 5672000000-N | 1515 | RELOCATE FIRE HYDRANT | 1 EA | | |
| 0051 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,500 LF | | |
| 0052 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 180 TON | | |
| 0053 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 155 TON | | |
| 0054 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 85 TON | | |

County : Warren

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 005E | 6015000000-E | 1615 | TEMPORARY MULCHING | 5.5 | ACR | |
| 005E | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 150 | LB | |
| 0057 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEEDING | 1.75 | TON | |
| 005E | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 375 | LF | |
| 005E | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 4 | EA | |
| 006C | 6029000000-E | SP | SAFETY FENCE | 950 | LF | |
| 0061 | 6030000000-E | 1630 | SILT EXCAVATION | 425 | CY | |
| 0062 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 2,400 | SY | |
| 0063 | 6037000000-E | SP | COIR FIBER MAT | 25 | SY | |
| 0064 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 1,150 | SY | |
| 006E | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 200 | LF | |
| 006E | 6071030000-E | SP | COIR FIBER BAFFLES | 200 | LF | |
| 0067 | 6071050000-E | SP | *** SKIMMER (1-1/2") | 4 | EA | |
| 006E | 6084000000-E | 1660 | SEEDING & MULCHING | 10 | ACR | |
| 006E | 6087000000-E | 1660 | MOWING | 3 | ACR | |
| 007C | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 | LB | |
| 0071 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 | TON | |
| 0072 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 125 | LB | |
| 0073 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 3.5 | TON | |

County : Warren

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|--|---------------|-----------|--------|
| 0074 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 5 HR | | |
| 0075 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 EA | | |
| STRUCTURE ITEMS | | | | | | |
| 0076 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 77.50-L-) | Lump Sum | L.S. | |
| 0077 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16 + 77.50-L-) | Lump Sum | L.S. | |
| 0078 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 5,029 SF | | |
| 0079 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 4,893 SF | | |
| 0080 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 45.4 CY | | |
| 0081 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (16 + 77.50-L-) | Lump Sum | L.S. | |
| 0082 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 6,244 LB | | |
| 0083 | 8280000000-E | 440 | APPROX LBS STRUCTURAL STEEL | 158,600 LS | | |
| 0084 | 8364000000-E | 450 | HP12X53 STEEL PILES | 700 LF | | |
| 0085 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 270 LF | | |
| 0086 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 401 TON | | |
| 0087 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 446 SY | | |
| 0088 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

Contract No **C202124**

County (ies): **Warren**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General