

PLANTING

SEASONAL LIMITATIONS

The initial planting and replacement of plants shall be done from October 15 thru March 31.

MULCH FOR PLANTING

Mulch for Planting shall be in accordance with Section 1670 of the *Standard Specifications*. Mulch for Planting shall consist of triple shredded hard wood.

BRICK BANDING / EDGING:

(6-21-09)

SPI

General

The work covered by this provision shall consist of furnishing and installing the Brick Banding / Edging as indicated on the plans and details and described herein.

Materials

Brick pavers shall be solid brick conforming to ASTM C-902. Brick pavers shall be Burgundy or Boston Red.

Concrete Paver Base shall be constructed in accordance with Section 825 of the *Standard Specifications*.

Construction Methods

Brick pavers shall be laid in or on preformed channels or ledges within the Concrete Paver Base on full mortar beds and have all joints filled with mortar, as shown on the plans.

Measurement and Payment

Brick Pavers shall be measured and paid for at the contract unit price bid per square foot.

Concrete Paver Base shall be measured and paid for at the contract unit price bid per square yard.

Payment will be made under:

Pay Item	Pay Unit
Brick Paver	Square Foot
Concrete Paver Base	Square Yard