

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,000 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	500 TON		
0008	0106000000-E	230	BORROW EXCAVATION	11,200 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	400 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0012	0241000000-E	SP	GENERIC GRADING ITEM ADDITIONAL FINE GRADING	2,000 SY		
0013	0245000000-E	SP	GENERIC GRADING ITEM CONTAMINATED WATER DISPOSAL	5,000 GAL		
0014	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, & DISPOSAL OF CONTAMINATED SOIL	500 TON		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,250 TON		
0016	0343000000-E	310	15" SIDE DRAIN PIPE	300 LF		
0017	0344000000-E	310	18" SIDE DRAIN PIPE	168 LF		
0018	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	104 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,696	LF	
0020	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,052	LF	
0021	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,316	LF	
0022	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,004	LF	
0023	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	792	LF	
0024	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	156	LF	
0025	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	208	LF	
0026	0660000000-E	310	***"BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (24", 0.064")	12	LF	
0027	0986000000-E	SP	GENERIC PIPE ITEM 15" SEALED DRAINAGE SYSTEM PIPE	232	LF	
0028	0986000000-E	SP	GENERIC PIPE ITEM 18" SEALED DRAINAGE SYSTEM PIPE	80	LF	
0029	0995000000-E	340	PIPE REMOVAL	4,973	LF	
0030	0996000000-N	350	PIPE CLEAN-OUT	35	EA	
0031	1110000000-E	510	STABILIZER AGGREGATE	1,000	TON	
0032	1220000000-E	545	INCIDENTAL STONE BASE	2,500	TON	
0033	1330000000-E	607	INCIDENTAL MILLING	3,000	SY	
0034	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	8,050	TON	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	14,000	TON	
003E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,700	TON	
0037	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,720	TON	
003E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	2,230	TON	
003E	2022000000-E	815	SUBDRAIN EXCAVATION	112	CY	
004C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84	CY	
0041	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500	LF	
0042	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15	EA	
0043	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0044	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
004E	2253000000-E	840	PIPE COLLARS	2	CY	
004E	2264000000-E	840	PIPE PLUGS	2	CY	
0047	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	110	EA	
004E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	22	LF	
004E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	37	EA	
005C	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	5	EA	
0051	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	16	EA	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	19 EA		
0053	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	17 EA		
0054	2396000000-N	840	FRAME WITH COVER, STD 840.54	13 EA		
005E	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	6 EA		
005E	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	2 EA		
0057	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	13 EA		
005E	2473000000-N	SP	GENERIC DRAINAGE ITEM CURB CUT WITH FLUME	23 EA		
005E	2473000000-N	SP	GENERIC DRAINAGE ITEM SEALED DRAINAGE SYSTEM STRUCT- URE	3 EA		
006C	2473000000-N	SP	GENERIC DRAINAGE ITEM TRAFFIC BEARING 30" STEEL PLATE FOR CURB CUTS	23 EA		
0061	2535000000-E	846	***X *** CONCRETE CURB (8" X 6")	2,850 LF		
0062	2538000000-E	846	***.*** CONCRETE CURB & GUTTER (2'-9")	1,940 LF		
0063	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	9,850 LF		
0064	2591000000-E	848	4" CONCRETE SIDEWALK	4,520 SY		
006E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	53 EA		
006E	2612000000-E	848	6" CONCRETE DRIVEWAY	410 SY		
0067	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,535 SY		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	2815000000-N	858	ADJUSTMENT OF DROP INLETS	5 EA		
006E	2830000000-N	858	ADJUSTMENT OF MANHOLES	15 EA		
007C	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	40 EA		
0071	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
0072	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	4 EA		
0073	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0074	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
007E	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	4 EA		
007E	3420000000-E	SP	GENERIC GUARDRAIL ITEM REMOVE EXISTING CABLE GUIDERAIL	400 LF		
0077	3574000000-E	867	GENERIC FENCING ITEM SPLIT RAIL FENCE RESET	25 LF		
007E	3628000000-E	876	RIP RAP, CLASS I	25 TON		
007E	3649000000-E	876	RIP RAP, CLASS B	50 TON		
008C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,180 SY		
0081	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,787 LF		
0082	4096000000-N	904	SIGN ERECTION, TYPE D	10 EA		
0083	4102000000-N	904	SIGN ERECTION, TYPE E	72 EA		
0084	4108000000-N	904	SIGN ERECTION, TYPE F	11 EA		
008E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	51 EA		
0087	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2 EA		
008E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	416 SF		
008E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	462 SF		
009C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	50 SF		
0091	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0092	4430000000-N	1130	DRUMS	240 EA		
0093	4435000000-N	1135	CONES	50 EA		
0094	4445000000-E	1145	BARRICADES (TYPE III)	168 LF		
009E	4455000000-N	1150	FLAGGER	480 MD		
009E	4480000000-N	1165	TMIA	2 EA		
0097	4516000000-N	1180	SKINNY DRUM	100 EA		
009E	4605000000-N	SP	GENERIC TRAFFIC CONTROL ITEM POLICE	80 HR		
009E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	563 EA		
010C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	12,318 LF		
0101	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	19,684 LF		
0102	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,506 LF		
0103	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	2,104 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,284	LF	
010E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4	EA	
010E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	141	EA	
0107	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	63,948	LF	
010E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,580	LF	
010E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,464	LF	
011C	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	8	EA	
0111	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	176	EA	
0112	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,000	LF	
011E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	656	EA	
0114	4915000000-E	1264	7' U-CHANNEL POSTS	3	EA	
011E	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	5	EA	
011E	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	5	EA	
0117	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	5	EA	
011E	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3	EA	
011E	5000000000-E	1401	***' HIGH MOUNT STANDARD (60')	2	EA	
012C	5015000000-E	1401	120' HIGH MOUNT STANDARD	2	EA	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	5020000000-N	1401	PORTABLE DRIVE UNIT	1	EA	
0122	5025000000-E	1402	HIGH MOUNT FOUNDATIONS	24	CY	
0123	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (400W HPS)	8	EA	
0124	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	12	EA	
0125	5045000000-N	1404	LIGHT STANDARD, TYPE MTLs ***** (35' SA 8' BREAKAWAY BASE)	2	EA	
0126	5070000000-N	1405	STANDARD FOUNDATION ***** (TYPE R1)	2	EA	
0127	5080000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE ***** (250W HPS)	2	EA	
0128	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	1	EA	
0129	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/0 USE)	80	LF	
0130	5130000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE ***** (RWY 240/480 VOLT)	1	EA	
0131	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	290	LF	
0132	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	80	LF	
0133	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	215	LF	
0134	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	680	LF	



County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
013E	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	3,230	LF	
013E	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	12	EA	
0137	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC30)	1	EA	
013E	5325200000-E	1510	2" WATER LINE	128	LF	
013E	5325600000-E	1510	6" WATER LINE	136	LF	
014C	5325800000-E	1510	8" WATER LINE	554	LF	
0141	5648000000-N	1515	RELOCATE WATER METER	28	EA	
0142	5672000000-N	1515	RELOCATE FIRE HYDRANT	11	EA	
014E	5691300000-E	1520	8" SANITARY GRAVITY SEWER	444	LF	
0144	5775000000-E	1525	4' DIA UTILITY MANHOLE	3	EA	
014E	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	8	LF	
014E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	363	LF	
0147	5816000000-N	1530	ABANDON UTILITY MANHOLE	1	EA	
014E	5828000000-N	1530	REMOVE UTILITY MANHOLE	1	EA	
014E	6000000000-E	1605	TEMPORARY SILT FENCE	3,600	LF	
015C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	840	TON	
0151	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	580	TON	
0152	6012000000-E	1610	SEDIMENT CONTROL STONE	840	TON	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0153	6015000000-E	1615	TEMPORARY MULCHING	21.5	ACR	
0154	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	600	LB	
0155	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3.25	TON	
0156	6024000000-E	1622	TEMPORARY SLOPE DRAINS	135	LF	
0157	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0158	6030000000-E	1630	SILT EXCAVATION	1,305	CY	
0159	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500	SY	
0160	6037000000-E	SP	COIR FIBER MAT	10	SY	
0161	6042000000-E	1632	1/4" HARDWARE CLOTH	1,550	LF	
0162	6071030000-E	SP	COIR FIBER BAFFLES	400	LF	
0163	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
0164	6084000000-E	1660	SEEDING & MULCHING	25	ACR	
0165	6087000000-E	1660	MOWING	10	ACR	
0166	6090000000-E	1661	SEED FOR REPAIR SEEDING	200	LB	
0167	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0168	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	400	LB	
0169	6108000000-E	1665	FERTILIZER TOPDRESSING	12	TON	
0170	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0171	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0172	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1)	24 EA		
0173	7060000000-E	1705	SIGNAL CABLE	13,090 LF		
0174	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	72 EA		
0175	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	10 EA		
0176	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	6 EA		
0177	7264000000-E	1710	MESSENGER CABLE (3/8")	1,520 LF		
0178	7279000000-E	1715	TRACER WIRE	865 LF		
0179	7300000000-E	1715	UNPAVED TRENCHING (***** (2, 2")	1,694 LF		
0180	7301000000-E	1715	DIRECTIONAL DRILL (***** (3, 2")	1,712 LF		
0181	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	28 EA		
0182	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	26 EA		
0183	7360000000-N	1720	WOOD POLE	12 EA		
0184	7372000000-N	1721	GUY ASSEMBLY	28 EA		
0185	7408000000-E	1722	1" RISER WITH WEATHERHEAD	3 EA		
0186	7420000000-E	1722	2" RISER WITH WEATHERHEAD	6 EA		
0187	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	2 EA		
0188	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,365 LF		
0189	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	17,635 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
019C	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	11 EA		
0191	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	5 EA		
0192	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	1,225 LF		
0193	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	10 EA		
0194	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	4 EA		
019E	7613000000-N	SP	SOIL TEST	14 EA		
0196	7614100000-E	SP	DRILLED PIER FOUNDATION	106 CY		
0197	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	5 EA		
019E	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	14 EA		
0199	7636000000-N	1745	SIGN FOR SIGNALS	15 EA		
020C	7684000000-N	1750	SIGNAL CABINET FOUNDATION	4 EA		
0201	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	4 EA		
0202	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	37 EA		
0203	7901000000-N	1753	CABINET BASE EXTENDER	4 EA		
0204	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO LIGHTNING ARRESTOR)	1 EA		
020E	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1 EA		

**Contract No**     **C201447**

**County (ies):**   **Brunswick**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General