

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	2,300 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	4,719 TON		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	6,900 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	300 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	668 LF		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	616 LF		
0011	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,092 LF		
0012	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	252 LF		
0013	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	84 LF		
0014	0536000000-E	SP	*** HDPE PIPE CULVERTS (36")	60 LF		
0015	0974000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, (UNDER RR) (42", 0.625")	60 LF		
0016	0995000000-E	340	PIPE REMOVAL	708 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (6")	11,885	SY	
001S	1330000000-E	607	INCIDENTAL MILLING	3,015	SY	
002C	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,580	TON	
0021	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,220	TON	
0022	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,150	TON	
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	130	TON	
0024	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	222	TON	
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200	TON	
002E	2275000000-E	SP	FLOWABLE FILL	41	CY	
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	42	EA	
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1	EA	
003C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	15	EA	
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	13	EA	
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	12	EA	
0033	2495000000-E	SP	GENERIC DRAINAGE ITEM GROUT	6	CY	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	1,520 LF		
003E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	4,100 LF		
003E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	22 EA		
0037	2612000000-E	848	6" CONCRETE DRIVEWAY	480 SY		
003E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	6 EA		
003E	2830000000-N	858	ADJUSTMENT OF MANHOLES	23 EA		
004C	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	70 EA		
0041	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	2 EA		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,377 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	87 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	503 SF		
004E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
004E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0047	4430000000-N	1130	DRUMS	210 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	590 LF		
004E	4507000000-E	SP	WATER FILLED BARRIER	100 LF		
005C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	575 LF		
0051	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6,255 LF		
0052	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	260 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	765 LF		
0054	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	264 LF		
0055	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	331 LF		
0056	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	36 EA		
0057	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	38 EA		
0058	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,698 LF		
0059	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	40 LF		
0060	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	120 LF		
0061	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16 EA		
0062	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	147 EA		
0063	6000000000-E	1605	TEMPORARY SILT FENCE	100 LF		
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	20 TON		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0066	7036000000-E	1705	PEDESTRIAN SIGNAL HEAD (12", 1 SECTION)	8 EA		
0067	7060000000-E	1705	SIGNAL CABLE	1,630 LF		
0068	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	7 EA		
0069	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	4 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	1		EA
0071	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	640		LF
0072	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	90		LF
0073	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	8		EA
0074	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,400		LF
0075	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	1,300		LF
0076	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	4		EA
0077	7613000000-N	SP	SOIL TEST	4		EA
0078	7614100000-E	SP	DRILLED PIER FOUNDATION	36		CY
0079	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	4		EA
008C	7636000000-N	1745	SIGN FOR SIGNALS	1		EA
0081	7648000000-N	SP	RELOCATE EXISTING SIGN	5		EA
0082	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1		EA
0083	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1		EA
0084	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	8		EA
0085	7901000000-N	1753	CABINET BASE EXTENDER	1		EA
0086	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	4		EA
0087	7972000000-N	SP	METAL POLE REMOVAL	4		EA

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	7990000000-E	SP	GENERIC SIGNAL ITEM RIGID METAL CONDUIT (2 CON- DUIT, 2")	170 LF		
008E	7990000000-E	SP	GENERIC SIGNAL ITEM RIGID METAL CONDUIT (3 CON- DUIT, 2")	120 LF		
1429/Jun02/Q71709.0/D355297600000/E89			Total Amount Of Bid For Entire Project :			

Contract No **C202119**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General