

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	50,000 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+89.07)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+90.21)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	1,725 CY		
0009	0106000000-E	230	BORROW EXCAVATION	230,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	725 CY		
0011	0141000000-E	240	BERM DITCH CONSTRUCTION	850 LF		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	3,230 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	2,075 SY		
0014	0192000000-N	260	PROOF ROLLING	9 HR		
0015	0195000000-E	265	SELECT GRANULAR MATERIAL	650 CY		
0016	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	650 SY		
0017	0199000000-E	SP	TEMPORARY SHORING	1,428 SF		
0018	0223000000-E	SP	ROCK PLATING	100 SY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0234000000-E	SP	GENERIC GRADING ITEM EXCAVATION & STOCKPILING OF CONTAMINATED SOIL	50	CY	
0020	0312000000-E	300	SELECT MATERIAL, CLASS IV	9,270	TON	
0021	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	670	TON	
0022	0343000000-E	310	15" SIDE DRAIN PIPE	24	LF	
0023	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	160	LF	
0024	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	36	LF	
0025	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (60")	380	LF	
0026	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	324	LF	
0027	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	48	LF	
0028	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4	EA	
0029	0809000000-E	310	30" BIT COAT CS PIPE ELBOWS, T YPE B 0.079" THICK	2	EA	
0030	0938000000-E	320	*** X *** CS STRUCTURAL PLATE PIPE ARCH, ** GAUGE (190" X 118", 7)	30	LF	
0031	0986000000-E	SP	GENERIC PIPE ITEM 15" DUCTILE IRON PIPE	636	LF	
0032	0986000000-E	SP	GENERIC PIPE ITEM 24" DUCTILE IRON PIPE	248	LF	
0033	0986000000-E	SP	GENERIC PIPE ITEM 30" DUCTILE IRON PIPE	124	LF	
0034	0995000000-E	340	PIPE REMOVAL	621	LF	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1000000000-E	462	6" SLOPE PROTECTION	90 SY		
003E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0037	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	21,850 SY		
003E	1066000000-E	501	LIME FOR LIME TREATED SOIL	220 TON		
003E	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
004C	1176000000-E	542	SOIL CEMENT BASE	14,570 SY		
0041	1187000000-E	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	401 TON		
0042	1209000000-E	543	ASPHALT CURING SEAL	5,470 GAL		
004E	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0044	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	19,520 SY		
004E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	8,650 TON		
004E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,500 TON		
0047	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	9,700 TON		
004E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	575 TON		
004E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	8,400 TON		
005C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,300 TON		
0051	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,425 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	80 TON		
0053	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		
0054	2022000000-E	815	SUBDRAIN EXCAVATION	168 CY		
005E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
005E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0057	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
005E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
005E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
006C	2143000000-E	818	BLOTTING SAND	15 TON		
0061	2209000000-E	838	ENDWALLS	6 CY		
0062	2220000000-E	838	REINFORCED ENDWALLS	4 CY		
0063	2253000000-E	840	PIPE COLLARS	3 CY		
0064	2264000000-E	840	PIPE PLUGS	0.3 CY		
006E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	106 EA		
006E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	88 LF		
0067	2354000000-N	840	FRAME WITH GRATE, STD 840.22	1 EA		
006E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	17 EA		
006E	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	8 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5 EA		
0071	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	26 EA		
0072	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	33 EA		
0073	2396000000-N	840	FRAME WITH COVER, STD 840.54	17 EA		
0074	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	13 EA		
007E	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	17 EA		
007E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	5,900 LF		
0077	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	14,990 LF		
007E	2591000000-E	848	4" CONCRETE SIDEWALK	8,030 SY		
007E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	35 EA		
008C	2612000000-E	848	6" CONCRETE DRIVEWAY	160 SY		
0081	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,280 SY		
0082	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	2 EA		
0083	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	275 LF		
0084	2830000000-N	858	ADJUSTMENT OF MANHOLES	16 EA		
008E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	15 EA		
008E	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
008E	3030000000-E	862	STEEL BM GUARDRAIL	3,162.5 LF		
008E	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	4 EA		
009C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0091	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0092	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0093	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0094	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	6 EA		
009E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	125 LF		
009E	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	11,225 LF		
0097	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	940 EA		
009E	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	57 EA		
009E	3557000000-E	866	ADDITIONAL BARBED WIRE	1,000 LF		
010C	3628000000-E	876	RIP RAP, CLASS I	313 TON		
0101	3635000000-E	876	RIP RAP, CLASS II	3 TON		
0102	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0103	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,489 SY		
0104	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	4 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	565 LF		
010E	4102000000-N	904	SIGN ERECTION, TYPE E	35 EA		
0107	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
010E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
010E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	18 EA		
011C	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	2 EA		
0111	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,534 SF		
0112	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	639 SF		
0113	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	538 SF		
0114	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	7 EA		
011E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
011E	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	99 DAY		
0117	4430000000-N	1130	DRUMS	660 EA		
011E	4445000000-E	1145	BARRICADES (TYPE III)	352 LF		
011E	4450000000-N	1150	FLAGGER	1,200 HR		
012C	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0121	4480000000-N	1165	TMIA	2 EA		
0122	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,996 LF		
0123	4507000000-E	SP	WATER FILLED BARRIER	1,064 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	814	EA	
0125	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	15,517	LF	
0126	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	740	LF	
0127	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	2,620	LF	
0128	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	740	LF	
0129	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8	EA	
0130	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	118	EA	
0131	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	113	LF	
0132	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	4,465	LF	
0133	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	53,715	LF	
0134	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	344	LF	
0135	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	314	LF	
0136	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	14	EA	
0137	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,063	LF	
0138	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	6	EA	



County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0139	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	253 EA		
0140	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0141	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
0142	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (1000W HPS)	6 EA		
0143	5070000000-N	1405	STANDARD FOUNDATION ***** (TYPE M1)	1 EA		
0144	5090000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE RDW 400W HPS	8 EA		
0145	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	100 LF		
0146	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	50 LF		
0147	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	150 LF		
0148	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	550 LF		
0149	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	150 LF		
0150	5190000000-E	1410	***** FEEDER CIRCUIT (2 #1 W/G)	150 LF		
0151	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	100 LF		
0152	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	250 LF		
0153	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	100 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0154	5225000000-E	1410	** #1 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	100 LF		
015E	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	3 EA		
015E	5270000000-N	SP	GENERIC LIGHTING ITEM 1000W LAMP HPS	2 EA		
0157	5270000000-N	SP	GENERIC LIGHTING ITEM 400W LAMP HPS	10 EA		
015E	5270000000-N	SP	GENERIC LIGHTING ITEM RELOCATE LIGHT STANDARD	1 EA		
015E	5271000000-N	SP	GENERIC LIGHTING ITEM FAULT TROUBLESHOOT & LOCATE	16 HR		
016C	5326200000-E	1510	12" WATER LINE	146 LF		
0161	5648000000-N	1515	RELOCATE WATER METER	8 EA		
0162	5653100000-E	1515	RELOCATE *** DCV BACK-FLOW PREVENTOR (2")	1 EA		
016E	5672000000-N	1515	RELOCATE FIRE HYDRANT	5 EA		
0164	5691300000-E	1520	8" SANITARY GRAVITY SEWER	40 LF		
016E	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	5 EA		
016E	5815000000-N	1530	REMOVE WATER METER	6 EA		
0167	5815500000-N	1530	REMOVE FIRE HYDRANT	2 EA		
016E	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE SANITARY SEWER C/O	5 EA		
016E	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE VALVE	3 EA		
017C	6000000000-E	1605	TEMPORARY SILT FENCE	12,000 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0171	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,375 TON		
0172	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,325 TON		
0173	6012000000-E	1610	SEDIMENT CONTROL STONE	2,150 TON		
0174	6015000000-E	1615	TEMPORARY MULCHING	34 ACR		
0175	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	650 LB		
0176	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.5 TON		
0177	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,750 LF		
0178	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	22 EA		
0179	6029000000-E	SP	SAFETY FENCE	2,400 LF		
0180	6030000000-E	1630	SILT EXCAVATION	9,100 CY		
0181	6036000000-E	1631	MATTING FOR EROSION CONTROL	12,000 SY		
0182	6037000000-E	SP	COIR FIBER MAT	137 SY		
0183	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,100 SY		
0184	6042000000-E	1632	1/4" HARDWARE CLOTH	6,175 LF		
0185	6071010000-E	SP	WATTLE	50 LF		
0186	6071020000-E	SP	POLYACRYLAMIDE (PAM)	24 LB		
0187	6071030000-E	SP	COIR FIBER BAFFLES	3,025 LF		
0188	6071050000-E	SP	*** SKIMMER (1-1/2")	6 EA		
0189	6084000000-E	1660	SEEDING & MULCHING	35 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
019C	6087000000-E	1660	MOWING	39	ACR	
0191	6090000000-E	1661	SEED FOR REPAIR SEEDING	250	LB	
0192	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25	TON	
0193	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	800	LB	
0194	6108000000-E	1665	FERTILIZER TOPDRESSING	23.5	TON	
019E	6114000000-N	SP	SPECIALIZED HAND MOWING	13	HR	
0196	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36	EA	
0197	6123000000-E	1670	REFORESTATION	0.25	ACR	
019E	6133000000-N	SP	GENERIC EROSION CONTROL ITEM ENERGY DISSIPATOR BASIN	Lump Sum	L.S.	
019E	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION WITH COUNT- DOWN)	28	EA	
020C	7060000000-E	1705	SIGNAL CABLE	9,220	LF	
0201	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	39	EA	
0202	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	1	EA	
0203	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	11	EA	
0204	7252000000-E	1710	MESSENGER CABLE (1/4")	2,800	LF	
020E	7264000000-E	1710	MESSENGER CABLE (3/8")	2,440	LF	
020E	7279000000-E	1715	TRACER WIRE	2,965	LF	
0207	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	3,060	LF	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
020E	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	815 LF		
020E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	17 EA		
021C	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	11 EA		
0211	7360000000-N	1720	WOOD POLE	16 EA		
0212	7372000000-N	1721	GUY ASSEMBLY	37 EA		
0213	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	10 EA		
0214	7408000000-E	1722	1" RISER WITH WEATHERHEAD	4 EA		
021E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	15 EA		
021E	7430000000-N	1722	HEAT SHRINK TUBING RETROFIT KIT	1 EA		
0217	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	4 EA		
021E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	6,680 LF		
021E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	8,870 LF		
022C	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	9,540 LF		
0221	7528000000-E	1730	DROP CABLE	800 LF		
0222	7540000000-N	1731	SPLICE ENCLOSURE	5 EA		
0223	7552000000-N	1731	INTERCONNECT CENTER	4 EA		
0224	7566000000-N	1733	DELINEATOR MARKER	9 EA		
022E	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	1,500 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0226	7575180000-N	1735	CABLE TRANSFER	1		
				EA		
0227	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	1		
				EA		
022E	7636000000-N	1745	SIGN FOR SIGNALS	5		
				EA		
0229	7684000000-N	1750	SIGNAL CABINET FOUNDATION	4		
				EA		
023C	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	4		
				EA		
0231	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	28		
				EA		
0232	7901000000-N	1753	CABINET BASE EXTENDER	4		
				EA		
0233	7980000000-N	SP	GENERIC SIGNAL ITEM FIELD ETHERNET SWITCH	4		
				EA		
0234	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH FIELD ETHERNET SWITCH	1		
				EA		
<p>***** BEGIN SCHEDULE AA *****                      ***** ( 3 ALTERNATES ) *****</p>						
023E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,340		
AA1				LF		
0236	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	612		
AA1				LF		
0237	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	804		
AA1				LF		
023E	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	424		
AA1				LF		
0239	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	148		
AA1				LF		
<p>*** OR ***</p>						
024C	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,300		
AA2				LF		
0241	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	512		
AA2				LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0242 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	772	LF	
0243 AA2	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	276	LF	
0244 AA2	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	108	LF	
0245 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	40	LF	
0246 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	100	LF	
0247 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	32	LF	
0248 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	148	LF	
0249 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (42")	40	LF	
*** OR ***						
0250 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,300	LF	
0251 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	512	LF	
0252 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	772	LF	
0253 AA3	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	276	LF	
0254 AA3	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	108	LF	
0255 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	40	LF	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0256 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	100 LF		
0257 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	32 LF		
0258 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (36", 0.079")	148 LF		
0259 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (42", 0.079")	40 LF		

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

**WALL ITEMS**

0260	8801000000-E	SP	MSE RETAINING WALLS (16 + 75.00-L-)	6,900 SF		
0261	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS (16 + 75.00-Y4-)	350 SF		

**STRUCTURE ITEMS**

0262	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,20 + 90.21-L-LTLN)	Lump Sum	L.S.	
0263	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,20 + 90.21-L-RTLN)	Lump Sum	L.S.	
0264	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	15,322 SF		
0265	8161000000-E	420	GROOVING BRIDGE FLOORS	13,274 SF		
0266	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	237.9 CY		



County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0267	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+90.21-L-LTLN)	Lump Sum	L.S.	
026E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+90.21-L-RTLN)	Lump Sum	L.S.	
026E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,120 LB		
027C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,558 LB		
0271	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	1,977.97 LF		
0272	8364000000-E	450	HP12X53 STEEL PILES	3,260 LF		
0273	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	1,375 LF		
0274	8482000000-E	460	THREE BAR METAL RAIL	383.74 LF		
027E	8503000000-E	460	CONCRETE BARRIER RAIL	398.83 LF		
027E	8531000000-E	462	4" SLOPE PROTECTION	526 SY		
0277	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
027E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0934/Jul13/Q747629.74/D1111009180000/E278

Total Amount Of Bid For Entire Project :

**Contract No**      **C202163**

**County (ies):**    **Guilford**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General