

County : Buncombe, Madison

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0003 | 1297000000-E | 607 | MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2") | 800 SY | | |
| 0004 | 1491000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0C | 4,200 TON | | |
| 000E | 1503000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C | 1,900 TON | | |
| 0006 | 1523000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5C | 1,150 TON | | |
| 0007 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 310 TON | | |
| 000E | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 291 TON | | |
| 0009 | 1565000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22 | 70 TON | | |
| 001C | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 975 SF | | |
| 0011 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 700 SF | | |
| 0012 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 20 SF | | |
| 0013 | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 5 EA | | |
| 0014 | 4420000000-N | 1120 | CHANGEABLE MESSAGE SIGN | 8 EA | | |
| 001E | 4422000000-N | 1120 | CHANGEABLE MESSAGE SIGN (SHORT TERM) | 4 DAY | | |
| 001E | 4430000000-N | 1130 | DRUMS | 1,000 EA | | |
| 0017 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 40 LF | | |

County : Buncombe, Madison

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|---------------|-----------|--------|
| 001E | 4465000000-N | 1160 | TEMPORARY CRASH CUSHIONS | 3 EA | | |
| 001E | 4470000000-N | 1160 | RESET TEMPORARY CRASH CUSHIONS | 7 EA | | |
| 002C | 4480000000-N | 1165 | TMIA | 2 EA | | |
| 0021 | 4485000000-E | 1170 | PORTABLE CONCRETE BARRIER | 2,500 LF | | |
| 0022 | 4500000000-E | 1170 | RESET PORTABLE CONCRETE BARRIER | 6,100 LF | | |
| 002E | 4510000000-N | SP | LAW ENFORCEMENT | 40 HR | | |
| 0024 | 4516000000-N | 1180 | SKINNY DRUM | 50 EA | | |
| 002E | 4770000000-E | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV) | 54,000 LF | | |
| 002E | 4847000000-E | 1205 | POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS) | 49,000 LF | | |
| 0027 | 4850000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (4") | 2,000 LF | | |
| 002E | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 15,760 LF | | |
| 002E | 6084000000-E | 1660 | SEEDING & MULCHING | 1 ACR | | |
| 003C | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 61,340 SF | | |
| 0031 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |
| 0032 | 8881000000-E | SP | GENERIC STRUCTURE ITEM LATEX MODIFIED CONC OVERLAY VERY EARLY STRENGTH | 727 CY | | |
| 003E | 8892000000-E | SP | GENERIC STRUCTURE ITEM CLASS II CONC DECK REPAIR FOR EPOXY/ASPHALT OVERLAY | 900 SF | | |
| 0034 | 8892000000-E | SP | GENERIC STRUCTURE ITEM PLACEMENT OF EPOXY OVERLAY | 267,351 SF | | |

County : Buncombe, Madison

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--|--------------|-------|---|-------------|-----------|--------|
| 003E | 8893000000-E | SP | GENERIC STRUCTURE ITEM CLASS IA SURFACE PREPARATION | 633 SY | | |
| 003E | 8893000000-E | SP | GENERIC STRUCTURE ITEM CLASS IB SURFACE PREPARATION | 2,960 SY | | |
| 0037 | 8893000000-E | SP | GENERIC STRUCTURE ITEM HYDRODEMOLITION OF BRIDGE DECK | 7,345 SY | | |
| 003E | 8893000000-E | SP | GENERIC STRUCTURE ITEM PLACING AND FINISHING OF LATEX MODIFIED CONCRETE - VERY EARLY STR | 7,345 SY | | |
| 003E | 8893000000-E | SP | GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK | 8,190 SY | | |
| 1152/Aug07/Q497730.0/D191814100000/E39 | | | Total Amount Of Bid For Entire Project : | | | |

Contract No **C202311**

Counties: **Buncombe and Madison**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General