

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	209	TON	
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	17.42	SMI	
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	36,435	SY	
0005	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,101	TON	
0006	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	8,966	TON	
0007	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	11,490	TON	
0008	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,477	TON	
0009	1704000000-E	SP	PATCHING EXISTING PAVEMENT	372	TON	
001C	2830000000-N	858	ADJUSTMENT OF MANHOLES	38	EA	
0011	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	22	EA	
0012	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	49,445	LF	
0013	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,400	LF	
0014	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	300	LF	
001E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	100	LF	
0016	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	855	LF	
0017	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	32	EA	

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	209	EA	
001S	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	388,585	LF	
002C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,700	LF	
0021	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	725	LF	
0022	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	12	EA	
0023	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	800	EA	
0024	6084000000-E	1660	SEEDING & MULCHING	21.12	ACR	
002E	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	45	LF	
002E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	200	LF	
0027	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	5	EA	
002E	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	2	EA	
002S	7420000000-E	1722	2" RISER WITH WEATHERHEAD	6	EA	
003C	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,000	LF	
0031	7456000000-E	1726	LEAD-IN CABLE (*****) (18-4)	30,000	LF	
0032	7990000000-E	SP	GENERIC SIGNAL ITEM 1" PVC CONDUIT	30	LF	
0033	7990000000-E	SP	GENERIC SIGNAL ITEM 2" PVC CONDUIT	150	LF	

Contract No **C202423**

County (ies): **Cumberland & Harnett**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General