

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0008	1121000000-E	520	AGGREGATE BASE COURSE	216 TON		
0009	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0010	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0011	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0012	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0013	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0014	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0015	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0016	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED ADDITIONAL GUARDRAIL POSTS	5 EA		
0017	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GR ANCHOR UNIT, TYPE III SHOP CURVE	1 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GR ANCHOR UNIT, TYPE 350	2 EA		
001E	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GR ANCHOR UNIT, TYPE III	2 EA		
002C	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GR ANCHOR UNIT,TYPE AT-1	1 EA		
0021	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	600 SY		
0022	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	98 SF		
0023	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	89 SF		
0024	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
002E	6000000000-E	1605	TEMPORARY SILT FENCE	400 LF		
002E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250 TON		
0027	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50 TON		
002E	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
002E	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
003C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0031	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0032	6029000000-E	SP	SAFETY FENCE	325 LF		
0033	6030000000-E	1630	SILT EXCAVATION	70 CY		
0034	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
003E	6042000000-E	1632	1/4" HARDWARE CLOTH	115 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6070000000-N	SP	SPECIAL STILLING BASINS	2	EA	
0037	6071010000-E	SP	WATTLE	15	LF	
0038	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5	LB	
0039	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0040	6087000000-E	1660	MOWING	0.5	ACR	
0041	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0042	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0043	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0044	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	
0045	6111000000-E	SP	IMPERVIOUS DIKE	125	LF	
0046	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0047	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

CULVERT ITEMS

0048	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (10 + 45.40-L-)	Lump Sum	L.S.	
0049	8196000000-E	420	CLASS A CONCRETE (CULVERT)	31	CY	
0050	8590000000-E	876	RIP RAP, CLASS ** (I)	32	TON	
0051	8804000000-N	SP	GENERIC CULVERT ITEM PRECAST REINF CONC THREE-SIDED CULVERT AT STA 10 + 45.40 -L-	Lump Sum	L.S.	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	8821000000-E	SP	GENERIC CULVERT ITEM ARCHITECTURAL CONCRETE SURFACE TREATMENT	1,250	SF	

0835/Aug03/Q5271.45/D231121130000/E52

Total Amount Of Bid For Entire Project :

Contract No **C202170**

County (ies): **Henderson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General