

FLAGGERS

DESCRIPTION

Furnish, relocate, and maintain the flaggers, hats, vests and STOP/SLOW Paddles and any other incidentals necessary to complete the work in accordance with the contract.

MATERIALS

Refer to Division 10:

Item	Section
Flaggers	1089-12

CONSTRUCTION METHODS

Provide the services of competent and properly equipped flagger(s) (see Roadway Standard Drawing No. 1150.01) at locations and times for such periods as necessary for the control and protection of vehicular and pedestrian traffic. Use flagging methods that comply with the guidelines in the MUTCD. Flagging operations are not allowed for the convenience of the Contractor's operations. However, if safety issues exist (i.e. sight/stopping site distance), the Engineer may approve the use of flagging operations.

MEASUREMENT AND PAYMENT

Flaggers and everything associated with flagging operations will be paid for at the contract lump sum price. Payment for Flaggers will be made on the following schedule:

- 40% of the unit bid upon the first use of flagging on the project.
- 30% of the unit bid when the project is 50% complete.
- 30% of the unit bid when the project is 100% complete.

