

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	65,000 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	50 TON		
0008	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	358 LF		
0009	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	32 LF		
0010	0732000000-E	310	36" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	72 LF		
0011	0809000000-E	310	30" BIT COAT CS PIPE ELBOWS, T YPE B 0.079" THICK	1 EA		
0012	0995000000-E	340	PIPE REMOVAL	45 LF		
0013	0996000000-N	350	PIPE CLEAN-OUT	2 EA		
0014	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0015	1121000000-E	520	AGGREGATE BASE COURSE	1,598 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	220 TON		
0017	1231000000-E	560	SHOULDER BORROW	1,360 CY		
0018	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,780 TON		
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,510 TON		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,040 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	360 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	90 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	25 EA		
0024	2275000000-E	SP	FLOWABLE FILL	34.3 CY		
0025	3030000000-E	862	STEEL BM GUARDRAIL	675 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0029	3360000000-E	863	REMOVE EXISTING GUARDRAIL	635 LF		
0030	3649000000-E	876	RIP RAP, CLASS B	35 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		
0032	3677000000-E	SP	GENERIC EROSION CONTROL ITEM SLOPE STABILIZATION	2,100 SY		
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
0034	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	170 SF		
0035	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1 EA		
0036	4430000000-N	1130	DRUMS	90 EA		
0037	4435000000-N	1135	CONES	50 EA		
0038	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4480000000-N	1165	TMIA	1 EA		
0040	4485000000-E	1170	PORTABLE CONCRETE BARRIER	910 LF		
0041	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM FLAGGER	Lump Sum	L.S.	
0042	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	161 EA		
0043	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	6,944 LF		
0044	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,410 LF		
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,834 LF		
0046	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	130 EA		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	2,475 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,405 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	385 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	7 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0054	6029000000-E	SP	SAFETY FENCE	100 LF		
0055	6030000000-E	1630	SILT EXCAVATION	2,175 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,875 SY		
0057	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,295 SY		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6084000000-E	1660	SEEDING & MULCHING	18.6	ACR	
0059	6087000000-E	1660	MOWING	6	ACR	
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	225	LB	
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	6.75	TON	
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0065	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

0824/Jul29/Q117526.65/D22793050000/E65

Total Amount Of Bid For Entire Project :

Contract No **C202175**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General