

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+93.50)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+40.25)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0106000000-E	230	BORROW EXCAVATION	12,600 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	50 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	12 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	64 LF		
0014	0660000000-E	310	****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064")	48 LF		
0015	0680000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (15", 0.064")	4 EA		
0016	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,730 TON		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,540 TON		
0019	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	620 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	150 TON		
0021	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	40 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	33 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0031	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	4 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	87 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	2,887.5 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3270000000-N	SP 350	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0037	3635000000-E	876	RIP RAP, CLASS II	10 TON		
0038	3649000000-E	876	RIP RAP, CLASS B	342 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,289 SY		
0040	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	573 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	188 SF		
0043	4445000000-E	1145	BARRICADES (TYPE III)	128 LF		
0044	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,870 LF		
0045	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,870 LF		
0046	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,308 LF		
0047	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	28 EA		
0048	6000000000-E	1605	TEMPORARY SILT FENCE	4,100 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	240 TON		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	360 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	430 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	400 LB		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0055	6024000000-E	1622	TEMPORARY SLOPE DRAINS	300 LF		
0056	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	8 EA		
0057	6029000000-E	SP	SAFETY FENCE	750 LF		
0058	6030000000-E	1630	SILT EXCAVATION	1,020 CY		
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0060	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	100 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	140 LF		
0062	6070000000-N	SP	SPECIAL STILLING BASINS	6 EA		
0063	6071030000-E	SP	COIR FIBER BAFFLES	310 LF		
0064	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0065	6087000000-E	1660	MOWING	6 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	7 TON		
0070	6114000000-N	SP	SPECIALIZED HAND MOWING	10 HR		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24 EA		
0072	6123000000-E	1670	REFORESTATION	0.1 ACR		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0073	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14+93.50-L-)	Lump Sum	L.S.	
0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+93.50-L-)	Lump Sum	L.S.	
0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+40.25-EL-)	Lump Sum	L.S.	
0076	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	143.1 LF		
0077	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	78 LF		
0078	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	150.2 LF		
0079	8115000000-N	SP	CROSSHOLE SONIC LOGGING	3 EA		
0080	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+93.50-L-)	Lump Sum	L.S.	
0081	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+40.25-EL-)	Lump Sum	L.S.	
0082	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,148 SF		
0083	8161000000-E	420	GROOVING BRIDGE FLOORS	10,845 SF		
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	205.6 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+93.50-L-)	Lump Sum	L.S.	
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+40.25-EL-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	44,037 LB		
0088	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,585 LB		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	1,152.75 LF		
0090	8364000000-E	450	HP12X53 STEEL PILES	760 LF		
0091	8503000000-E	460	CONCRETE BARRIER RAIL	589 LF		
0092	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,085 TON		
0093	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,200 SY		
0094	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0095	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0946/Aug17/Q120467.65/D435845870000/E95			Total Amount Of Bid For Entire Project :			

Contract No C202147

County (ies): Person

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General