

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	140 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	12.48 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	173,655 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	315 SY		
0006	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	17,065 TON		
0007	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	13 TON		
0008	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,024 TON		
0009	1661000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1	195 TON		
0010	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	4 EA		
0011	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	8 EA		
0012	2752000000-E	SP	GENERIC PAVING ITEM 2'-6" CONCRETE CURB & GUTTER	740 LF		
0013	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0014	2830000000-N	858	ADJUSTMENT OF MANHOLES	12 EA		
0015	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	7 EA		
0016	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	76,100 LF		
0017	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	49,570 LF		

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	140	LF	
001E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	116	EA	
002C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	103,960	LF	
0021	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,307	EA	
0022	6084000000-E	1660	SEEDING & MULCHING	9.12	ACR	
002E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	11,600	LF	
0905/Sep15/Q435994.6/D69892100000/E23			Total Amount Of Bid For Entire Project :			

Contract No **C202453**

County (ies): **Richmond**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General