

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	12.48	SMI	
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	139,110	SY	
0004	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,724	TON	
0005	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	704	TON	
0006	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	65,894	LF	
0007	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0008	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	74,134	LF	
0009	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	74,134	LF	
0010	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	412	EA	
0011	6084000000-E	1660	SEEDING & MULCHING	7.6	ACR	

0903/Aug28/Q366134.08/D32710200000/E11

Total Amount Of Bid For Entire Project :

Contract No **C202394**

County (ies): **Yadkin**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General