

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0234000000-E	SP	GENERIC GRADING ITEM BORROW EXCAVATION (STATE FURNISHED SOURCES)	15,646 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	770 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	52.2 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	1,479 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	14,544 SY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	116,615 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	2,267 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,708 TON		
0010	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	10,238 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	18,544 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	25,170 TON		
0013	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	27,976 TON		
0014	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	29 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,323 TON		
0016	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,680 TON		

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	119,433	LF	
0018	1880000000-E	SP	GENERIC PAVING ITEM AGGREGATE BASE COURSE, PAVEMENT REPAIR	1,148	TON	
0019	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT PLANT MIX, PAVEMENT REPAIR	918	TON	
0020	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	265	TON	
0021	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	3,725	TON	
0022	2738000000-E	SP	GENERIC PAVING ITEM INCIDENTAL CONCRETE	145	SY	
0023	3030000000-E	862	STEEL BM GUARDRAIL	50	LF	
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0026	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0027	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0028	4480000000-N	1165	TMIA	2	EA	
0029	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	282,032	LF	
0030	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	69,616	LF	
0031	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	150	LF	
0032	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	72	EA	
0033	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	128	EA	

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	351,614 LF		
0035	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	150 LF		
0036	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	100 EA		
0037	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	128 EA		
0038	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,157 EA		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	2,332 LF		
0040	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	673 TON		
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	673 TON		
0042	6015000000-E	1615	TEMPORARY MULCHING	26.89 ACR		
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,320 LB		
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6.73 TON		
0045	6042000000-E	1632	1/4" HARDWARE CLOTH	1,347 LF		
0046	6084000000-E	1660	SEEDING & MULCHING	32.77 ACR		
0047	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,850 LF		
0048	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	550 LF		

0846/Oct15/Q1091699.59/D165827100000/E48

Total Amount Of Bid For Entire Project :

Contract No **C202474**

County (ies): **Duplin/Sampson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General