

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+90.71 LEFT)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (28+01.29 RIGHT)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	3,500 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	4,000 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	450 CY		
0010	0141000000-E	240	BERM DITCH CONSTRUCTION	410 LF		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	6,000 SY		
0013	0199000000-E	SP	TEMPORARY SHORING	950 SF		
0014	0223000000-E	SP	ROCK PLATING	655 SY		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	370 TON		
0016	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	1,160 SY		
0017	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	208 LF		
0018	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	16 LF		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0570000000-E	310	6" CS PIPE CULVERTS, 0.064" THICK (SPRING BOX)	8 LF		
0020	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	684 LF		
0021	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	488 LF		
0022	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0023	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	32 LF		
0024	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	18 EA		
0025	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		
0026	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0027	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0028	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0029	1330000000-E	607	INCIDENTAL MILLING	5,510 SY		
0030	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	560 TON		
0031	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	20,900 TON		
0032	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	400 TON		
0033	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	12,900 TON		
0034	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	405 TON		
0035	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	10,425 TON		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,573 TON		
0037	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	626 TON		
0038	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	115 TON		
0039	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	13,250 LF		
0040	2022000000-E	815	SUBDRAIN EXCAVATION	672 CY		
0041	2033000000-E	815	SUBDRAIN FINE AGGREGATE	336 CY		
0042	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
0043	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60 EA		
0044	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0045	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24 LF		
0046	2253000000-E	840	PIPE COLLARS	5 CY		
0047	2264000000-E	840	PIPE PLUGS	0.2 CY		
0048	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	39 EA		
0049	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	8 LF		
0050	2354000000-N	840	FRAME WITH GRATE, STD 840.22	2 EA		
0051	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	1 EA		
0052	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	27 EA		
0053	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0054	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	11 EA		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2556000000-E	846	SHOULDER BERM GUTTER	2,900 LF		
0056	2619000000-E	850	4" CONCRETE PAVED DITCH	11 SY		
0057	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	6 EA		
0058	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0059	3030000000-E	862	STEEL BM GUARDRAIL	9,675 LF		
0060	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0061	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0062	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0063	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0064	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	2,350 LF		
0065	3360000000-E	863	REMOVE EXISTING GUARDRAIL	9,100 LF		
0066	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	4 EA		
0067	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	4,050 LF		
0068	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	250 EA		
0069	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	90 EA		
0070	3557000000-E	866	ADDITIONAL BARBED WIRE	4,050 LF		
0071	3628000000-E	876	RIP RAP, CLASS I	75 TON		
0072	3649000000-E	876	RIP RAP, CLASS B	20 TON		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,265 SY		
0074	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0075	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 CY		
0076	4057000000-E	SP	OVERHEAD FOOTING	12 CY		
0077	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	218 LB		
0078	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	109 LF		
0079	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (38+50.00)	Lump Sum	L.S.	
0080	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0081	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0082	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	1 EA		
0083	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	3 EA		
0084	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	5 EA		
0085	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400 SF		
0086	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	650 SF		
0087	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	50 SF		
0088	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0089	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0090	4430000000-N	1130	DRUMS	375 EA		
0091	4445000000-E	1145	BARRICADES (TYPE III)	60 LF		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0093	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0094	4480000000-N	1165	TMIA	2 EA		
0095	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	605 LF		
0096	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	2,600 LF		
0097	4506000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER (DRAINAGE)	1,960 LF		
0098	4510000000-N	SP	LAW ENFORCEMENT	100 HR		
0099	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	225 EA		
0100	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	9,000 LF		
0101	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,560 LF		
0102	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	15,772 LF		
0103	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	3,050 LF		
0104	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	350 LF		
0105	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1,280 LF		
0106	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
0107	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	11 EA		
0108	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	2,100 LF		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	1,066 LF		
0110	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (III)	1 EA		
0111	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,400 LF		
0112	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	3 EA		
0113	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,500 LF		
0114	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	206 EA		
0115	5589200000-E	1515	2" AIR RELEASE VALVE	1 EA		
0116	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
0117	5888000000-E	SP	GENERIC UTILITY ITEM PROTECTIVE STEEL PLATING	220 LF		
0118	6000000000-E	1605	TEMPORARY SILT FENCE	14,200 LF		
0119	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,350 TON		
0120	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,925 TON		
0121	6012000000-E	1610	SEDIMENT CONTROL STONE	2,575 TON		
0122	6015000000-E	1615	TEMPORARY MULCHING	33.5 ACR		
0123	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	700 LB		
0124	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	4.5 TON		
0125	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,650 LF		
0126	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	11 EA		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	6029000000-E	SP	SAFETY FENCE	2,900 LF		
0128	6030000000-E	1630	SILT EXCAVATION	9,000 CY		
0129	6036000000-E	1631	MATTING FOR EROSION CONTROL	20,200 SY		
0130	6037000000-E	SP	COIR FIBER MAT	110 SY		
0131	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	4,500 SY		
0132	6042000000-E	1632	1/4" HARDWARE CLOTH	3,100 LF		
0133	6070000000-N	SP	SPECIAL STILLING BASINS	20 EA		
0134	6071010000-E	SP	WATTLE	500 LF		
0135	6071020000-E	SP	POLYACRYLAMIDE (PAM)	125 LB		
0136	6071030000-E	SP	COIR FIBER BAFFLES	7,500 LF		
0137	6071050000-E	SP	*** SKIMMER (1-1/2")	8 EA		
0138	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0139	6084000000-E	1660	SEEDING & MULCHING	25 ACR		
0140	6087000000-E	1660	MOWING	23.5 ACR		
0141	6090000000-E	1661	SEED FOR REPAIR SEEDING	300 LB		
0142	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
0143	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	475 LB		
0144	6108000000-E	1665	FERTILIZER TOPDRESSING	14 TON		
0145	6114500000-N	SP	SPECIALIZED HAND MOWING	200 MHR		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36		EA
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0147	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,192		LF
AA1						
0148	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	284		LF
AA1						
0149	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	488		LF
AA1						
*** OR ***						
0150	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	744		LF
AA2						
0151	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	32		LF
AA2						
0152	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	44		LF
AA2						
0153	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	448		LF
AA2						
0154	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	252		LF
AA2						
0155	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	444		LF
AA2						
*** OR ***						
0156	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	744		LF
AA3						
0157	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	32		LF
AA3						
0158	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	44		LF
AA3						
0159	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	448		LF
AA3						

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0160 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	252 LF		
0161 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.079")	444 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0162	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (27+96.00-L-LT)	Lump Sum	L.S.	
0163	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (27+96.00-L-RT)	Lump Sum	L.S.	
0164	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+96.00-L-LT)	Lump Sum	L.S.	
0165	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+96.00-L-RT)	Lump Sum	L.S.	
0166	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	556.66 LF		
0167	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	218 LF		
0168	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	419 LF		
0169	8113000000-N	SP	SID INSPECTION	20 EA		
0170	8114000000-N	SP	SPT TESTING	10 EA		
0171	8115000000-N	SP	CROSSHOLE SONIC LOGGING	10 EA		
0172	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	3,370 CY		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0173	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	34,138 SF		
0174	8161000000-E	420	GROOVING BRIDGE FLOORS	37,786 SF		
0175	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	508.7 CY		
0176	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+96.00-L-LT)	Lump Sum	L.S.	
0177	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+96.00-L-RT)	Lump Sum	L.S.	
0178	8217000000-E	425	REINFORCING STEEL (BRIDGE)	150,278 LB		
0179	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	28,302 LB		
0180	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	4,175.84 LF		
0181	8364000000-E	SP	HP12X53 STEEL PILES	1,720 LF		
0182	8503000000-E	460	CONCRETE BARRIER RAIL	850.84 LF		
0183	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	3,349 TON		
0184	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	3,723 SY		
0185	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0186	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

Contract No **C202258**

County (ies): **Forsyth**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General