

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+55)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0223000000-E	SP	ROCK PLATING	50 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	10 SY		
0011	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	330 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	270 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
0015	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0016	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0017	2556000000-E	846	SHOULDER BERM GUTTER	13 LF		
0018	3030000000-E	862	STEEL BM GUARDRAIL	325 LF		
0019	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0021	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0022	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0023	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	457 SY		
0024	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	25 SF		
0025	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	43 LF		
0026	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0027	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	1 EA		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	430 SF		
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	137 SF		
0030	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,908 LF		
0032	6000000000-E	1605	TEMPORARY SILT FENCE	900 LF		
0033	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	230 TON		
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	130 TON		
0035	6012000000-E	1610	SEDIMENT CONTROL STONE	120 TON		
0036	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0037	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0039	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0040	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0041	6029000000-E	SP	SAFETY FENCE	460 LF		
0042	6030000000-E	1630	SILT EXCAVATION	180 CY		
0043	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	300 LF		
0045	6071030000-E	SP	COIR FIBER BAFFLES	200 LF		
0046	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0047	6087000000-E	1660	MOWING	0.5 ACR		
0048	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0049	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0050	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0051	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0052	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0053	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0054	6147000000-E	SP	GENERIC EROSION CONTROL ITEM TEMPORARY SILT FENCE WITH WOODEN POSTS	900 LF		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0055	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	16 LF		
------	--------------	-----	------------------------------------	----------	--	--

AA1

*** OR ***

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	16 LF		
*** OR ***						
0057 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	16 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+55.00-L-)	Lump Sum	L.S.	
0059	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+55.00-L-)	Lump Sum	L.S.	
0060	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	39.2 CY		
0061	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+55.00-L-)	Lump Sum	L.S.	
0062	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,598 LB		
0063	8364000000-E	SP	HP12X53 STEEL PILES	480 LF		
0064	8503000000-E	460	CONCRETE BARRIER RAIL	115.5 LF		
0065	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	205 TON		
0066	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	228 SY		
0067	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0068	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	577.5 LF		
0069	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" STEEL SHEET PILES	1,935 SF		

Contract No **C202234**

County (ies): **Halifax**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General