

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	18.5 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1/2")	450 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	7,800 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	4,000 SY		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	324 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	14,350 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,082 TON		
0010	1704000000-E	SP	PATCHING EXISTING PAVEMENT	125 TON		
0011	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S4.75A (LEVELING COURSE)	2,950 TON		
0012	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0013	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	105,248 LF		
0014	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	14,600 LF		
0015	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	100 LF		
0016	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	13 EA		
0017	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	126,052 LF		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	740	EA	
0019	6084000000-E	1660	SEEDING & MULCHING	14	ACR	
			Total Amount Of Bid For Entire Project :			

1545/Nov03/Q278168.5/D53730100000/E19

Contract No **C202477**

County (ies): **Bertie**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General