

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15 + 98)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	140 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	47 SY		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	140 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0014	0995000000-E	340	PIPE REMOVAL	108 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	130 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	310 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	170 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
002C	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	16 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.33)	1 EA		
003C	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	15 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	37.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	3 EA		
003E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III -SHOP CURVED)	1 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
003E	3635000000-E	876	RIP RAP, CLASS II	146 TON		
003E	3649000000-E	876	RIP RAP, CLASS B	2 TON		
004C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	766 SY		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	232 SF		
0042	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	170 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0044	4435000000-N	1135	CONES	20 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
004E	4450000000-N	1150	FLAGGER	80 HR		
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,112 LF		
004E	6000000000-E	1605	TEMPORARY SILT FENCE	650 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	330 TON		
005C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	60 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0057	6029000000-E	SP	SAFETY FENCE	1,200	LF	
005E	6030000000-E	1630	SILT EXCAVATION	200	CY	
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,000	SY	
006C	6037000000-E	SP	COIR FIBER MAT	30	SY	
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	650	LF	
0062	6071010000-E	SP	WATTLE	50	LF	
0063	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10	LB	
0064	6071030000-E	SP	COIR FIBER BAFFLES	200	LF	
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
006E	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0067	6087000000-E	1660	MOWING	0.5	ACR	
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
007C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	
0072	6114500000-N	SP	SPECIALIZED HAND MOWING	10	MHR	
0073	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6123000000-E	1670	REFORESTATION	0.25	ACR	

STRUCTURE ITEMS						

007E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+98.00-L-)	Lump Sum	L.S.	

007E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+98.00-L-)	Lump Sum	L.S.	

0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	46	CY	

007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+98.00-L-)	Lump Sum	L.S.	

007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,335	LB	

008C	8364000000-E	SP	HP12X53 STEEL PILES	300	LF	

0081	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	134.73	LF	

0082	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	102	TON	

008E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	113	SY	

0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

008E	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	606.28	LF	

1330/Oct28/Q29541.26/D353414710000/E85

Total Amount Of Bid For Entire Project :

Contract No **C202168**

County (ies): **Burke**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General