

County : Harnett, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+21.00 -L-)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (35+90.00 -L-)	Lump Sum	L.S.	
0005	0036000000-E	225	UNDERCUT EXCAVATION	1,500 CY		
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0106000000-E	230	BORROW EXCAVATION	14,450 CY		
0009	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	1,500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	5,000 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	70 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	80 SY		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	112 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	106 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		
0016	1121000000-E	520	AGGREGATE BASE COURSE	1,700 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1275000000-E	600	PRIME COAT	1,190 GAL		

County : Harnett, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1330000000-E	607	INCIDENTAL MILLING	600 SY		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	810 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	630 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,330 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	145 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	23 TON		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	200 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	1,275 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0031	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0032	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	750 LF		
0033	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	8 EA		
0034	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	12 EA		
0035	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,405 SY		

County : Harnett, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	133 LF		
0038	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0039	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0040	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0041	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	16 EA		
0043	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	130 SF		
0045	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	150 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	75 SF		
0047	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0048	4430000000-N	1130	DRUMS	70 EA		
0049	4435000000-N	1135	CONES	30 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	70 LF		
0051	4455000000-N	1150	FLAGGER	200 MD		
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	180 EA		
0053	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,158 LF		
0054	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,091 LF		

County : Harnett, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	784 LF		
0056	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	24,160 LF		
0057	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,800 LF		
0058	4880000000-E	1205	CURING COMPOUND REMOVAL, LINES	588 LF		
0059	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	25 EA		
0060	5325800000-E	1510	8" WATER LINE	1,233 LF		
0061	5546000000-E	1515	8" VALVE	3 EA		
0062	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0063	5656210000-E	1515	RELOCATE 2" RPZ BACK-FLOW PRE-VENTOR	1 EA		
0064	5801000000-E	1530	ABANDON 8" UTILITY PIPE	1,034 LF		
0065	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	226 LF		
0066	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	226 LF		
0067	6000000000-E	1605	TEMPORARY SILT FENCE	8,000 LF		
0068	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	675 TON		
0069	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	455 TON		
0070	6012000000-E	1610	SEDIMENT CONTROL STONE	550 TON		
0071	6015000000-E	1615	TEMPORARY MULCHING	11.5 ACR		
0072	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		

County : Harnett, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0074	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,300	LF	
0075	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	15	EA	
0076	6029000000-E	SP	SAFETY FENCE	14,780	LF	
0077	6030000000-E	1630	SILT EXCAVATION	485	CY	
0078	6036000000-E	1631	MATTING FOR EROSION CONTROL	14,000	SY	
0079	6037000000-E	SP	COIR FIBER MAT	400	SY	
0080	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	370	SY	
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	1,835	LF	
0082	6071010000-E	SP	WATTLE	270	LF	
0083	6071020000-E	SP	POLYACRYLAMIDE (PAM)	68	LB	
0084	6071030000-E	SP	COIR FIBER BAFFLES	585	LF	
0085	6084000000-E	1660	SEEDING & MULCHING	10	ACR	
0086	6087000000-E	1660	MOWING	5.5	ACR	
0087	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0088	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0089	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	225	LB	
0090	6108000000-E	1665	FERTILIZER TOPDRESSING	6.5	TON	
0091	6114500000-N	SP	SPECIALIZED HAND MOWING	20	MHR	
0092	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	

County : Harnett, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6123000000-E	1670	REFORESTATION	0.75 ACR		
<b>STRUCTURE ITEMS</b>						
0094	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (19+21.00-L-)	Lump Sum	L.S.	
0095	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (35+90.00-L-)	Lump Sum	L.S.	
0096	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+21.00-L-)	Lump Sum	L.S.	
0097	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (35+90.00-L-)	Lump Sum	L.S.	
0098	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19+21.00-L-)	Lump Sum	L.S.	
0099	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (35+90.00-L-)	Lump Sum	L.S.	
0100	8156000000-E	SP	CONCRETE WEARING SURFACE	6,279 SF		
0101	8161000000-E	420	GROOVING BRIDGE FLOORS	8,533 SF		
0102	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	91.4 CY		
0103	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+21.00-L-)	Lump Sum	L.S.	
0104	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (35+90.00-L-)	Lump Sum	L.S.	
0105	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,258 LB		
0106	8364000000-E	SP	HP12X53 STEEL PILES	1,210 LF		

County : Harnett, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	1,190 LF		
0108	8393000000-N	SP	PILE REDRIVES	39 EA		
0109	8503000000-E	460	CONCRETE BARRIER RAIL	382 LF		
0110	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	535 TON		
0111	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	594 SY		
0112	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0113	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0114	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,292 LF		

0811/Nov09/Q151306.15/D533453280000/E114

Total Amount Of Bid For Entire Project :

**Contract No**     **C202260**

**County (ies):**   **Harnett and Sampson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General