

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (STA 17+48.00 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	30 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	425 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	13 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	16 SY		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	88 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0016	1121000000-E	520	AGGREGATE BASE COURSE	100 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	520 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	580 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	65 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	32 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	52 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	1,225 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0036	3649000000-E	876	RIP RAP, CLASS B	45 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,750 SY		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	441 SF		
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104 SF		
0041	4430000000-N	1130	DRUMS	34 EA		
0042	4435000000-N	1135	CONES	34 EA		
0043	4445000000-E	1145	BARRICADES (TYPE III)	104 LF		
0044	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	19,004 LF		
0045	6000000000-E	1605	TEMPORARY SILT FENCE	3,400 LF		
0046	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	650 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	350 TON		
0048	6012000000-E	1610	SEDIMENT CONTROL STONE	710 TON		
0049	6015000000-E	1615	TEMPORARY MULCHING	7.5 ACR		
0050	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.75 TON		
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	650 LF		
0053	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
0054	6029000000-E	SP	SAFETY FENCE	1,500 LF		
0055	6030000000-E	1630	SILT EXCAVATION	980 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,300 SY		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6037000000-E	SP	COIR FIBER MAT	90		SY
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	350		SY
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	680		LF
0060	6045000000-E	SP	*** TEMPORARY PIPE (18")	160		LF
0061	6069000000-E	1638	STILLING BASINS	130		CY
0062	6070000000-N	SP	SPECIAL STILLING BASINS	18		EA
0063	6071010000-E	SP	WATTLE	50		LF
0064	6071020000-E	SP	POLYACRYLAMIDE (PAM)	11		LB
0065	6071030000-E	SP	COIR FIBER BAFFLES	900		LF
0066	6071050000-E	SP	*** SKIMMER (1-1/2")	8		EA
0067	6084000000-E	1660	SEEDING & MULCHING	10		ACR
0068	6087000000-E	1660	MOWING	5		ACR
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	100		LB
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		TON
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125		LB
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5		TON
0073	6111000000-E	SP	IMPERVIOUS DIKE	150		LF
0074	6114500000-N	SP	SPECIALIZED HAND MOWING	10		MHR
0075	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27		EA

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6123000000-E	1670	REFORESTATION	0.1 ACR		
CULVERT ITEMS						
0077	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (28+92.66-L-)	Lump Sum	L.S.	
0078	8126000000-N	414	CULVERT EXCAVATION, STA ***** (28+92.66-L-)	Lump Sum	L.S.	
0079	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	156 TON		
0080	8196000000-E	420	CLASS A CONCRETE (CULVERT)	251.1 CY		
0081	8245000000-E	425	REINFORCING STEEL (CULVERT)	49,600 LB		
0082	8590000000-E	876	RIP RAP, CLASS ** (I)	20 TON		
0083	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	40 SY		
STRUCTURE ITEMS						
0084	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+48.00-L-)	Lump Sum	L.S.	
0085	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+48.00-L-)	Lump Sum	L.S.	
0086	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+48.00-L-)	Lump Sum	L.S.	
0087	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,798 SF		
0088	8161000000-E	420	GROOVING BRIDGE FLOORS	5,344 SF		
0089	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	74.6 CY		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+48.00-L-)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,454 LB		
0092	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	706.67 LF		
0093	8364000000-E	SP	HP12X53 STEEL PILES	580 LF		
0094	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	670 LF		
0095	8391000000-N	SP	STEEL PILE POINTS	5 EA		
0096	8503000000-E	460	CONCRETE BARRIER RAIL	359.54 LF		
0097	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	360 TON		
0098	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	400 SY		
0099	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0100	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1112/Nov06/Q126381.01/D477421910000/E100

Total Amount Of Bid For Entire Project :

Contract No **C202233**

County (ies): **Rutherford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General