

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	3,000 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+70.00)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (39+85.50)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	500 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	300 TON		
0010	0106000000-E	230	BORROW EXCAVATION	71,200 CY		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	575 CY		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	6,220 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	4,100 SY		
0014	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0015	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	800 SY		
0016	0199000000-E	SP	TEMPORARY SHORING	8,752 SF		
0017	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	2,225 SY		
0018	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	770 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0335000000-E	SP	*** DRAINAGE PIPE (66")	388 LF		
0020	0335200000-E	SP	15" DRAINAGE PIPE	4,360 LF		
0021	0335300000-E	SP	18" DRAINAGE PIPE	944 LF		
0022	0335400000-E	SP	24" DRAINAGE PIPE	480 LF		
0023	0335500000-E	SP	30" DRAINAGE PIPE	256 LF		
0024	0335700000-E	SP	42" DRAINAGE PIPE	84 LF		
0025	0986000000-E	SP	GENERIC PIPE ITEM 48" CS PIPE CULVERTS, 0.109" THICK	136 LF		
0026	0995000000-E	340	PIPE REMOVAL	349 LF		
0027	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0028	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0029	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	315 SY		
0030	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,220 TON		
0031	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,500 TON		
0032	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,945 TON		
0033	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	730 TON		
0034	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0035	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0036	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0038	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0039	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0040	2209000000-E	838	ENDWALLS	11 CY		
0041	2220000000-E	838	REINFORCED ENDWALLS	38 CY		
0042	2253000000-E	840	PIPE COLLARS	1 CY		
0043	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	84 EA		
0044	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	24 CY		
0045	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	17 LF		
0046	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	6 EA		
0047	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	12 EA		
0048	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	32 EA		
0049	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	35 EA		
0050	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0051	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	7 EA		
0052	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	4 EA		
0053	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	5,710 LF		
0054	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	7,625 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2591000000-E	848	4" CONCRETE SIDEWALK	680 SY		
0056	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2 EA		
0057	2612000000-E	848	6" CONCRETE DRIVEWAY	131 SY		
0058	2627000000-E	852	4" CONCRETE ISLAND COVERS	70 SY		
0059	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	680 SY		
0060	3030000000-E	862	STEEL BM GUARDRAIL	2,050 LF		
0061	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0062	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0063	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0064	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	7 EA		
0065	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	13 EA		
0066	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	315 LF		
0067	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	26 EA		
0068	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	2 EA		
0069	3628000000-E	876	RIP RAP, CLASS I	141 TON		
0070	3635000000-E	876	RIP RAP, CLASS II	350 TON		
0071	3649000000-E	876	RIP RAP, CLASS B	110 TON		
0072	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,850 SY		
0073	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	670 LF		
0075	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
0076	4102000000-N	904	SIGN ERECTION, TYPE E	33 EA		
0077	4108000000-N	904	SIGN ERECTION, TYPE F	3 EA		
0078	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	32 EA		
0079	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	3 EA		
0080	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	302 SF		
0081	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	196 SF		
0082	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	208 SF		
0083	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0084	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0085	4430000000-N	1130	DRUMS	220 EA		
0086	4435000000-N	1135	CONES	100 EA		
0087	4445000000-E	1145	BARRICADES (TYPE III)	200 LF		
0088	4450000000-N	1150	FLAGGER	3,440 HR		
0089	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	10 EA		
0090	4480000000-N	1165	TMIA	2 EA		
0091	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,143 LF		
0092	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	1,126 LF		
0093	4510000000-N	SP	LAW ENFORCEMENT	720 HR		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	4520000000-N	1266	TUBULAR MARKERS (FIXED)	21 EA		
0095	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	739 EA		
0096	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,345 LF		
0097	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,502 LF		
0098	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	38 LF		
0099	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	53 LF		
0100	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	67 LF		
0101	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	27 EA		
0102	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	37,240 LF		
0103	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,550 LF		
0104	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	183 LF		
0105	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	20 EA		
0106	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	856 LF		
0107	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	330 LF		
0108	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,435 EA		
0109	5325600000-E	1510	6" WATER LINE	12 LF		
0110	5325800000-E	1510	8" WATER LINE	127 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	5326200000-E	1510	12" WATER LINE	2,682	LF	
0112	5546000000-E	1515	8" VALVE	1	EA	
0113	5558000000-E	1515	12" VALVE	4	EA	
0114	5571600000-E	1515	6" TAPPING VALVE	1	EA	
0115	5653400000-E	1515	4" DCV BACK-FLOW PREVENTOR	1	EA	
0116	5666000000-E	1515	FIRE HYDRANT	2	EA	
0117	5691500000-E	1520	12" SANITARY GRAVITY SEWER	403	LF	
0118	5775000000-E	1525	4' DIA UTILITY MANHOLE	3	EA	
0119	5780000000-E	1525	UTILITY MANHOLE WALL, *** DIA (4')	13	LF	
0120	5804000000-E	1530	ABANDON 12" UTILITY PIPE	405	LF	
0121	5816000000-N	1530	ABANDON UTILITY MANHOLE	1	EA	
0122	5871800000-E	1550	TRENCHLESS INSTALLATION OF 14" IN SOIL	1,100	LF	
0123	5882000000-N	SP	GENERIC UTILITY ITEM WATER METER ASSEMBLY	1	EA	
0124	5888000000-E	SP	GENERIC UTILITY ITEM 12" RESTRAINED JOINT DUCTILE IRON WATER LINE	325	LF	
0125	5888000000-E	SP	GENERIC UTILITY ITEM 12" RIGID RESTRAINED JOINT DUCTILE IRON SEWER	80	LF	
0126	5888000000-E	SP	GENERIC UTILITY ITEM 4" RESTRAINED JOINT DUCTILE IRON WATER LINE	70	LF	
0127	5888000000-E	SP	GENERIC UTILITY ITEM 6" RESTRAINED JOINT DUCTILE IRON WATER LINE	40	LF	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	5888000000-E	SP	GENERIC UTILITY ITEM 8" RESTRAINED JOINT DUCTILE IRON WATER LINE	40 LF		
0129	6000000000-E	1605	TEMPORARY SILT FENCE	13,000 LF		
0130	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	430 TON		
0131	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,320 TON		
0132	6012000000-E	1610	SEDIMENT CONTROL STONE	1,120 TON		
0133	6015000000-E	1615	TEMPORARY MULCHING	15 ACR		
0134	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	450 LB		
0135	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.5 TON		
0136	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,050 LF		
0137	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	10 EA		
0138	6029000000-E	SP	SAFETY FENCE	5,000 LF		
0139	6030000000-E	1630	SILT EXCAVATION	2,250 CY		
0140	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,800 SY		
0141	6037000000-E	SP	COIR FIBER MAT	120 SY		
0142	6042000000-E	1632	1/4" HARDWARE CLOTH	2,900 LF		
0143	6045000000-E	SP	*** TEMPORARY PIPE (24")	360 LF		
0144	6069000000-E	1638	STILLING BASINS	50 CY		
0145	6071030000-E	SP	COIR FIBER BAFFLES	3,900 LF		
0146	6071050000-E	SP	*** SKIMMER (1-1/2")	13 EA		



County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0147	6084000000-E	1660	SEEDING & MULCHING	18 ACR		
0148	6087000000-E	1660	MOWING	9 ACR		
0149	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0150	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0151	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	350 LB		
0152	6108000000-E	1665	FERTILIZER TOPDRESSING	10.5 TON		
0153	6111000000-E	SP	IMPERVIOUS DIKE	135 LF		
0154	6114500000-N	SP	SPECIALIZED HAND MOWING	30 MHR		
0155	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0156	6123000000-E	1670	REFORESTATION	0.5 ACR		
0157	6138000000-E	SP	GENERIC EROSION CONTROL ITEM BORROW PIT DEWATERING BASIN	14,200 CY		
<b>CULVERT ITEMS</b>						
0158	8126000000-N	414	CULVERT EXCAVATION, STA ***** (45+86.00-L-)	Lump Sum	L.S.	
0159	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	66 TON		
0160	8196000000-E	420	CLASS A CONCRETE (CULVERT)	120 CY		
0161	8245000000-E	425	REINFORCING STEEL (CULVERT)	13,831 LB		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>WALL ITEMS</b>						
0162	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	1,320 SF		
<b>STRUCTURE ITEMS</b>						
0163	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (27+70.00-L-)	Lump Sum	L.S.	
0164	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+70.00-L-)	Lump Sum	L.S.	
0165	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (39+85.50-L-)	Lump Sum	L.S.	
0166	8112730000-N	SP	PDA TESTING	1 EA		
0167	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0168	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	3,185 CY		
0169	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	30,422 SF		
0170	8161000000-E	420	GROOVING BRIDGE FLOORS	27,518 SF		
0171	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	318.2 CY		
0172	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+70.00-L-)	Lump Sum	L.S.	
0173	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (39+85.50-L-)	Lump Sum	L.S.	
0174	8217000000-E	425	REINFORCING STEEL (BRIDGE)	48,706 LB		
0175	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	4,582.33 LF		
0176	8364000000-E	SP	HP12X53 STEEL PILES	2,645 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0177	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	1,150 LF		
0178	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	2,025 LF		
0179	8393000000-N	SP	PILE REDRIVES	45 EA		
0180	8482000000-E	460	THREE BAR METAL RAIL	635.29 LF		
0181	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,990 TON		
0182	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	2,215 SY		
0183	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0184	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1339/Dec02/Q402621.32/D796022764000/E184

Total Amount Of Bid For Entire Project :

**Contract No**     **C202066**

**County (ies):**   **Cumberland**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General