

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	363 SY		
0007	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	290 TON		
0008	0343000000-E	310	15" SIDE DRAIN PIPE	304 LF		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	398 LF		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	536 LF		
0011	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	924 LF		
0012	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	496 LF		
0013	0995000000-E	340	PIPE REMOVAL	309 LF		
0014	1121000000-E	520	AGGREGATE BASE COURSE	130 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1297000000-E	607	MILLING ASPHALT PAVEMENT, *** DEPTH (1-1/2")	540 SY		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,225 TON		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,400	TON	
001E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	3,675	TON	
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	340	TON	
0021	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	225	TON	
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100	TON	
0023	2253000000-E	840	PIPE COLLARS	1	CY	
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	15	EA	
0025	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	11	LF	
002E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4	EA	
0027	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5	EA	
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	6	EA	
002E	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	6	EA	
003C	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	3	EA	
0031	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	2,400	LF	
0032	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	20	LF	
0033	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	700	SY	
0034	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	420	LF	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	30 EA		
003E	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	20 EA		
0037	3557000000-E	866	ADDITIONAL BARBED WIRE	100 LF		
003E	3649000000-E	876	RIP RAP, CLASS B	5 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	16 SY		
004C	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	32 SF		
0041	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	51 SF		
0042	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	187 SF		
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	30 LF		
0044	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
004E	4108000000-N	904	SIGN ERECTION, TYPE F	14 EA		
0047	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1 EA		
004E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	20 EA		
004E	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	15 EA		
005C	4360000000-N	SP	GENERIC SIGNING ITEM WARNING FLAGS	18 EA		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	56 SF		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	12	SF	
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57	SF	
0054	4430000000-N	1130	DRUMS	30	EA	
005E	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
005E	4455000000-N	1150	FLAGGER	12	MD	
0057	4510000000-N	SP	LAW ENFORCEMENT	16	HR	
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	9,300	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,650	LF	
006C	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	200	LF	
0061	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	55	LF	
0062	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	20	EA	
0063	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	310	EA	
0064	5325200000-E	1510	2" WATER LINE	131	LF	
006E	5325800000-E	1510	8" WATER LINE	331	LF	
006E	5326200000-E	1510	12" WATER LINE	60	LF	
0067	5606000000-E	1515	2" BLOW OFF	1	EA	
006E	5648000000-N	1515	RELOCATE WATER METER	2	EA	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	4,200	LF	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	60 TON		
0071	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	110 TON		
0072	6012000000-E	1610	SEDIMENT CONTROL STONE	180 TON		
0073	6015000000-E	1615	TEMPORARY MULCHING	7 ACR		
0074	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
007E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
007E	6030000000-E	1630	SILT EXCAVATION	550 CY		
0077	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,300 SY		
007E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	14 SY		
007E	6042000000-E	1632	1/4" HARDWARE CLOTH	720 LF		
008C	6071030000-E	SP	COIR FIBER BAFFLES	80 LF		
0081	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0082	6087000000-E	1660	MOWING	2 ACR		
0083	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0084	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
008E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250 LB		
008E	6108000000-E	1665	FERTILIZER TOPDRESSING	6 TON		
0087	6114500000-N	SP	SPECIALIZED HAND MOWING	3 MHR		
008E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	20 EA		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	7060000000-E	1705	SIGNAL CABLE	970	LF	
009C	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	5	EA	
0091	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	5	EA	
0092	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2	EA	
009E	7264000000-E	1710	MESSENGER CABLE (3/8")	380	LF	
0094	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	690	LF	
009E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6	EA	
009E	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1	EA	
0097	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1	EA	
009E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,060	LF	
009E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	1,810	LF	
010C	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	2	EA	
0101	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4	EA	
0102	7613000000-N	SP	SOIL TEST	4	EA	
010E	7614100000-E	SP	DRILLED PIER FOUNDATION	24	CY	
0104	7636000000-N	1745	SIGN FOR SIGNALS	3	EA	
010E	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
010E	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1	EA	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	7	EA	
010E	7901000000-N	1753	CABINET BASE EXTENDER	1	EA	
010E	7980000000-N	SP	GENERIC SIGNAL ITEM AUXILIARY OUTPUT FILE	1	EA	
011C	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS LIGHTNING ARRESTORS	2	EA	
0111	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEMS	1	EA	

1123/Dec09/Q54695.25/D490881572000/E111

Total Amount Of Bid For Entire Project :

Contract No **C202088**

County (ies): **Harnett**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General