

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	277 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	170 TON		
0004	1243000000-E	SP	SHOULDER CONSTRUCTION	8.88 SMI		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	13.37 SMI		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	201,160 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	19,500 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	4,800 SY		
0009	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,236 TON		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,736 TON		
0011	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	35,146 TON		
0012	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	4,755 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	226 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,419 TON		
0015	1704000000-E	SP	PATCHING EXISTING PAVEMENT	9,860 TON		
0016	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	13 EA		
0017	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2 EA		
0018	2612000000-E	848	6" CONCRETE DRIVEWAY	300 SY		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0020	2830000000-N	858	ADJUSTMENT OF MANHOLES	92 EA		
0021	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	73 EA		
0022	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0023	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	91,900 LF		
0024	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	193,700 LF		
0025	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	7,500 LF		
0026	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	3,000 LF		
0027	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	5,880 LF		
0028	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,800 LF		
0029	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	500 LF		
0030	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	200 LF		
0031	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,454 LF		
0032	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	66 EA		
0033	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	277 EA		
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	45,200 LF		
0035	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	198 LF		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2,555 EA		
0037	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0038	6000000000-E	1605	TEMPORARY SILT FENCE	3,800 LF		
0039	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
1141/Dec16/Q641829.25/D123088100000/E39			Total Amount Of Bid For Entire Project :			

Contract No **C202519**

County (ies): **Mecklenburg**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General