

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,800 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+55.00-L-)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	600 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	48 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	600 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	600 SY		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	50 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION COND MATERIAL MINOR STRS	16 TON		
0012	0335200000-E	SP	15" DRAINAGE PIPE	104 LF		
0013	0335400000-E	SP	24" DRAINAGE PIPE	40 LF		
0014	0995000000-E	340	PIPE REMOVAL	80 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	142 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	230 SY		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	350 TON		
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	170 TON		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	270 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0025	3420000000-E	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED STEEL BEAM GUARDRAIL	350 LF		
0026	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNIT, TYPE 350	4 EA		
0028	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNIT, TYPE III	4 EA		
0029	3628000000-E	876	RIP RAP, CLASS I	233 TON		
0030	3635000000-E	876	RIP RAP, CLASS II	20 TON		
0031	3649000000-E	876	RIP RAP, CLASS B	155 TON		
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,290 SY		
0033	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0034	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	38 LF		
0035	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0036	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9 EA		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	491 SF		
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	139 SF		
0039	4430000000-N	1130	DRUMS	20 EA		
0040	4445000000-E	1145	BARRICADES (TYPE III)	160 LF		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,200 LF		
0042	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	24 EA		
0043	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	230 TON		
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0047	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0052	6029000000-E	SP	SAFETY FENCE	850 LF		
0053	6030000000-E	1630	SILT EXCAVATION	550 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,500 SY		
0055	6037000000-E	SP	COIR FIBER MAT	50 SY		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	560 LF		
0058	6071010000-E	SP	WATTLE	40 LF		
0059	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0060	6071030000-E	SP	COIR FIBER BAFFLES	380 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0063	6087000000-E	1660	MOWING	1 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0068	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0070	6123000000-E	1670	REFORESTATION	0.25 ACR		

STRUCTURE ITEMS

0071	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+55.00-L-)	Lump Sum	L.S.	
0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+55.00-L-)	Lump Sum	L.S.	

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,18+55.00-L-)	Lump Sum	L.S.	
0074	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	575 CY		
0075	8156000000-E	SP	CONCRETE WEARING SURFACE	3,533 SF		
0076	8161000000-E	420	GROOVING BRIDGE FLOORS	4,829 SF		
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	68.5 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+55.00-L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,221 LB		
0080	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	595 LB		
0081	8364000000-E	SP	HP12X53 STEEL PILES	140 LF		
0082	8391000000-N	SP	STEEL PILE POINTS	14 EA		
0083	8475000000-E	460	TWO BAR METAL RAIL	179.519 LF		
0084	8517000000-E	460	1'-****X ***** CONCRETE PARAPET (1'-2"X2'-9 13/16")	195.431 LF		
0085	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	475 TON		
0086	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	525 SY		
0087	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0088	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0089	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,268.583 LF		

Contract No **C202267**

County (ies): **Orange**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General