

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	275 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	565 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	22.16 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	14,193 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	75,469 SY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	1,067 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	17,852 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")	271 SY		
0010	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/2")	856 SY		
0011	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (3" TO 5-1/2")	4,128 SY		
0012	1330000000-E	607	INCIDENTAL MILLING	1,283 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,184 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	882 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	11,831 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	14,552 TON		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,960	TON	
0018	1704000000-E	SP	PATCHING EXISTING PAVEMENT	114	TON	
0019	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	136,294	SY	
0020	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	56	EA	
0021	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2	EA	
0022	2830000000-N	858	ADJUSTMENT OF MANHOLES	50	EA	
0023	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	31	EA	
0024	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	59,126	LF	
0025	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	50,346	LF	
0026	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	338	LF	
0027	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,505	LF	
0028	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	7,135	LF	
0029	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	611	LF	
0030	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,107	LF	
0031	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	32	EA	
0032	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	133	EA	
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	378,957	LF	

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	565 LF		
0035	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	611 LF		
0036	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	151 LF		
0037	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	12 EA		
0038	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0039	6084000000-E	1660	SEEDING & MULCHING	4.23 ACR		
0040	6110000000-E	SP	RESIDENTIAL SEEDING	4.11 ACR		
0041	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	7 LF		
0042	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	3,256 LF		
0043	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	44 EA		
0044	7420000000-E	1722	2" RISER WITH WEATHERHEAD	8 EA		
0045	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	11,361 LF		
0046	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	19,849 LF		
			0808/Dec16/Q825101.5/D163101100000/E46			
			Total Amount Of Bid For Entire Project :			

Contract No **C202540**

County (ies): **Orange**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General