

County : Orange

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|-------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB-BING | 1 ACR | | |
| 0004 | 0063000000-N | SP | GRADING | Lump Sum | L.S. | |
| 000E | 0106000000-E | 230 | BORROW EXCAVATION | 6,000 CY | | |
| 000E | 0192000000-N | 260 | PROOF ROLLING | 1.5 HR | | |
| 0007 | 0320000000-E | SP | FOUNDATION CONDITIONING FABRIC | 283 SY | | |
| 000E | 0330000000-E | SP | GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 230 TON | | |
| 000E | 0335100000-E | SP | 12" DRAINAGE PIPE | 200 LF | | |
| 001C | 0335200000-E | SP | 15" DRAINAGE PIPE | 1,124 LF | | |
| 0011 | 0335300000-E | SP | 18" DRAINAGE PIPE | 152 LF | | |
| 0012 | 0335400000-E | SP | 24" DRAINAGE PIPE | 332 LF | | |
| 0013 | 0335500000-E | SP | 30" DRAINAGE PIPE | 32 LF | | |
| 0014 | 0335600000-E | SP | 36" DRAINAGE PIPE | 32 LF | | |
| 001E | 0986000000-E | SP | GENERIC PIPE ITEM 12" SIDE DRAIN PIPE | 132 LF | | |
| 001E | 0986000000-E | SP | GENERIC PIPE ITEM 15" SIDE DRAIN PIPE | 112 LF | | |
| 0017 | 0995000000-E | 340 | PIPE REMOVAL | 884 LF | | |
| 001E | 1220000000-E | 545 | INCIDENTAL STONE BASE | 250 TON | | |

County : Orange

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0019 | 1308000000-E | 607 | MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2") | 600 | SY | |
| 002C | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 1,760 | TON | |
| 0021 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 1,400 | TON | |
| 0022 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 2,100 | TON | |
| 0023 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 270 | TON | |
| 0024 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 80 | TON | |
| 002E | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 39 | EA | |
| 002E | 2308000000-E | 840 | MASONRY DRAINAGE STRUCTURES | 7.3 | LF | |
| 0027 | 2364000000-N | 840 | FRAME WITH TWO GRATES, STD 840.16 | 16 | EA | |
| 002E | 2366000000-N | 840 | FRAME WITH TWO GRATES, STD 840.24 | 1 | EA | |
| 002E | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 1 | EA | |
| 003C | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E) | 2 | EA | |
| 0031 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F) | 10 | EA | |
| 0032 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G) | 10 | EA | |
| 0033 | 2542000000-E | 846 | 1'-6" CONCRETE CURB & GUTTER | 760 | LF | |
| 0034 | 2549000000-E | 846 | 2'-6" CONCRETE CURB & GUTTER | 4,570 | LF | |

County : Orange

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 003E | 2577000000-E | 846 | CONCRETE EXPRESSWAY GUTTER | 100 | LF | |
| 003E | 2591000000-E | 848 | 4" CONCRETE SIDEWALK | 1,520 | SY | |
| 0037 | 2605000000-N | 848 | CONCRETE WHEELCHAIR RAMPS | 10 | EA | |
| 003E | 2612000000-E | 848 | 6" CONCRETE DRIVEWAY | 300 | SY | |
| 003E | 2619000000-E | 850 | 4" CONCRETE PAVED DITCH | 20 | SY | |
| 004C | 2647000000-E | 852 | 5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED) | 90 | SY | |
| 0041 | 2905000000-N | 859 | CONVERT EXISTING DROP INLET TO JUNCTION BOX | 1 | EA | |
| 0042 | 2920000000-N | SP | CONVERT EXISTING DROP INLET TO CATCH BASIN | 1 | EA | |
| 004E | 3628000000-E | 876 | RIP RAP, CLASS I | 20 | TON | |
| 0044 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 290 | SY | |
| 004E | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 572 | LF | |
| 004E | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 48 | EA | |
| 0047 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 23 | EA | |
| 004E | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 152 | SF | |
| 004E | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 224 | SF | |
| 005C | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 2 | EA | |
| 0051 | 4420000000-N | 1120 | CHANGEABLE MESSAGE SIGN | 2 | EA | |
| 0052 | 4430000000-N | 1130 | DRUMS | 209 | EA | |
| 005E | 4435000000-N | 1135 | CONES | 20 | EA | |

County : Orange

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0054 | 4455000000-N | 1150 | FLAGGER | 80 | MD | |
| 005E | 4480000000-N | 1165 | TMIA | 2 | EA | |
| 005E | 4510000000-N | SP | LAW ENFORCEMENT | 56 | HR | |
| 0057 | 4516000000-N | 1180 | SKINNY DRUM | 10 | EA | |
| 005E | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 5,960 | LF | |
| 005E | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 7,824 | LF | |
| 006C | 4695000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS) | 1,141 | LF | |
| 0061 | 4697000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS) | 180 | LF | |
| 0062 | 4710000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 559 | LF | |
| 006E | 4721000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS) | 6 | EA | |
| 0064 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 48 | EA | |
| 006E | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 28,465 | LF | |
| 006E | 4820000000-E | 1205 | PAINT PAVEMENT MARKING LINES (8") | 1,488 | LF | |
| 0067 | 4835000000-E | 1205 | PAINT PAVEMENT MARKING LINES (24") | 1,040 | LF | |
| 006E | 4840000000-N | 1205 | PAINT PAVEMENT MARKING CHARACTER | 12 | EA | |
| 006E | 4845000000-N | 1205 | PAINT PAVEMENT MARKING SYMBOL | 150 | EA | |
| 007C | 4860000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (8") | 460 | LF | |

County : Orange

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|------------------------------------|-------------|-----------|--------|
| 0071 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 145 EA | | |
| 0072 | 5326600000-E | 1510 | 16" WATER LINE | 104 LF | | |
| 0073 | 5648000000-N | 1515 | RELOCATE WATER METER | 3 EA | | |
| 0074 | 5649000000-N | 1515 | RECONNECT WATER METER | 3 EA | | |
| 007E | 5672000000-N | 1515 | RELOCATE FIRE HYDRANT | 1 EA | | |
| 007E | 5691100000-E | 1520 | 4" SANITARY GRAVITY SEWER | 48 LF | | |
| 0077 | 5768000000-N | 1520 | SANITARY SEWER CLEAN-OUT | 1 EA | | |
| 007E | 5810000000-E | 1530 | ABANDON 16" UTILITY PIPE | 94 LF | | |
| 007E | 5828000000-N | 1530 | REMOVE UTILITY MANHOLE | 1 EA | | |
| 008C | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 2,250 LF | | |
| 0081 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 250 TON | | |
| 0082 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 250 TON | | |
| 008E | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 500 TON | | |
| 0084 | 6015000000-E | 1615 | TEMPORARY MULCHING | 4.5 ACR | | |
| 008E | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 LB | | |
| 008E | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEEDING | 0.5 TON | | |
| 0087 | 6030000000-E | 1630 | SILT EXCAVATION | 450 CY | | |
| 008E | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 7,500 SY | | |
| 008E | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 1,575 LF | | |

County : Orange

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 009C | 6071030000-E | SP | COIR FIBER BAFFLES | 50 LF | | |
| 0091 | 6084000000-E | 1660 | SEEDING & MULCHING | 5 ACR | | |
| 0092 | 6087000000-E | 1660 | MOWING | 2 ACR | | |
| 0093 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0094 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 009E | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 100 LB | | |
| 009E | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 2.5 TON | | |
| 0097 | 6114500000-N | SP | SPECIALIZED HAND MOWING | 5 MHR | | |
| 009E | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 EA | | |
| 009E | 7000000000-E | 1705 | PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/COUNTDOWN) | 2 EA | | |
| 010C | 7060000000-E | 1705 | SIGNAL CABLE | 1,760 LF | | |
| 0101 | 7120000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 3 SECTION) | 9 EA | | |
| 0102 | 7232000000-N | SP | AUDIBLE PEDESTRIAN SIGNAL | 2 EA | | |
| 0103 | 7264000000-E | 1710 | MESSENGER CABLE (3/8") | 725 LF | | |
| 0104 | 7288000000-E | 1715 | PAVED TRENCHING (*****) (1, 2") | 20 LF | | |
| 010E | 7300000000-E | 1715 | UNPAVED TRENCHING (*****) (1, 2") | 750 LF | | |
| 010E | 7301000000-E | 1715 | DIRECTIONAL DRILL (*****) (1, 2") | 110 LF | | |
| 0107 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 9 EA | | |
| 010E | 7360000000-N | 1720 | WOOD POLE | 6 EA | | |

County : Orange

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 010E | 7372000000-N | 1721 | GUY ASSEMBLY | 8 | EA | |
| 011C | 7396000000-E | 1722 | 1/2" RISER WITH WEATHERHEAD | 1 | EA | |
| 0111 | 7408000000-E | 1722 | 1" RISER WITH WEATHERHEAD | 1 | EA | |
| 0112 | 7420000000-E | 1722 | 2" RISER WITH WEATHERHEAD | 7 | EA | |
| 011E | 7444000000-E | 1725 | INDUCTIVE LOOP SAWCUT | 1,050 | LF | |
| 0114 | 7456000000-E | 1726 | LEAD-IN CABLE (***** (14-2) | 5,015 | LF | |
| 011E | 7624000000-N | 1743 | SIGNAL PEDESTAL WITH FOUNDATION | 2 | EA | |
| 011E | 7636000000-N | 1745 | SIGN FOR SIGNALS | 3 | EA | |
| 0117 | 7675000000-N | SP | LED BLANKOUT SIGN | 1 | EA | |
| 011E | 7684000000-N | 1750 | SIGNAL CABINET FOUNDATION | 1 | EA | |
| 011E | 7756000000-N | 1751 | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) | 1 | EA | |
| 012C | 7780000000-N | 1751 | DETECTOR CARD (TYPE 2070L) | 6 | EA | |
| 0121 | 7901000000-N | 1753 | CABINET BASE EXTENDER | 1 | EA | |

1453/Nov30/Q95476.55/D523858830000/E121

Total Amount Of Bid For Entire Project :

Contract No **C202372**

County (ies): **Orange**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General