

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	7.95	SMI	
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	23,714	SY	
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	379,983	SY	
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	109,766	SY	
0006	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	18,770	TON	
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	24,960	TON	
0008	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	36,389	TON	
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,559	TON	
0010	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	882	TON	
0011	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	3,141	TON	
0012	1663000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED	15,932	TON	
0013	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	206,005	LF	
0014	2354200000-N	840	FRAME WITH GRATE, STD 840.24	13	EA	
0015	2473000000-N	SP	GENERIC DRAINAGE ITEM DRAINAGE STRUCTURE REPAIR	13	EA	
0016	2473000000-N	SP	GENERIC DRAINAGE ITEM FUNNEL DRAIN INLET REPAIR	14	EA	

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2619000000-E	850	4" CONCRETE PAVED DITCH	8,746 SY		
001E	2752000000-E	SP	GENERIC PAVING ITEM CONCRETE MEDIAN BARRIER WALL REPAIR	1,200 LF		
001E	3030000000-E	862	STEEL BM GUARDRAIL	3,750 LF		
002C	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	54 EA		
0021	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	704 SF		
0022	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	2,400 SF		
0023	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	6 EA		
0024	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	6 EA		
002E	4430000000-N	1130	DRUMS	100 EA		
002E	4435000000-N	1135	CONES	800 EA		
0027	4480000000-N	1165	TMIA	4 EA		
002E	4516000000-N	1180	SKINNY DRUM	800 EA		
002E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	51,680 LF		
003C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	11,760 LF		
0031	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	173,660 LF		
0032	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	33,320 LF		
0033	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	7,000 LF		
0034	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	25 EA		

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	964,369 LF		
003E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	47 EA		
0037	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,986 EA		
003E	4960000000-N	SP	GENERIC TRAFFIC CONTROL ITEM GUARDRAIL DELINEATORS	600 EA		
003E	4960000000-N	SP	GENERIC TRAFFIC CONTROL ITEM REMOVE & REPLACE TOP MOUNTED BARRIER WALL DELINEATORS	250 EA		
004C	4960000000-N	SP	GENERIC TRAFFIC CONTROL ITEM SIDE MOUNTED BARRIER WALL DELINEATORS	100 EA		
0041	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0934/Nov30/Q2084517.95/D13516150000/E41			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202483**

**County (ies):**   **Polk**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General