

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+55.20)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (38+12.60)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	15,972 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	275 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	150 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	300 SY		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	20 LF		
0015	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	32 LF		
0016	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	44 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	35 TON		
0019	1220000000-E	545	INCIDENTAL STONE BASE	240 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.6 SMI		
0021	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	195 SY		
0022	1330000000-E	607	INCIDENTAL MILLING	448 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,925 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,180 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,505 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	393 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0028	1704000000-E	SP	PATCHING EXISTING PAVEMENT	930 TON		
0029	2000000000-N	806	RIGHT OF WAY MARKERS	23 EA		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	13 EA		
0031	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	19.7 LF		
0032	2355000000-N	840	FRAME WITH GRATE, STD 840.29	4 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	5 EA		
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0035	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	820 LF		
0036	2591000000-E	848	4" CONCRETE SIDEWALK	700 SY		
0037	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2619000000-E	850	4" CONCRETE PAVED DITCH	43 SY		
0039	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA		
0040	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0041	3030000000-E	862	STEEL BM GUARDRAIL	237.5 LF		
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0043	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	5 EA		
0044	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0045	3628000000-E	876	RIP RAP, CLASS I	20 TON		
0046	3649000000-E	876	RIP RAP, CLASS B	20 TON		
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,275 SY		
0048	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0049	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	120 LF		
0050	4102000000-N	904	SIGN ERECTION, TYPE E	7 EA		
0051	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
0052	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	17 EA		
0053	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0054	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	436 SF		
0055	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	148 SF		
0056	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	78 SF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4445000000-E	1145	BARRICADES (TYPE III)	144 LF		
0058	4455000000-N	1150	FLAGGER	30 MD		
0059	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	21,341 LF		
0060	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	22,677 LF		
0061	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	933 LF		
0062	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	142 LF		
0063	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6 EA		
0064	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	957 LF		
0065	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)	356 LF		
0066	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,840 LF		
0067	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	197 EA		
0068	5326200000-E	1510	12" WATER LINE	799 LF		
0069	5558000000-E	1515	12" VALVE	2 EA		
0070	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0071	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0072	5804000000-E	1530	ABANDON 12" UTILITY PIPE	745 LF		
0073	5836000000-E	1540	24" ENCASMENT PIPE	332 LF		
0074	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	166 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	5872210000-E	1550	TRENCHLESS INSTALLATION OF 24" NOT IN SOIL	166 LF		
0076	6000000000-E	1605	TEMPORARY SILT FENCE	4,000 LF		
0077	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	450 TON		
0078	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	750 TON		
0079	6012000000-E	1610	SEDIMENT CONTROL STONE	350 TON		
0080	6015000000-E	1615	TEMPORARY MULCHING	6 ACR		
0081	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0082	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0083	6024000000-E	1622	TEMPORARY SLOPE DRAINS	800 LF		
0084	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	8 EA		
0085	6029000000-E	SP	SAFETY FENCE	2,000 LF		
0086	6030000000-E	1630	SILT EXCAVATION	1,725 CY		
0087	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,500 SY		
0088	6037000000-E	SP	COIR FIBER MAT	275 SY		
0089	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	900 SY		
0090	6042000000-E	1632	1/4" HARDWARE CLOTH	625 LF		
0091	6071010000-E	SP	WATTLE	400 LF		
0092	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100 LB		
0093	6071030000-E	SP	COIR FIBER BAFFLES	1,025 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0095	6084000000-E	1660	SEEDING & MULCHING	12.6 ACR		
0096	6087000000-E	1660	MOWING	3 ACR		
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5 TON		
0101	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0102	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0103	6123000000-E	1670	REFORESTATION	0.1 ACR		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0104 AA1	0366000000-E	310	12" RC PIPE CULVERTS, CLASS III	20 LF		
0105 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	716 LF		
0106 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
0107 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	12 LF		
0108 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	12 LF		
*** OR ***						
0109 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	616 LF		
0110 AA2	0536000000-E	SP	*** HDPE PIPE CULVERTS (12")	20 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	100 LF		
0112 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	48 LF		
0113 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	12 LF		
0114 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	12 LF		
*** OR ***						
0115 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	616 LF		
0116 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (12", 0.064")	20 LF		
0117 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	100 LF		
0118 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	48 LF		
0119 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	12 LF		
0120 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.064")	12 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0121	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+55.20-L-)	Lump Sum	L.S.	
0122	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (38+12.60-L-)	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	8096000000-E	SP	PILE EXCAVATION IN SOIL	80 LF		
0124	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	30 LF		
0125	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	2,065 CY		
0126	8156000000-E	SP	CONCRETE WEARING SURFACE	12,160 SF		
0127	8161000000-E	420	GROOVING BRIDGE FLOORS	14,653 SF		
0128	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	113.1 CY		
0129	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	164.6 CY		
0130	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+55.20-L-)	Lump Sum	L.S.	
0131	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (38+12.60-L-)	Lump Sum	L.S.	
0132	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,714 LB		
0133	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	3,817 LB		
0134	8364000000-E	SP	HP12X53 STEEL PILES	930 LF		
0135	8482000000-E	460	THREE BAR METAL RAIL	322.7 LF		
0136	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	655 TON		
0137	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	730 SY		
0138	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0139	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0140	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	2,241 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	2,629.69 LF		

1315/Jan07/Q181774.09/D560825720000/E141

Total Amount Of Bid For Entire Project :

Contract No **C202232**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General