

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	43,500 CY		
0006	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (24+61.31 -L-)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	2,124 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	5,900 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	370 CY		
0010	0141000000-E	240	BERM DITCH CONSTRUCTION	340 LF		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	13,750 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	9,300 SY		
0014	0199000000-E	SP	TEMPORARY SHORING	110 SF		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	150 TON		
0016	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	450 SY		
0017	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	12 LF		
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
002C	0995000000-E	340	PIPE REMOVAL	122 LF		
0021	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0022	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0023	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0024	1231000000-E	560	SHOULDER BORROW	8,600 CY		
002E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	15,800 SY		
002E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	246,489 SY		
0027	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (5")	29,236 SY		
002E	1330000000-E	607	INCIDENTAL MILLING	510 SY		
002E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	14,700 TON		
003C	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	5,200 TON		
0031	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	5,172 TON		
0032	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	12,958 TON		
0033	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	24,941 TON		
0034	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	880 TON		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,021 TON		
003E	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	1,372 TON		
0037	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	400 TON		
003E	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	81,898 LF		
003E	2253000000-E	840	PIPE COLLARS	1.56 CY		
004C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	17 EA		
0041	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	8.3 LF		
0042	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	17 EA		
0043	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0044	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	30 LF		
004E	2556000000-E	846	SHOULDER BERM GUTTER	2,150 LF		
004E	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	50 LF		
0047	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
004E	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	3 EA		
004E	3030000000-E	862	STEEL BM GUARDRAIL	3,900 LF		
005C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0051	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6 EA		
0052	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	2 EA		
0054	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
005E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,252 LF		
005E	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	1,980 LF		
0057	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	130 EA		
005E	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	80 EA		
005E	3628000000-E	876	RIP RAP, CLASS I	265 TON		
006C	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0061	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,135 SY		
0062	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	4 CY		
0063	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	2 CY		
0064	4057000000-E	SP	OVERHEAD FOOTING	60 CY		
006E	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	4,007 LB		
006E	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	172 LB		
0067	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	126 LF		
006E	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	1 EA		
006E	4082000000-E	903	SUPPORTS, WOOD	45 LF		
007C	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (10+00 -CD-)	Lump Sum	L.S.	

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (10+00 -RP2B-)	Lump Sum	L.S.	
0072	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (25+70 -L-)	Lump Sum	L.S.	
0073	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (36+00 -L-)	Lump Sum	L.S.	
0074	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
0075	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0076	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0077	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	9 EA		
0078	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (B)	5 EA		
0079	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	7 EA		
0080	4114000000-N	904	SIGN ERECTION, MILEMARKERS	1 EA		
0081	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	1 EA		
0082	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (B)	1 EA		
0083	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	2 EA		
0084	4149000000-N	907	DISPOSAL OF SIGN SYSTEM, OVERHEAD	4 EA		
0085	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	5 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	5 EA		
0087	4157000000-N	907	STOCKPILE SIGN SYSTEM, WOOD	1 EA		
008E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	457 SF		
008E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,349 SF		
009C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	188 SF		
0091	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	8 EA		
009Z	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	12 EA		
009Z	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	65 DAY		
0094	4430000000-N	1130	DRUMS	790 EA		
009E	4445000000-E	1145	BARRICADES (TYPE III)	192 LF		
009E	4450000000-N	1150	FLAGGER	240 HR		
0097	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
009E	4480000000-N	1165	TMIA	3 EA		
009E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	406 LF		
010C	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	210 LF		
0101	4507000000-E	SP	WATER FILLED BARRIER	400 LF		
0102	4510000000-N	SP	LAW ENFORCEMENT	2,160 HR		
010Z	4516000000-N	1180	SKINNY DRUM	480 EA		
0104	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,413 LF		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	114,302 LF		
010E	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	41,920 LF		
0107	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	649 LF		
010E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	745 LF		
010E	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	3,188 LF		
011C	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	10,711 LF		
0111	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	402 LF		
0112	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	61 EA		
0113	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	87 EA		
0114	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	1,454 LF		
011E	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (IV)	616 LF		
011E	4785000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (12") (III)	21 LF		
0117	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,048 LF		
011E	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	22,401 LF		
011E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	900 LF		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012C	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	4,296	LF	
0121	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	192	LF	
0122	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	40	EA	
0123	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	121	EA	
0124	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	6,831	LF	
012E	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	900	LF	
012E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	24	EA	
0127	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,797	EA	
012E	5020000000-N	1401	PORTABLE DRIVE UNIT	1	EA	
012E	5025000000-E	1402	HIGH MOUNT FOUNDATIONS	32.4	CY	
013C	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (400W HPS)	40	EA	
0131	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	8	EA	
0132	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	1	EA	
0133	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/O USE)	100	LF	
0134	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	50	LF	
013E	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	150	LF	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (2")	200 LF		
0137	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	40 LF		
0138	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	40 LF		
0139	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	50 LF		
0140	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	265 LF		
0141	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	55 LF		
0142	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	210 LF		
0143	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	1,775 LF		
0144	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	1,530 LF		
0145	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	620 LF		
0146	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	9 EA		
0147	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC30)	3 EA		
0148	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC36)	1 EA		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0149	5252000000-N	1412	UNDERPASS LUMINARIES ***** (150W HPS)	8 EA		
015C	5253000000-N	1412	UNDERPASS CIRCUITRY AT ***** (UPL-1, PAGE ROAD)	Lump Sum	L.S.	
0151	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0152	5270000000-N	SP	GENERIC LIGHTING ITEM 120' HIGH MOUNT STANDARD	1 EA		
0153	5270000000-N	SP	GENERIC LIGHTING ITEM 80' HIGH MOUNT STANDARD	5 EA		
0154	5270000000-N	SP	GENERIC LIGHTING ITEM LIGHT CONTROL EQUIPMENT, RW, 2 40/480V	1 EA		
015E	5270000000-N	SP	GENERIC LIGHTING ITEM RELOCATE CONTROL SYSTEM	1 EA		
015E	6000000000-E	1605	TEMPORARY SILT FENCE	18,500 LF		
0157	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,000 TON		
015E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,700 TON		
0159	6012000000-E	1610	SEDIMENT CONTROL STONE	1,350 TON		
016C	6015000000-E	1615	TEMPORARY MULCHING	51 ACR		
0161	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	950 LB		
0162	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.75 TON		
0163	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,100 LF		
0164	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	12 EA		
016E	6029000000-E	SP	SAFETY FENCE	2,000 LF		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
016E	6030000000-E	1630	SILT EXCAVATION	5,800 CY		
0167	6036000000-E	1631	MATTING FOR EROSION CONTROL	60,000 SY		
016E	6037000000-E	SP	COIR FIBER MAT	100 SY		
016E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,650 SY		
017C	6042000000-E	1632	1/4" HARDWARE CLOTH	1,300 LF		
0171	6071010000-E	SP	WATTLE	200 LF		
0172	6071020000-E	SP	POLYACRYLAMIDE (PAM)	400 LB		
0173	6071030000-E	SP	COIR FIBER BAFFLES	2,750 LF		
0174	6071050000-E	SP	*** SKIMMER (1-1/2")	6 EA		
017E	6084000000-E	1660	SEEDING & MULCHING	30 ACR		
017E	6087000000-E	1660	MOWING	34 ACR		
0177	6090000000-E	1661	SEED FOR REPAIR SEEDING	400 LB		
017E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25 TON		
017E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	700 LB		
018C	6108000000-E	1665	FERTILIZER TOPDRESSING	20.5 TON		
0181	6114500000-N	SP	SPECIALIZED HAND MOWING	40 MHR		
0182	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0183	6123000000-E	1670	REFORESTATION	7 ACR		
0184	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,675 LF		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
018E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	200	LF	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
018E AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,264	LF	
*** OR ***						
0187 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	300	LF	
018E AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	964	LF	
*** OR ***						
018S AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	300	LF	
019C AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	964	LF	
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0191	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24 + 32.55-L-)	Lump Sum	L.S.	
0192	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 24 + 32.55-L-)	Lump Sum	L.S.	
0193	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 24 + 32.55-L-)	Lump Sum	L.S.	
0194	8096000000-E	SP	PILE EXCAVATION IN SOIL	12 LF		
019E	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	20 LF		
019E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,697 SF		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0197	8161000000-E	420	GROOVING BRIDGE FLOORS	3,404 SF		
019E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	85.3 CY		
019E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24 + 32.55-L-)	Lump Sum	L.S.	
020C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,787 LB		
0201	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,511 LB		
020Z	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	115,500 LS		
020E	8364000000-E	SP	HP12X53 STEEL PILES	150 LF		
0204	8503000000-E	460	CONCRETE BARRIER RAIL	186.02 LF		
020E	8531000000-E	462	4" SLOPE PROTECTION	200 SY		
020E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0207	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1441/Dec10/Q1027743.78/D864283110000/E207

Total Amount Of Bid For Entire Project :

Contract No **C202277**

County (ies): **Wake & Durham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General