

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,250 CY		
0003	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0063000000-N	SP	GRADING	Lump Sum	L.S.	
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
001C	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	30 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION COND MATERIAL MINOR STRS	10 TON		
0012	0986000000-E	SP	GENERIC PIPE ITEM 15" RC PIPE CULVERTS CLASS IV	40 LF		
0013	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	32 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	260 TON		
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	140 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	16	EA	
001E	2022000000-E	815	SUBDRAIN EXCAVATION	22.4	CY	
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8	CY	
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3	EA	
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1	EA	
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
002E	3420000000-E	SP	GENERIC GUARDRAIL ITEM STEEL BEAM GUARDRAIL	225	LF	
002E	3435000000-N	SP	GENERIC GUARDRAIL ITEM ADDITIONAL GUARDRAIL POSTS	3	EA	
003C	3575000000-E	SP	GENERIC FENCING ITEM TEMPORARY 4 STRAND BARRBED WIRE FENCE WITH POSTS	600	LF	
0031	3649000000-E	876	RIP RAP, CLASS B	10	TON	
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	675	SY	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	335	SF	
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119	SF	
003E	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,160	LF	
0037	6000000000-E	1605	TEMPORARY SILT FENCE	450	LF	
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250	TON	
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70	TON	
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	150	TON	
0041	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	75	LB	
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250	LF	
0045	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5	EA	
0046	6029000000-E	SP	SAFETY FENCE	700	LF	
0047	6030000000-E	1630	SILT EXCAVATION	160	CY	
0048	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,000	SY	
0049	6037000000-E	SP	COIR FIBER MAT	20	SY	
0050	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	300	SY	
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	400	LF	
0052	6070000000-N	SP	SPECIAL STILLING BASINS	2	EA	
0053	6071010000-E	SP	WATTLE	80	LF	
0054	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20	LB	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0057	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0063	6111000000-E	SP	IMPERVIOUS DIKE	150 LF		
0064	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

**CULVERT ITEMS**

006E	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 67.00-L-)	Lump Sum	L.S.	
0067	8196000000-E	420	CLASS A CONCRETE (CULVERT)	56.9 CY		
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	30 TON		
006E	8804000000-N	SP	GENERIC CULVERT ITEM PRECAST REINF CONC 3-SIDED CULVERT @ STA.15 + 67.00-L-	Lump Sum	L.S.	

**Contract No**     **C202273**

**County (ies):**   **Wilkes**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General