

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (29+94.00)	Lump Sum	L.S.	
0005	0036000000-E	225	UNDERCUT EXCAVATION	1,300 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	7,950 CY		
0008	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	450 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0010	0220000000-E	SP	ROCK EMBANKMENTS	650 TON		
0011	0223000000-E	SP	ROCK PLATING	900 SY		
0012	0241000000-E	SP	GENERIC GRADING ITEM FILTER FABRIC FOR ROCK EMBANK- MENTS	360 SY		
0013	0255000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS VI	350 TON		
0014	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	40 SY		
0015	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0016	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0017	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0019	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0020	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,370 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,179 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,270 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	195 TON		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0028	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0029	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0030	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0032	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.29)	4 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	440 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	512.5 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0038	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	600 SY		
0039	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0040	4082000000-E	903	SUPPORTS, WOOD	211 LF		
0041	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0042	4102000000-N	904	SIGN ERECTION, TYPE E	19 EA		
0043	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0044	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2 EA		
0045	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	22 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	320 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	80 SF		
0049	4430000000-N	1130	DRUMS	60 EA		
0050	4435000000-N	1135	CONES	25 EA		
0051	4445000000-E	1145	BARRICADES (TYPE III)	50 LF		
0052	4450000000-N	1150	FLAGGER	600 HR		
0053	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	35 EA		
0054	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,982 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,035 LF		
0056	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	30 LF		
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,800 LF		
0058	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	31 EA		
0059	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0060	6000000000-E	1605	TEMPORARY SILT FENCE	2,100 LF		
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	300 TON		
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	950 TON		
0064	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0067	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250 LF		
0068	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0069	6029000000-E	SP	SAFETY FENCE	4,000 LF		
0070	6030000000-E	1630	SILT EXCAVATION	150 CY		
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500 SY		
0072	6037000000-E	SP	COIR FIBER MAT	50 SY		
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	4,500 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	1,400 SY		
0075	6071010000-E	SP	WATTLE	100 LF		
0076	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0077	6071030000-E	SP	COIR FIBER BAFFLES	325 LF		
0078	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0079	6087000000-E	1660	MOWING	2 ACR		
0080	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0081	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0082	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0083	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0084	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
0085	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0086	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0087	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (28+50.00-L-)	Lump Sum	L.S.	
0088	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (28+50.00-L-)	Lump Sum	L.S.	
0089	8112730000-N	SP	PDA TESTING	5 EA		
0090	8112740000-N	SP	PDA ASSISTANCE	5 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (28+50.00-L-)	Lump Sum	L.S.	
0092	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	216.8 CY		
0093	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (28+50.00-L-)	Lump Sum	L.S.	
0094	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	41,744 LB		
0095	8364000000-E	SP	HP12X53 STEEL PILES	625 LF		
0096	8392000000-N	SP	PIPE PILE PLATES	84 EA		
0097	8393000000-N	SP	PILE REDRIVES	94 EA		
0098	8475000000-E	460	TWO BAR METAL RAIL	1,420.5 LF		
0099	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-7 1/2")	1,435.5 LF		
0100	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	193 TON		
0101	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	215 SY		
0102	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0103	8744000000-N	SP	SOLAR ARRAY SUPPORT PLATFORM	Lump Sum	L.S.	
0104	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	8,592 LF		
0105	8867000000-E	SP	GENERIC STRUCTURE ITEM PP 18 X 0.50 METALLIZED STEEL PILES	1,680 LF		
0106	8867000000-E	SP	GENERIC STRUCTURE ITEM PP 24 X 0.625 METALLIZED STEEL PILES	5,880 LF		

Contract No **C202325**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)