

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+66)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	300 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0008	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	240 SY		
0009	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	70 TON		
0010	0335200000-E	SP	15" DRAINAGE PIPE	60 LF		
0011	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0012	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	56 LF		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	80 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	210 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	18 TON		
0016	2022000000-E	815	SUBDRAIN EXCAVATION	22 CY		
0017	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
001E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
002C	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	52 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	500 SY		
003C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	295 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
0034	5326000000-E	1510	10" WATER LINE	621 LF		
003E	5802000000-E	1530	ABANDON 10" UTILITY PIPE	520 LF		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	5871600000-E	1550	TRENCHLESS INSTALLATION OF 10" IN SOIL	218	LF	
0037	5871610000-E	1550	TRENCHLESS INSTALLATION OF 10" NOT IN SOIL	218	LF	
003E	5882000000-N	SP	GENERIC UTILITY ITEM 10" INSERT GATE VALVE & VALVE BOX, 150# WP	1	EA	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	1,900	LF	
004C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	275	TON	
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	60	TON	
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	75	TON	
0043	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250	LF	
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
004E	6029000000-E	SP	SAFETY FENCE	2,500	LF	
004E	6030000000-E	1630	SILT EXCAVATION	75	CY	
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,950	SY	
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	250	LF	
0052	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	500	SY	
0053	6071030000-E	SP	COIR FIBER BAFFLES	30	LF	

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
006C	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0061	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
<b>STRUCTURE ITEMS</b>						
0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+66.00-L-)	Lump Sum	L.S.	
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+66.00-L-)	Lump Sum	L.S.	
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	43 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+66.00-L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,308 LB		
0067	8364000000-E	SP	HP12X53 STEEL PILES	625 LF		
006E	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	900 LF		
006E	8393000000-N	SP	PILE REDRIVES	22 EA		
007C	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	280.5 LF		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	352 TON		
0072	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	392 SY		
0073	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0074	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,400 LF		
1503/Dec30/Q23920.75/D336644290000/E74			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202268**

**County (ies):**   **Bertie**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General