

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	9,431 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	600 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	29 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	75,467 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	2,270 SY		
0007	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	11,425 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	28,174 TON		
0009	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	50 TON		
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	539 TON		
0011	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,696 TON		
0012	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	153,121 LF		
0013	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	105 TON		
0014	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	925 TON		
0015	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0017	3030000000-E	862	STEEL BM GUARDRAIL	275 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0019	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0020	3360000000-E	863	REMOVE EXISTING GUARDRAIL	125 LF		
0021	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0022	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0023	4480000000-N	1165	TMIA	2 EA		
0024	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	156,014 LF		
0025	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	30,859 LF		
0026	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,600 LF		
0027	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	419 EA		
0028	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	66,171 LF		
0029	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	93 EA		
0030	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	479 EA		
0031	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,383 EA		
0032	6000000000-E	1605	TEMPORARY SILT FENCE	1,454 LF		
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	364 TON		
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	364 TON		
0035	6015000000-E	1615	TEMPORARY MULCHING	14.54 ACR		
0036	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	727 LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.64 TON		
0038	6042000000-E	1632	1/4" HARDWARE CLOTH	727 LF		
0039	6084000000-E	1660	SEEDING & MULCHING	24.67 ACR		
0858/Jan15/Q545952.85/D136725100000/E39			Total Amount Of Bid For Entire Project :			

Contract No **C202562**

County (ies): **Brunswick**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General