

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0005	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0006	0223000000-E	SP	ROCK PLATING	670 SY		
0007	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	1,080 SY		
0008	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RAIL, MINOR STRS	350 TON		
0009	0335200000-E	SP	15" DRAINAGE PIPE	480 LF		
0010	0335300000-E	SP	18" DRAINAGE PIPE	1,218 LF		
0011	0335400000-E	SP	24" DRAINAGE PIPE	448 LF		
0012	0335500000-E	SP	30" DRAINAGE PIPE	780 LF		
0013	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	234 LF		
0014	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	45 LF		
0015	0986000000-E	SP	GENERIC PIPE ITEM 24" SIDE DRAIN PIPE	40 LF		
0016	0986000000-E	SP	GENERIC PIPE ITEM 60" RC PIPE CULVERTS, CLASS III	20 LF		
0017	0992000000-E	SP	GENERIC PIPE ITEM 15" PIPE END SECTION	12 EA		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0992000000-E	SP	GENERIC PIPE ITEM 18" PIPE END SECTION	1 EA		
001E	0992000000-E	SP	GENERIC PIPE ITEM 24" PIPE END SECTION	3 EA		
002C	0995000000-E	340	PIPE REMOVAL	573 LF		
0021	1121000000-E	520	AGGREGATE BASE COURSE	4,868 TON		
0022	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0023	1275000000-E	600	PRIME COAT	2,583 GAL		
0024	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	2,200 SY		
002E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	60 TON		
002E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,690 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,490 TON		
002E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	290 TON		
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	45 TON		
003C	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0031	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0032	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
003E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0034	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	2 EA		
003E	2220000000-E	838	REINFORCED ENDWALLS	12 CY		
0037	2264000000-E	840	PIPE PLUGS	0.11 CY		
003E	2275000000-E	SP	FLOWABLE FILL	4 CY		
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	35 EA		
004C	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	10 CY		
0041	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	7.9 LF		
0042	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	9 EA		
004E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	6 EA		
0044	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	19 EA		
004E	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
004E	2535000000-E	846	***X *** CONCRETE CURB (9" X 12")	1,870 LF		
0047	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	1,645 LF		
004E	2830000000-N	858	ADJUSTMENT OF MANHOLES	8 EA		
004E	3030000000-E	862	STEEL BM GUARDRAIL	825 LF		
005C	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0051	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0052	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0054	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,525 LF		
005E	3649000000-E	876	RIP RAP, CLASS B	19 TON		
005E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	513 SY		
0057	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	4 EA		
005E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	4 EA		
005E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (F)	3 EA		
006C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	632 SF		
0061	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		
0062	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	100 SF		
0063	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	3 DAY		
0064	4430000000-N	1130	DRUMS	122 EA		
006E	4435000000-N	1135	CONES	35 EA		
006E	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0067	4450000000-N	1150	FLAGGER	2,700 HR		
006E	4480000000-N	1165	TMIA	1 EA		
006E	4516000000-N	1180	SKINNY DRUM	25 EA		
007C	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	400 LF		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	200 LF		
0072	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	50 EA		
0073	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,500 LF		
0074	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	275 EA		
007E	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	9 EA		
007E	5882000000-N	SP	GENERIC UTILITY ITEM WATER SERVICE STUBOUT	13 EA		
0077	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
007E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
007E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
008C	6012000000-E	1610	SEDIMENT CONTROL STONE	75 TON		
0081	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0082	6029000000-E	SP	SAFETY FENCE	500 LF		
0083	6030000000-E	1630	SILT EXCAVATION	500 CY		
0084	6036000000-E	1631	MATTING FOR EROSION CONTROL	200 SY		
008E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,000 LF		
008E	6045000000-E	SP	*** TEMPORARY PIPE (36")	134 LF		
0087	6070000000-N	SP	SPECIAL STILLING BASINS	1 EA		
008E	6071010000-E	SP	WATTLE	168 LF		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	6071020000-E	SP	POLYACRYLAMIDE (PAM)	74	LB	
009C	6071030000-E	SP	COIR FIBER BAFFLES	136	LF	
0091	6084000000-E	1660	SEEDING & MULCHING	3.9	ACR	
0092	6111000000-E	SP	IMPERVIOUS DIKE	10	LF	
0093	6114500000-N	SP	SPECIALIZED HAND MOWING	100	MHR	
0094	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	
009E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	400	LF	

1554/Jan12/Q60293.91/D301575360000/E95

Total Amount Of Bid For Entire Project :

**Contract No**     **C202534**

**County (ies):**   **Clay**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General