

County : Greene

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 92.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	70 CY		
0008	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100 CY		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	160 SY		
0010	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	50 TON		
0011	0335200000-E	SP	15" DRAINAGE PIPE	56 LF		
0012	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	408 LF		
0013	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0014	0995000000-E	340	PIPE REMOVAL	56 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	225 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	550 TON		

County : Greene

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	450 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53 TON		
002C	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	60 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	110 LF		
003C	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0031	2619000000-E	850	4" CONCRETE PAVED DITCH	10 SY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		

County : Greene

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	200 SY		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	472 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
004C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,600 LF		
0041	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	15 EA		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	450 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	85 TON		
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75 LF		
005C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0051	6029000000-E	SP	SAFETY FENCE	500 LF		
0052	6030000000-E	1630	SILT EXCAVATION	270 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	700 SY		

County : Greene

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6037000000-E	SP	COIR FIBER MAT	15 SY		
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	335 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0057	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	80 SY		
005E	6071030000-E	SP	COIR FIBER BAFFLES	135 LF		
005E	6071050000-E	SP	*** SKIMMER (2")	2 EA		
006C	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0061	6087000000-E	1660	MOWING	1 ACR		
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0064	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
006E	6114500000-N	SP	SPECIALIZED HAND MOWING	2 MHR		
0067	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

006E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+92.50 -L-)	Lump Sum	L.S.	
007C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+92.50 -L-)	Lump Sum	L.S.	

County : Greene

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	50.8 CY		
0072	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+92.50 -L-)	Lump Sum	L.S.	
0073	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,466 LB		
0074	8364000000-E	SP	HP12X53 STEEL PILES	360 LF		
0075	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	540 LF		
0076	8391000000-N	SP	STEEL PILE POINTS	18 EA		
0077	8503000000-E	460	CONCRETE BARRIER RAIL	195.5 LF		
0078	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	600 TON		
0079	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	660 SY		
008C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0081	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,267.51 LF		
1318/Jan08/Q28986.66/D349114280000/E81			Total Amount Of Bid For Entire Project :			

Contract No **C201638**

County (ies): **Greene**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General