

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	10,000 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+42)	Lump Sum	L.S.	
0005	0036000000-E	225	UNDERCUT EXCAVATION	1,175 CY		
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,250 TON		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,250 SY		
0011	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, & DISPOS- AL OF CONTAMINATED SOIL	45 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	190 SY		
0013	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	155 TON		
0014	0335200000-E	SP	15" DRAINAGE PIPE	140 LF		
0015	0986000000-E	SP	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS IV	376 LF		
0016	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	40 LF		
0017	0995000000-E	340	PIPE REMOVAL	87 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1121000000-E	520	AGGREGATE BASE COURSE	2,380 TON		
001E	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	50 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	975 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	870 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	105 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	135 TON		
002E	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
003C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		
0032	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3.8 LF		
0033	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	3 EA		
0037	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,300 LF		
003E	2591000000-E	848	4" CONCRETE SIDEWALK	970 SY		
003E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	6 EA		
004C	2612000000-E	848	6" CONCRETE DRIVEWAY	500 SY		
0041	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0042	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	6 EA		
004E	3030000000-E	862	STEEL BM GUARDRAIL	75 LF		
0044	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	4 EA		
004E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
004E	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (72")	52 LF		
0047	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	4 EA		
004E	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	2 EA		
004E	3575000000-E	SP	GENERIC FENCING ITEM ALUMINUM ORNAMENTAL FENCE (BLACK)	230 LF		
005C	3575000000-E	SP	GENERIC FENCING ITEM TEMP CHAIN LINK FENCE, 72" FABRIC, 3 STRANDS BARB WIRE	320 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	3578000000-N	SP	GENERIC FENCING ITEM TEMPORARY METAL LINE POSTS FOR 72" CHAIN LINK FENCE	27 EA		
0052	3578000000-N	SP	GENERIC FENCING ITEM TEMPORARY METAL TERMINAL POSTS FOR 72" CHAIN LINK FENCE	3 EA		
0053	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	725 SY		
0054	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	13.5 SF		
005E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	72 LF		
005E	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		
0057	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	443 SF		
005E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	240 SF		
005E	4430000000-N	1130	DRUMS	34 EA		
006C	4445000000-E	1145	BARRICADES (TYPE III)	320 LF		
0061	4450000000-N	1150	FLAGGER	600 HR		
0062	4507000000-E	SP	WATER FILLED BARRIER	413 LF		
0063	4520000000-N	1266	TUBULAR MARKERS (FIXED)	42 EA		
0064	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (IV)	100 LF		
006E	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	1 EA		
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	13,397 LF		
0067	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	106 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	112 LF		
006E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	32 EA		
007C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	34 EA		
0071	5325600000-E	1510	6" WATER LINE	655 LF		
0072	5325800000-E	1510	8" WATER LINE	523 LF		
0073	5326200000-E	1510	12" WATER LINE	171 LF		
0074	5540000000-E	1515	6" VALVE	2 EA		
007E	5546000000-E	1515	8" VALVE	4 EA		
007E	5558000000-E	1515	12" VALVE	2 EA		
0077	5648000000-N	1515	RELOCATE WATER METER	7 EA		
007E	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
007E	5691300000-E	1520	8" SANITARY GRAVITY SEWER	411 LF		
008C	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	3 EA		
0081	5775000000-E	1525	4' DIA UTILITY MANHOLE	5 EA		
0082	5800000000-E	1530	ABANDON 6" UTILITY PIPE	640 LF		
008E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	576 LF		
0084	5804000000-E	1530	ABANDON 12" UTILITY PIPE	135 LF		
008E	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
008E	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	18 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	18		LF
008E	6000000000-E	1605	TEMPORARY SILT FENCE	4,900		LF
008E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	350		TON
009C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200		TON
0091	6012000000-E	1610	SEDIMENT CONTROL STONE	175		TON
0092	6015000000-E	1615	TEMPORARY MULCHING	4		ACR
009E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		LB
0094	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5		TON
009E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	30		LF
009E	6030000000-E	1630	SILT EXCAVATION	490		CY
0097	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,720		SY
009E	6037000000-E	SP	COIR FIBER MAT	15		SY
009E	6042000000-E	1632	1/4" HARDWARE CLOTH	410		LF
010C	6071010000-E	SP	WATTLE	40		LF
0101	6071020000-E	SP	POLYACRYLAMIDE (PAM)	14		LB
0102	6071030000-E	SP	COIR FIBER BAFFLES	140		LF
010E	6071050000-E	SP	*** SKIMMER (1-1/2")	2		EA
0104	6084000000-E	1660	SEEDING & MULCHING	5		ACR
010E	6087000000-E	1660	MOWING	1.5		ACR

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0107	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0108	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0109	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0110	6114500000-N	SP	SPECIALIZED HAND MOWING	5 MHR		
0111	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
<b>WALL ITEMS</b>						
0112	8801000000-E	SP	MSE RETAINING WALLS	4,292 SF		
<b>STRUCTURE ITEMS</b>						
0113	8042000000-N	402	REMOVAL OF EXISTING STRUCTURES AT STATION ***** (19 + 35.95-L-)	Lump Sum	L.S.	
0114	8112730000-N	SP	PDA TESTING	4 EA		
0115	8112740000-N	SP	PDA ASSISTANCE	4 EA		
0116	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19 + 35.95-L-)	Lump Sum	L.S.	
0117	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	17,968 SF		
0118	8161000000-E	420	GROOVING BRIDGE FLOORS	13,130 SF		
0119	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	173.3 CY		
0120	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19 + 35.95-L-)	Lump Sum	L.S.	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	8217000000-E	425	REINFORCING STEEL (BRIDGE)	28,980 LB		
0122	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	509,000 LS		
0123	8364000000-E	SP	HP12X53 STEEL PILES	1,370 LF		
0124	8385200000-E	SP	PP ** X **** GALVANIZED STEEL PILES (24 X 0.5)	2,440 LF		
0125	8391000000-N	SP	STEEL PILE POINTS	50 EA		
0126	8475000000-E	460	TWO BAR METAL RAIL	739.61 LF		
0127	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 3'- 3 3/8")	372.11 LF		
0128	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 3'- 7 3/8")	383.44 LF		
0129	8531000000-E	462	4" SLOPE PROTECTION	572 SY		
013C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0131	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1425/Jan11/Q634563.01/D580738890000/E131

Total Amount Of Bid For Entire Project :



**Contract No**     **C202158**

**County (ies):**    **Iredell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General