

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0004	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM REMOVAL OF EXISTING CURB & GUTTER	270 LF		
0005	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM REMOVAL OF EXISTING CONC IS- LAND COVER	55 SY		
0006	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0007	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0008	0022000000-E	225	UNCLASSIFIED EXCAVATION	196,000 CY		
0009	0036000000-E	225	UNDERCUT EXCAVATION	10,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	7,022 CY		
0011	0141000000-E	240	BERM DITCH CONSTRUCTION	900 LF		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	3,625 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	5,150 SY		
0014	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	20,000 CY		
0015	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	10,000 SY		
0016	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION AND STOCKPILING CONTAMINATED SOIL	50 TON		
0017	0262000000-N	SP	GENERIC GRADING ITEM CONTAMINATED WATER STORAGE VESSEL DAILY RENTAL	50 EA		
0018	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	1,570 SY		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	500 TON		
0020	0343000000-E	310	15" SIDE DRAIN PIPE	40 LF		
0021	0345000000-E	310	24" SIDE DRAIN PIPE	88 LF		
0022	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	160 LF		
0023	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	392 LF		
0024	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	236 LF		
0025	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	620 LF		
0026	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	68 LF		
0027	0536000000-E	SP	**** HDPE PIPE CULVERTS (48")	614 LF		
0028	0536000000-E	SP	**** HDPE PIPE CULVERTS (60")	970 LF		
0029	0684000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK (24", 0.079")	180 LF		
0030	0684000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK (36", 0.109")	753 LF		
0031	0684000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK (42", 0.138")	252 LF		
0032	0684000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK (48", 0.138")	56 LF		
0033	0684000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK (66", 0.168")	52 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	0684000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK (72", 0.168")	140 LF		
0035	0902000000-E	310	**** X **** BIT COAT CS PIPE ARCH CULVERTS, TYPE A ***** THICK (95" X 67", 0.109")	72 LF		
0036	0995000000-E	340	PIPE REMOVAL	1,005 LF		
0037	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0038	1077000000-E	SP	#57 STONE	670 TON		
0039	1121000000-E	520	AGGREGATE BASE COURSE	1,850 TON		
0040	1275000000-E	600	PRIME COAT	1,013 GAL		
0041	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	4,700 SY		
0042	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,350 TON		
0043	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,750 TON		
0044	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	413 TON		
0045	2209000000-E	838	ENDWALLS	63.9 CY		
0046	2220000000-E	838	REINFORCED ENDWALLS	23.4 CY		
0047	2253000000-E	840	PIPE COLLARS	1.1 CY		
0048	2264000000-E	840	PIPE PLUGS	0.23 CY		
0049	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0050	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	16.2 CY		
0051	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	5 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	2531000000-E	SP	GENERIC GRADING ITEM (SY) GEOGRID	6,500 SY		
0053	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	210 LF		
0054	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	790 LF		
0055	2627000000-E	852	4" CONCRETE ISLAND COVERS	120 SY		
0056	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	270 SY		
0057	2752000000-E	SP	GENERIC PAVING ITEM 1'-6" CONCRETE CURB & GUTTER (MOD)	30 LF		
0058	3030000000-E	862	STEEL BM GUARDRAIL	500 LF		
0059	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0060	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0061	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0062	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	1,529 LF		
0063	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	134 EA		
0064	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	41 EA		
0065	3628000000-E	876	RIP RAP, CLASS I	321 TON		
0066	3635000000-E	876	RIP RAP, CLASS II	432 TON		
0068	3649000000-E	876	RIP RAP, CLASS B	220 TON		
0069	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	8,450 SY		
0070	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	3804000000-E	SP	AGGREGATE BASE COURSE (SUB-BALLAST)	36,055	TON	
0072	3876000000-E	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL CONC GRADE CROSS	478	LF	
0073	3876000000-E	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL RUBBER/ASPH GRD CROSS	78	LF	
0074	3880000000-E	SP	GENERIC TRACKWORK ITEM CONSTRUCT TRACK, WOOD TIES, 136RE CC	28,993	TF	
0075	3880000000-E	SP	GENERIC TRACKWORK ITEM CONSTRUCT TRACK, WOOD TIES, 136RE PREM	4,428	TF	
0076	3880000000-E	SP	GENERIC TRACKWORK ITEM FINAL SURFACE & ALIGN TRACK	34,530	TF	
0077	3880000000-E	SP	GENERIC TRACKWORK ITEM STRESS RELIEVE/DESTRESS RAIL	33,421	TF	
0078	3884000000-N	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL BUMPING POST	1	EA	
0079	3884000000-N	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL DBL SWITCH PT DERAIL	1	EA	
0080	3884000000-N	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL FIELD WELDS	198	EA	
0081	3884000000-N	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL INS JOINT PLUG RAILS	44	EA	
0082	3884000000-N	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL NO 10 TURN- OUT	5	EA	
0083	3884000000-N	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL RAIL LUBRI- CATORS	1	EA	
0084	3884000000-N	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL SLIDING BLOCK DERAIL	1	EA	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	3885000000-E	SP	GENERIC TRACKWORK ITEM FURNISH & INSTALL WALKWAY STONE	265 TON		
0087	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	443 SF		
0088	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0089	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	110 SF		
0090	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0091	4430000000-N	1130	DRUMS	40 EA		
0092	4445000000-E	1145	BARRICADES (TYPE III)	160 LF		
0093	4455000000-N	1150	FLAGGER	5 MD		
0094	4520000000-N	1266	TUBULAR MARKERS (FIXED)	102 EA		
0095	4610000000-N	SP	GENERIC TRAFFIC CONTROL ITEM RAILROAD FLAGGING	30 MD		
0096	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,250 LF		
0097	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	172 LF		
0098	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	96 LF		
0099	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
0100	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	43,590 LF		
0101	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	400 LF		
0102	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	1,720 LF		
0103	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,446 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	92 EA		
0105	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4 EA		
0106	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	8 EA		
0107	4915000000-E	1264	7' U-CHANNEL POSTS	90 EA		
0108	5325400000-E	1510	4" WATER LINE	986 LF		
0109	5325800000-E	1510	8" WATER LINE	1,463 LF		
0110	5326200000-E	1510	12" WATER LINE	1,377 LF		
0111	5326600000-E	1510	16" WATER LINE	1,981 LF		
0112	5534000000-E	1515	*** VALVE (12")	6 EA		
0113	5534000000-E	1515	*** VALVE (16")	7 EA		
0114	5534000000-E	1515	*** VALVE (4")	6 EA		
0115	5534000000-E	1515	*** VALVE (8")	4 EA		
0116	5572200000-E	1515	12" TAPPING VALVE	2 EA		
0117	5589100000-E	1515	1" AIR RELEASE VALVE	2 EA		
0118	5606000000-E	1515	2" BLOW OFF	1 EA		
0119	5643200000-E	1515	2" WATER METER	1 EA		
0120	5666000000-E	1515	FIRE HYDRANT	7 EA		
0121	5678200000-E	1515	4" LINE STOP	1 EA		
0122	5678400000-E	1515	6" LINE STOP	1 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	5678600000-E	1515	8" LINE STOP	1 EA		
0124	5691300000-E	1520	8" SANITARY GRAVITY SEWER	254 LF		
0125	5691400000-E	1520	10" SANITARY GRAVITY SEWER	150 LF		
0126	5691600000-E	1520	16" SANITARY GRAVITY SEWER	160 LF		
0127	5709200000-E	1520	4" FORCE MAIN SEWER	1,112 LF		
0128	5709300000-E	1520	6" FORCE MAIN SEWER	192 LF		
0129	5775000000-E	1525	4' DIA UTILITY MANHOLE	8 EA		
0130	5776000000-E	1525	5' DIA UTILITY MANHOLE	4 EA		
0131	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	6 LF		
0132	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	9.7 LF		
0133	5798000000-E	1530	ABANDON *** UTILITY PIPE (15")	160 LF		
0134	5798000000-E	1530	ABANDON *** UTILITY PIPE (2")	112 LF		
0135	5798000000-E	1530	ABANDON *** UTILITY PIPE (4")	2,868 LF		
0136	5800000000-E	1530	ABANDON 6" UTILITY PIPE	192 LF		
0137	5801000000-E	1530	ABANDON 8" UTILITY PIPE	1,909 LF		
0138	5802000000-E	1530	ABANDON 10" UTILITY PIPE	150 LF		
0139	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,363 LF		
0140	5810000000-E	1530	ABANDON 16" UTILITY PIPE	1,933 LF		
0141	5815000000-N	1530	REMOVE WATER METER	1 EA		
0142	5815500000-N	1530	REMOVE FIRE HYDRANT	7 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0143	5828000000-N	1530	REMOVE UTILITY MANHOLE	3 EA		
0144	5835000000-E	1540	*** ENCASEMENT PIPE (10")	483 LF		
0145	5835000000-E	1540	*** ENCASEMENT PIPE (22")	448 LF		
0146	5835000000-E	1540	*** ENCASEMENT PIPE (26")	609 LF		
0147	5835000000-E	1540	*** ENCASEMENT PIPE (56")	160 LF		
0148	5835600000-E	1540	12" ENCASEMENT PIPE	127 LF		
0149	5835800000-E	1540	18" ENCASEMENT PIPE	507 LF		
0150	5835900000-E	1540	20" ENCASEMENT PIPE	100 LF		
0151	6000000000-E	1605	TEMPORARY SILT FENCE	31,800 LF		
0152	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,620 TON		
0153	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	350 TON		
0154	6012000000-E	1610	SEDIMENT CONTROL STONE	90 TON		
0155	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0156	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	2,500 LB		
0157	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	10 TON		
0158	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,800 LF		
0159	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	64 EA		
0160	6029000000-E	SP	SAFETY FENCE	42,000 LF		
0161	6030000000-E	1630	SILT EXCAVATION	5,100 CY		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0162	6036000000-E	1631	MATTING FOR EROSION CONTROL	49,160 SY		
0163	6037000000-E	SP	COIR FIBER MAT	15 SY		
0164	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	3,675 SY		
0165	6042000000-E	1632	1/4" HARDWARE CLOTH	2,500 LF		
0166	6045000000-E	SP	*** TEMPORARY PIPE (24")	320 LF		
0167	6045000000-E	SP	*** TEMPORARY PIPE (48")	8 LF		
0168	6046000000-E	SP	TEMPORARY PIPE FOR STREAM CROSSING	440 LF		
0169	6060000000-E	1637	***X***X*** PERFORATED CS PIPE TEE RISER, 0.109"THICK (48" X 24" X 48")	1 EA		
0170	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		
0171	6071030000-E	SP	COIR FIBER BAFFLES	1,200 LF		
0172	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0173	6071050000-E	SP	*** SKIMMER (2-1/2")	1 EA		
0174	6084000000-E	1660	SEEDING & MULCHING	65 ACR		
0175	6087000000-E	1660	MOWING	41 ACR		
0176	6090000000-E	1661	SEED FOR REPAIR SEEDING	700 LB		
0177	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
0178	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,625 LB		
0179	6108000000-E	1665	FERTILIZER TOPDRESSING	13 TON		
0180	6111000000-E	SP	IMPERVIOUS DIKE	180 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0181	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	100 EA		
0182	6138000000-E	SP	GENERIC EROSION CONTROL ITEM BORROW EXCAVATION FOR TEMP EARTH BERMS	500 CY		
0183	6674000000-N	SP	GENERIC PLANTING ITEM (LS) BERM PLANTING AND LANDSCAPING	Lump Sum	L.S.	
0184	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL AEROSYSTEMS BLVD RR WARN DEV	Lump Sum	L.S.	
0185	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL AIRPORT RD RR WARN DEV	Lump Sum	L.S.	
0186	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL DOBBS FARM RD RR WARN DEV	Lump Sum	L.S.	
0187	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL HARVEY PKWY RR WARN DEV	Lump Sum	L.S.	
0188	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL HULL RD RR WARN DEV	Lump Sum	L.S.	
0189	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL MEWBORNE RD RR WARN DEV	Lump Sum	L.S.	
0190	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL ROUSE RD(1) RR WARN DEV	Lump Sum	L.S.	
0191	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL ROUSE RD(2) RR WARN DEV	Lump Sum	L.S.	
0192	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL SAND CLAY RD RR WARN DEV	Lump Sum	L.S.	
0193	7985000000-N	SP	GENERIC SIGNAL ITEM FURNISH & INSTALL SHACKLEFORD RD RR WARN DEV	Lump Sum	L.S.	
0194	8112730000-N	SP	PDA TESTING	1 EA		
0195	8112740000-N	SP	PDA ASSISTANCE	1 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0196	8126000000-N	414	CULVERT EXCAVATION, STA ***** (14+52.00)	Lump Sum	L.S.	
0197	8126000000-N	414	CULVERT EXCAVATION, STA ***** (191+95.00)	Lump Sum	L.S.	
0198	8126000000-N	414	CULVERT EXCAVATION, STA ***** (52+86.61)	Lump Sum	L.S.	
0199	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	344 TON		
0200	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	136.9 CY		
0201	8217000000-E	425	REINFORCING STEEL (BRIDGE)	26,054 LB		
0202	8245000000-E	425	REINFORCING STEEL (CULVERT)	161,549 LB		
0203	8252000000-E	425	REINFORCING STEEL (RETAINING WALL)	1,304.4 LB		
0204	8384000000-E	SP	HP14X73 STEEL PILES	1,150 LF		
0205	8453000000-E	454	METHOD B DAMPPROOFING	111.1 SY		
0206	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0207	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (154+58.00)	Lump Sum	L.S.	
0208	8826000000-E	420	GENERIC CULVERT ITEM CLASS AA CONCRETE (CULVERT)	928.2 CY		
0209	8867000000-E	SP	GENERIC STRUCTURE ITEM 16" OD GALVANIZED STEEL PIPE PILES	2,560 LF		
0210	8867000000-E	SP	GENERIC STRUCTURE ITEM 4'-0" x 4'-6" PRESTRESS CONC BOX GIRDER	1,246.9 LF		
0211	8867000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE BALLAST CURB	498.8 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0212	8867000000-E	SP	GENERIC STRUCTURE ITEM STEEL HANDRAIL	585 LF		

1134/Feb09/Q847973.83/D936491190000/E210

Total Amount Of Bid For Entire Project :

Contract No **C202402**

County (ies): **Lenoir**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General