

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (27+66.5 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	425 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	350 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	130 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	20 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
0012	0986000000-E	SP	GENERIC PIPE ITEM 15" CS PIPE CULVERTS, 0.064" THICK	32 LF		
0013	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	20 LF		
0014	0992000000-E	SP	GENERIC PIPE ITEM 15" CS PIPE ELBOWS, 0.064" THICK	2 EA		
0015	0995000000-E	340	PIPE REMOVAL	40 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	490 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	310	TON	
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	300	TON	
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	60	TON	
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10	TON	
0022	2000000000-N	806	RIGHT OF WAY MARKERS	14	EA	
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
0025	2556000000-E	846	SHOULDER BERM GUTTER	45	LF	
0026	3030000000-E	862	STEEL BM GUARDRAIL	537.5	LF	
0027	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	87.5	LF	
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0029	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3	EA	
0032	3649000000-E	876	RIP RAP, CLASS B	24	TON	
0033	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,095	SY	
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	586	SF	
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	139	SF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4445000000-E	1145	BARRICADES (TYPE III)	144	LF	
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,240	LF	
0038	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,240	LF	
0039	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	40	LF	
0040	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	24	LF	
0041	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	2	EA	
0042	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	960	LF	
0043	6000000000-E	1605	TEMPORARY SILT FENCE	500	LF	
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250	TON	
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150	TON	
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	250	TON	
0047	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	125	LB	
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0052	6029000000-E	SP	SAFETY FENCE	650	LF	
0053	6030000000-E	1630	SILT EXCAVATION	385	CY	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,250 SY		
0055	6037000000-E	SP	COIR FIBER MAT	50 SY		
0056	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	235 LF		
0058	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0059	6071010000-E	SP	WATTLE	235 LF		
0060	6071020000-E	SP	POLYACRYLAMIDE (PAM)	60 LB		
0061	6071030000-E	SP	COIR FIBER BAFFLES	225 LF		
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0063	6084000000-E	1660	SEEDING & MULCHING	6 ACR		
0064	6087000000-E	1660	MOWING	1 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0069	6114500000-N	SP	SPECIALIZED HAND MOWING	12 MHR		
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0071	6123000000-E	1670	REFORESTATION	0.35 ACR		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (27+66.50-L-)	Lump Sum	L.S.	
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+66.50-L-)	Lump Sum	L.S.	
0074	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	42.67 LF		
0075	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	31 LF		
0076	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	31.66 LF		
0077	8113000000-N	SP	SID INSPECTION	1 EA		
0078	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (27+66.50-L-)	Lump Sum	L.S.	
0080	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,224 SF		
0081	8161000000-E	420	GROOVING BRIDGE FLOORS	8,242 SF		
0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	130.4 CY		
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+66.50-L-)	Lump Sum	L.S.	
0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,793 LB		
0085	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,321 LB		
0086	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	942.5 LF		
0087	8364000000-E	SP	HP12X53 STEEL PILES	295 LF		
0088	8391000000-N	SP	STEEL PILE POINTS	16 EA		

County: Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8475000000-E	460	TWO BAR METAL RAIL	460.42 LF		
0090	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	475.58 LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	275 TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	306 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1028/Jan08/Q70709.08/D457215930000/E94			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202271**

**County (ies):**   **Rowan**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General