

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+79.00)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	70 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	125 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	120 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100 CY		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	145 SY		
0012	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	46 TON		
0013	0335300000-E	SP	18" DRAINAGE PIPE	200 LF		
0014	0335600000-E	SP	36" DRAINAGE PIPE	112 LF		
0015	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	112 LF		
0016	0995000000-E	340	PIPE REMOVAL	222 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	220 TON		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	270 TON		
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	580 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	60 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	21 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	6 EA		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0031	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5 LF		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0037	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	645 LF		
0038	2591000000-E	848	4" CONCRETE SIDEWALK	170 SY		
0039	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	4 EA		
0040	2612000000-E	848	6" CONCRETE DRIVEWAY	60 SY		
0041	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	10 EA		
0042	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		
0043	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0044	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0045	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0046	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	2 EA		
0047	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0048	3628000000-E	876	RIP RAP, CLASS I	60 TON		
0049	3649000000-E	876	RIP RAP, CLASS B	4 TON		
0050	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	930 SY		
0051	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	1.5 SF		
0052	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0053	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	396 SF		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
0055	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	154	SF	
0056	4430000000-N	1130	DRUMS	34	EA	
0057	4435000000-N	1135	CONES	34	EA	
0058	4445000000-E	1145	BARRICADES (TYPE III)	160	LF	
0059	4450000000-N	1150	FLAGGER	3,840	HR	
0060	4516000000-N	1180	SKINNY DRUM	48	EA	
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,096	LF	
0062	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	540	LF	
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	640	LF	
0064	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	24	EA	
0065	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16	EA	
0066	5540000000-E	1515	6" VALVE	1	EA	
0067	5546000000-E	1515	8" VALVE	2	EA	
0068	5648000000-N	1515	RELOCATE WATER METER	2	EA	
0069	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
0070	5801000000-E	1530	ABANDON 8" UTILITY PIPE	191	LF	
0071	5882000000-N	SP	GENERIC UTILITY ITEM STEEL H PILE PIERS	2	EA	
0072	5888000000-E	SP	GENERIC UTILITY ITEM 8" DUCTILE IRON RIGID RESTRAINED JOINT WATER PIPE	60	LF	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	5889000000-E	1510	GENERIC UTILITY ITEM 6" WATER LINE RESTRAINED JOINT DUCTILE IRON	98	LF	
0074	5889000000-E	1510	GENERIC UTILITY ITEM 8" WATER LINE RESTRAINED JOINT DUCTILE IRON	184	LF	
0075	5889000000-E	1510	GENERIC UTILITY ITEM 8" WATER LINE RESTRAINED JOINT DUCTILE IRON CLASS 56	81	LF	
0076	6000000000-E	1605	TEMPORARY SILT FENCE	1,500	LF	
0077	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200	TON	
0078	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150	TON	
0079	6012000000-E	1610	SEDIMENT CONTROL STONE	225	TON	
0080	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0081	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0082	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0083	6029000000-E	SP	SAFETY FENCE	750	LF	
0084	6030000000-E	1630	SILT EXCAVATION	355	CY	
0085	6036000000-E	1631	MATTING FOR EROSION CONTROL	925	SY	
0086	6037000000-E	SP	COIR FIBER MAT	10	SY	
0087	6042000000-E	1632	1/4" HARDWARE CLOTH	260	LF	
0088	6070000000-N	SP	SPECIAL STILLING BASINS	6	EA	
0089	6071010000-E	SP	WATTLE	40	LF	
0090	6071020000-E	SP	POLYACRYLAMIDE (PAM)	12	LB	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6071030000-E	SP	COIR FIBER BAFFLES	60 LF		
0092	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0093	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0094	6087000000-E	1660	MOWING	0.5 ACR		
0095	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0096	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0097	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0098	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0099	6114500000-N	SP	SPECIALIZED HAND MOWING	5 MHR		
0100	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0101	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+79.00-L-)	Lump Sum	L.S.	
0102	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+79.00-L-)	Lump Sum	L.S.	
0103	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	9.5 LF		
0104	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	30 LF		
0105	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	12.3 LF		
0106	8113000000-N	SP	SID INSPECTION	1 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0108	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	885 CY		
0109	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	28.3 CY		
0110	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	75.5 CY		
0111	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+79.00-L)	Lump Sum	L.S.	
0112	8217000000-E	425	REINFORCING STEEL (BRIDGE)	16,538 LB		
0113	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	711 LB		
0114	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,173 LB		
0115	8364000000-E	SP	HP12X53 STEEL PILES	440 LF		
0116	8468000000-E	460	ONE BAR METAL RAIL	110.25 LF		
0117	8482000000-E	460	THREE BAR METAL RAIL	110.25 LF		
0118	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-10 1/2")	117.75 LF		
0119	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	579 TON		
0120	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	643 SY		
0121	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0122	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,882 LF		

Contract No **C202090**

County (ies): **Jackson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General