

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+82.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	440 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	50 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0335200000-E	SP	15" DRAINAGE PIPE	24 LF		
0013	0335300000-E	SP	18" DRAINAGE PIPE	28 LF		
0014	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0015	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	96 LF		
0016	0995000000-E	340	PIPE REMOVAL	111 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,040 TON		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	200 TON		
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,540 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	150 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	15 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	7 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0027	2054000000-E	815	4" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	14 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
003E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	520	LF	
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	400	LF	
004C	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4	EA	
0041	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4	EA	
0042	3649000000-E	876	RIP RAP, CLASS B	335	TON	
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,290	SY	
0044	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	210	LF	
004E	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
004E	4102000000-N	904	SIGN ERECTION, TYPE E	11	EA	
0047	4108000000-N	904	SIGN ERECTION, TYPE F	1	EA	
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	9	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	90	SF	
005C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	115	SF	
0051	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	115	SF	
0052	4430000000-N	1130	DRUMS	60	EA	
005E	4435000000-N	1135	CONES	25	EA	
0054	4445000000-E	1145	BARRICADES (TYPE III)	40	LF	
005E	4450000000-N	1150	FLAGGER	1,080	HR	

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	160	EA	
0057	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,764	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,449	LF	
005E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	90	LF	
006C	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	50	LF	
0061	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	6	EA	
0062	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2	EA	
0063	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	460	LF	
0064	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	30,670	LF	
006E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	170	LF	
006E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	200	LF	
0067	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	24	EA	
006E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	8	EA	
006E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	23	EA	
007C	6000000000-E	1605	TEMPORARY SILT FENCE	2,725	LF	
0071	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	185	TON	

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	215 TON		
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	160 TON		
0074	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0075	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0076	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.5 TON		
0077	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0078	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0079	6029000000-E	SP	SAFETY FENCE	400 LF		
0080	6030000000-E	1630	SILT EXCAVATION	755 CY		
0081	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,000 SY		
0082	6037000000-E	SP	COIR FIBER MAT	30 SY		
0083	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	350 SY		
0084	6042000000-E	1632	1/4" HARDWARE CLOTH	425 LF		
0085	6071010000-E	SP	WATTLE	185 LF		
0086	6071020000-E	SP	POLYACRYLAMIDE (PAM)	45 LB		
0087	6071030000-E	SP	COIR FIBER BAFFLES	555 LF		
0088	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0089	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0090	6087000000-E	1660	MOWING	2.5 ACR		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0092	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0093	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0094	6108000000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
009E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0097	6123000000-E	1670	REFORESTATION	0.4 ACR		
009E	7648000000-N	SP	RELOCATE EXISTING SIGN	2 EA		

---

**STRUCTURE ITEMS**


---

009E	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (14+82.50-L-)	Lump Sum	L.S.	
010C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+82.50-L-)	Lump Sum	L.S.	
0101	8070000000-E	410	FOUNDATION EXCAVATION	284 CY		
0102	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	771 CY		
0103	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,785 SF		
0104	8161000000-E	420	GROOVING BRIDGE FLOORS	4,324 SF		
010E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	95.2 CY		
010E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+82.50-L-)	Lump Sum	L.S.	

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,825 LB		
010E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	571 LB		
010E	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	104,700 LS		
011C	8503000000-E	460	CONCRETE BARRIER RAIL	227.67 LF		
0111	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	166 TON		
0112	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	185 SY		
0113	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0114	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1036/Jan07/Q197030.27/D499026160000/E114

Total Amount Of Bid For Entire Project :

**Contract No**     **C202327**

**County (ies):**    **Montgomery**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General