

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+12.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0007	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	200 CY		
0008	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	30 SY		
0009	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0010	0335200000-E	SP	15" DRAINAGE PIPE	16 LF		
0011	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	68 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	380 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
0016	2000000000-N	806	RIGHT OF WAY MARKERS	7 EA		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	33.6 CY		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
002C	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0021	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0022	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	13 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
003C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	410 LF		
0031	3635000000-E	876	RIP RAP, CLASS II	65 TON		
0032	3649000000-E	876	RIP RAP, CLASS B	40 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,380 SY		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	283 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,260	LF	
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	9	EA	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	1,100	LF	
004C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	340	TON	
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65	TON	
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	225	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
004E	6029000000-E	SP	SAFETY FENCE	950	LF	
004E	6030000000-E	1630	SILT EXCAVATION	200	CY	
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,000	SY	
0051	6037000000-E	SP	COIR FIBER MAT	625	SY	
0052	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200	SY	
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	150	LF	
0054	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
005E	6071030000-E	SP	COIR FIBER BAFFLES	150 LF		
0057	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
005E	6087000000-E	1660	MOWING	1 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0064	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0067	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 12.50-L-)	Lump Sum	L.S.	
006E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	15 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	27 LF		
007C	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	18 LF		
0071	8113000000-N	SP	SID INSPECTION	2 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0073	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15 + 12.50-L-)	Lump Sum	L.S.	
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	71.1 CY		
007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 12.50-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,122 LB		
0077	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,746 LB		
007E	8364000000-E	SP	HP12X53 STEEL PILES	150 LF		
007E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	204.21 LF		
008C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	405 TON		
0081	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	451 SY		
0082	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0083	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,021.04 LF		

0920/Feb09/Q40178.35/D390510480000/E83

Total Amount Of Bid For Entire Project :

Contract No **C202338**

County (ies): **Person**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General