

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	19 EA		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (96+49.00 LT)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (96+49.00 RT)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	12,500 CY		
0009	0038000000-E	SP	SHALLOW UNDERCUT	5,000 CY		
0010	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	10,000 TON		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	9,700 CY		
0012	0141000000-E	240	BERM DITCH CONSTRUCTION	2,500 LF		
0013	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	42,000 SY		
0014	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	9,600 SY		
0015	0192000000-N	260	PROOF ROLLING	45 HR		
0016	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	15,000 SY		
0017	0199000000-E	SP	TEMPORARY SHORING	987 SF		
0018	0223000000-E	SP	ROCK PLATING	3,500 SY		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	7,000 CY		
0020	0241000000-E	SP	GENERIC GRADING ITEM FILTER FABRIC FOR ROADBED STABILIZATION	400 SY		
0021	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	8,320 SY		
0022	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL MINOR STRS	2,650 TON		
0023	0343000000-E	310	15" SIDE DRAIN PIPE	1,060 LF		
0024	0344000000-E	310	18" SIDE DRAIN PIPE	556 LF		
0025	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	180 LF		
0026	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (30")	344 LF		
0027	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (48")	100 LF		
0028	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	960 LF		
0029	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	264 LF		
0030	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	1,344 LF		
0031	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	792 LF		
0032	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0033	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	34 EA		
0034	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	26 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0986000000-E	SP	GENERIC PIPE ITEM 8" DUCTILE IRON PIPE	80 LF		
0036	0995000000-E	340	PIPE REMOVAL	2,570 LF		
0037	0996000000-N	350	PIPE CLEAN-OUT	3 EA		
0038	1000000000-E	462	6" SLOPE PROTECTION	150 SY		
0039	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0040	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	100,000 SY		
0041	1066000000-E	501	LIME FOR LIME TREATED SOIL	1,000 TON		
0042	1077000000-E	SP	#57 STONE	60 TON		
0043	1110000000-E	510	STABILIZER AGGREGATE	17,000 TON		
0044	1176000000-E	542	SOIL CEMENT BASE	100,000 SY		
0045	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	2,800 TON		
0046	1209000000-E	543	ASPHALT CURING SEAL	30,000 GAL		
0047	1220000000-E	545	INCIDENTAL STONE BASE	11,500 TON		
0048	1275000000-E	600	PRIME COAT	2,625 GAL		
0049	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,700 TON		
0050	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	900 TON		
0051	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	750 TON		
0052	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	42,000 TON		
0053	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	3,300 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,520 TON		
0055	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		
0056	2000000000-N	806	RIGHT OF WAY MARKERS	353 EA		
0057	2022000000-E	815	SUBDRAIN EXCAVATION	672 CY		
0058	2033000000-E	815	SUBDRAIN FINE AGGREGATE	336 CY		
0059	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
0060	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60 EA		
0061	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0062	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24 LF		
0063	2143000000-E	818	BLOTTING SAND	30 TON		
0064	2209000000-E	838	ENDWALLS	37.6 CY		
0065	2220000000-E	838	REINFORCED ENDWALLS	10 CY		
0066	2253000000-E	840	PIPE COLLARS	8.121 CY		
0067	2264000000-E	840	PIPE PLUGS	5.66 CY		
0068	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	213 EA		
0069	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	14.6 CY		
0070	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	199.53 LF		
0071	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	27 EA		
0072	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	113 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	57 EA		
0074	2396000000-N	840	FRAME WITH COVER, STD 840.54	8 EA		
0075	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	27 EA		
0076	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	200 LF		
0077	2556000000-E	846	SHOULDER BERM GUTTER	10,000 LF		
0078	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0079	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	600 LF		
0080	2612000000-E	848	6" CONCRETE DRIVEWAY	390 SY		
0081	2619000000-E	850	4" CONCRETE PAVED DITCH	140 SY		
0082	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,700 SY		
0083	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	8,600 SY		
0084	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	160 LF		
0085	2752000000-E	SP	GENERIC PAVING ITEM MILLED RUMBLE STRIPS	96,500 LF		
0086	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0087	3030000000-E	862	STEEL BM GUARDRAIL	13,400 LF		
0088	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	125 LF		
0089	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0090	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0092	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	28 EA		
0093	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	33 EA		
0094	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	4 EA		
0095	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	12 EA		
0096	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,055 LF		
0097	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	11,845 LF		
0098	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	47 EA		
0099	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	47,000 LF		
0100	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	2,850 EA		
0101	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	940 EA		
0102	3628000000-E	876	RIP RAP, CLASS I	885 TON		
0103	3635000000-E	876	RIP RAP, CLASS II	150 TON		
0104	3649000000-E	876	RIP RAP, CLASS B	1,700 TON		
0105	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	29,600 SY		
0106	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0107	3804000000-E	SP	AGGREGATE BASE COURSE (SUB-BALLAST)	2,210 TON		
0108	3812000000-E	SP	RAILROAD TRACK TO BE CONSTRUCTED	1,415 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	3828000000-E	SP	RAILROAD TRACK TO BE REMOVED & RELAID	1,135 LF		
0110	3836000000-E	SP	RAILROAD TRACK TO BE REMOVED	2,655 LF		
0111	3844000000-E	SP	RAILROAD TRACK TO BE LINED	500 LF		
0112	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	1 CY		
0113	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	381 LB		
0114	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	304 LB		
0115	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	4,590 LF		
0116	4096000000-N	904	SIGN ERECTION, TYPE D	12 EA		
0117	4102000000-N	904	SIGN ERECTION, TYPE E	230 EA		
0118	4108000000-N	904	SIGN ERECTION, TYPE F	16 EA		
0119	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	2 EA		
0120	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	4 EA		
0121	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	63 EA		
0122	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	3 EA		
0123	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	4 EA		
0124	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	2,672 SF		
0125	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	480 SF		
0126	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	934 SF		
0127	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0129	4430000000-N	1130	DRUMS	1,000 EA		
0130	4435000000-N	1135	CONES	100 EA		
0131	4445000000-E	1145	BARRICADES (TYPE III)	680 LF		
0132	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0133	4480000000-N	1165	TMIA	2 EA		
0134	4485000000-E	1170	PORTABLE CONCRETE BARRIER	305 LF		
0135	4510000000-N	SP	LAW ENFORCEMENT	80 HR		
0136	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM FLAGGERS	Lump Sum	L.S.	
0137	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	823 EA		
0138	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	126,800 LF		
0139	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	28,364 LF		
0140	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	133 LF		
0141	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	30,650 LF		
0142	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	256 LF		
0143	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	36 EA		
0144	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	138 EA		
0145	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	2,621 LF		



County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	502,190 LF		
0147	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,360 LF		
0148	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	84 EA		
0149	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	10,000 LF		
0150	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,111 EA		
0151	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0152	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
0153	5325200000-E	1510	2" WATER LINE	95 LF		
0154	5325400000-E	1510	4" WATER LINE	44 LF		
0155	5325600000-E	1510	6" WATER LINE	383 LF		
0156	5325800000-E	1510	8" WATER LINE	916 LF		
0157	5326600000-E	1510	16" WATER LINE	424 LF		
0158	5540000000-E	1515	6" VALVE	2 EA		
0159	5546000000-E	1515	8" VALVE	1 EA		
0160	5571800000-E	1515	8" TAPPING VALVE	1 EA		
0161	5648000000-N	1515	RELOCATE WATER METER	38 EA		
0162	5666000000-E	1515	FIRE HYDRANT	1 EA		
0163	5672000000-N	1515	RELOCATE FIRE HYDRANT	5 EA		
0164	5815000000-N	1530	REMOVE WATER METER	3 EA		
0165	5815500000-N	1530	REMOVE FIRE HYDRANT	1 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0166	6000000000-E	1605	TEMPORARY SILT FENCE	60,000 LF		
0167	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	24,100 TON		
0168	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	21,000 TON		
0169	6012000000-E	1610	SEDIMENT CONTROL STONE	14,500 TON		
0170	6015000000-E	1615	TEMPORARY MULCHING	360 ACR		
0171	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	5,050 LB		
0172	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	22 TON		
0173	6024000000-E	1622	TEMPORARY SLOPE DRAINS	15,500 LF		
0174	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	78 EA		
0175	6029000000-E	SP	SAFETY FENCE	22,000 LF		
0176	6030000000-E	1630	SILT EXCAVATION	67,000 CY		
0177	6036000000-E	1631	MATTING FOR EROSION CONTROL	150,000 SY		
0178	6037000000-E	SP	COIR FIBER MAT	1,000 SY		
0179	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	5,600 SY		
0180	6042000000-E	1632	1/4" HARDWARE CLOTH	7,700 LF		
0181	6045000000-E	SP	*** TEMPORARY PIPE (18")	375 LF		
0182	6070000000-N	SP	SPECIAL STILLING BASINS	50 EA		
0183	6071020000-E	SP	POLYACRYLAMIDE (PAM)	3,000 LB		
0184	6071030000-E	SP	COIR FIBER BAFFLES	30,000 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0185	6071050000-E	SP	*** SKIMMER (1-1/2")	53	EA	
0186	6084000000-E	1660	SEEDING & MULCHING	145	ACR	
0187	6087000000-E	1660	MOWING	230.5	ACR	
0188	6090000000-E	1661	SEED FOR REPAIR SEEDING	2,700	LB	
0189	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	7.5	TON	
0190	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	3,075	LB	
0191	6108000000-E	1665	FERTILIZER TOPDRESSING	92.25	TON	
0192	6111000000-E	SP	IMPERVIOUS DIKE	375	LF	
0193	6114500000-N	SP	SPECIALIZED HAND MOWING	100	MHR	
0194	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	72	EA	
0195	6120000000-E	SP	CULVERT DIVERSION CHANNEL	360	CY	
0196	6123000000-E	1670	REFORESTATION	5	ACR	

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
 \*\*\*\*\* ( 2 ALTERNATES ) \*\*\*\*\*

0197	0022000000-E	225	UNCLASSIFIED EXCAVATION	690,000	CY	
<b>AA1</b>						
0198	1121000000-E	520	AGGREGATE BASE COURSE	105,000	TON	
<b>AA1</b>						
0199	1231000000-E	560	SHOULDER BORROW	36,000	CY	
<b>AA1</b>						
0200	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	22,500	TON	
<b>AA1</b>						
0201	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C	46,000	TON	
<b>AA1</b>						
0202	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,505	TON	
<b>AA1</b>						

\*\*\* OR \*\*\*

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0203 AA2	0022000000-E	225	UNCLASSIFIED EXCAVATION	672,000 CY		
0204 AA2	1121000000-E	520	AGGREGATE BASE COURSE	10,500 TON		
0205 AA2	1231000000-E	560	SHOULDER BORROW	7,500 CY		
0206 AA2	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	70,000 TON		
0207 AA2	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	40,500 TON		
0208 AA2	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	5,290 TON		
<p>***** END SCHEDULE AA *****</p> <p>***** BEGIN SCHEDULE AB *****</p> <p>***** ( 3 ALTERNATES ) *****</p>						
0209 AB1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	5,932 LF		
0210 AB1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	8,972 LF		
0211 AB1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	5,240 LF		
0212 AB1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	340 LF		
0213 AB1	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	312 LF		
0214 AB1	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	80 LF		
<p>*** OR ***</p>						
0215 AB2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,580 LF		
0216 AB2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4,956 LF		
0217 AB2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,396 LF		
0218 AB2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	216 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0219 AB2	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	172 LF		
0220 AB2	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	28 LF		
0221 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", .064")	2,352 LF		
0222 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", .064")	4,016 LF		
0223 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", .064")	2,844 LF		
0224 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", .079")	124 LF		
0225 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (36", .079")	140 LF		
0226 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (48", .109")	52 LF		
*** OR ***						
0227 AB3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,580 LF		
0228 AB3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4,956 LF		
0229 AB3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,396 LF		
0230 AB3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	216 LF		
0231 AB3	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	172 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0232 AB3	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	28 LF		
0233 AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	2,352 LF		
0234 AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	4,016 LF		
0235 AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	2,844 LF		
0236 AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	124 LF		
0237 AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	140 LF		
0238 AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (48")	52 LF		
***** END SCHEDULE AB *****						
0288	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
<b>CULVERT ITEMS</b>						
0239	8126000000-N	414	CULVERT EXCAVATION, STA ***** (224+63.70-L-)	Lump Sum	L.S.	
0240	8126000000-N	414	CULVERT EXCAVATION, STA ***** (234+89.70-L-)	Lump Sum	L.S.	
0241	8126000000-N	414	CULVERT EXCAVATION, STA ***** (261+30.70-L-)	Lump Sum	L.S.	
0242	8126000000-N	414	CULVERT EXCAVATION, STA ***** (31+32.10-L-)	Lump Sum	L.S.	
0243	8126000000-N	414	CULVERT EXCAVATION, STA ***** (40+98.50-L-)	Lump Sum	L.S.	
0244	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	273 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0245	8196000000-E	420	CLASS A CONCRETE (CULVERT)	465.2 CY		
0246	8245000000-E	425	REINFORCING STEEL (CULVERT)	61,514 LB		
<b>STRUCTURE ITEMS</b>						
0247	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (96+49.00-L-LT)	Lump Sum	L.S.	
0248	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (96+49.00-L-RT)	Lump Sum	L.S.	
0249	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (96+49.00-L-LT)	Lump Sum	L.S.	
0250	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (45+00.89-L-)	Lump Sum	L.S.	
0251	8105500000-E	SP	***.*** DIA DRILLED PIERS IN SOIL (4'-6")	173.66 LF		
0252	8105600000-E	SP	***.*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	168 LF		
0253	8111000000-E	SP	PERMANENT STEEL CASING FOR ***.*** DIA DRILLED PIER (4'-6")	103.03 LF		
0254	8113000000-N	SP	SID INSPECTION	4 EA		
0255	8115000000-N	SP	CROSSHOLE SONIC LOGGING	8 EA		
0256	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (96+49.00-L-LT)	Lump Sum	L.S.	
0257	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (96+49.00-L-RT)	Lump Sum	L.S.	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0258	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	41,748 SF		
0259	8161000000-E	420	GROOVING BRIDGE FLOORS	38,152 SF		
0260	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	627.4 CY		
0261	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (96+49.00-L-LT)	Lump Sum	L.S.	
0262	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (96+49.00-L-RT)	Lump Sum	L.S.	
0263	8217000000-E	425	REINFORCING STEEL (BRIDGE)	293,592 LB		
0264	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	90,596 LB		
0265	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	28,673 LB		
0266	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	5,281.66 LF		
0267	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	1,982,800 LS		
0268	8364000000-E	SP	HP12X53 STEEL PILES	15,575 LF		
0269	8391000000-N	SP	STEEL PILE POINTS	265 EA		
0270	8440000000-E	454	METHOD A WATERPROOFING	154 SY		
0271	8503000000-E	460	CONCRETE BARRIER RAIL	2,127.28 LF		
0272	8531000000-E	462	4" SLOPE PROTECTION	528 SY		
0273	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	2,947 TON		
0274	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	3,275 SY		
0275	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0276	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	



County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0277	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (45+00.89 -L-)	Lump Sum	L.S.	
0278	8860000000-N	SP	GENERIC STRUCTURE ITEM FOUNDATION EXCAVATION AT ABUTMENT 1	Lump Sum	L.S.	
0279	8860000000-N	SP	GENERIC STRUCTURE ITEM FOUNDATION EXCAVATION AT PIER 1	Lump Sum	L.S.	
0280	8860000000-N	SP	GENERIC STRUCTURE ITEM PAINTING STRUCTURAL STEEL	Lump Sum	L.S.	
0281	8860000000-N	SP	GENERIC STRUCTURE ITEM ROCKER BEARING ASSEMBLIES	Lump Sum	L.S.	
0282	8860000000-N	SP	GENERIC STRUCTURE ITEM TEMPORARY RAILROAD SHORING	Lump Sum	L.S.	
0283	8867000000-E	SP	GENERIC STRUCTURE ITEM METAL HANDRAIL	558 LF		
0284	8881000000-E	SP	GENERIC STRUCTURE ITEM SUBSTRUCTURE CONCRETE	1,425.1 CY		
0285	8881000000-E	SP	GENERIC STRUCTURE ITEM SUPERSTRUCTURE CONCRETE	444.6 CY		
0286	8892000000-E	SP	GENERIC STRUCTURE ITEM DAMPPROOFING (RAILROAD STRUCTURES)	8,660 SF		
0287	8892000000-E	SP	GENERIC STRUCTURE ITEM WATERPROOFING (RAILROAD STRUCTURES)	12,844 SF		

1002/Mar08/Q6212528.691/D1077202000000/E288

Total Amount Of Bid For Entire Project :

**Contract No**     **C202264**

**County (ies):**   **Rutherford**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)