

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	990 SY		
0004	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	320 TON		
0005	0335200000-E	SP	15" DRAINAGE PIPE	1,912 LF		
0006	0335300000-E	SP	18" DRAINAGE PIPE	796 LF		
0007	0335400000-E	SP	24" DRAINAGE PIPE	60 LF		
0008	0986000000-E	SP	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS III	144 LF		
0009	0986000000-E	SP	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	40 LF		
0010	0986000000-E	SP	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	4 LF		
0011	0995000000-E	340	PIPE REMOVAL	1,795 LF		
0012	0996000000-N	350	PIPE CLEAN-OUT	36 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	968 TON		
0014	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	634 SY		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	11,120 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,810 TON		
0017	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	200 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,140 TON		
0019	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0020	1891000000-E	SP	GENERIC PAVING ITEM PAVEMENT FABRIC	28,400 SY		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	35 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2253000000-E	840	PIPE COLLARS	14.5 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	39 EA		
0029	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	39 EA		
0030	2591000000-E	848	4" CONCRETE SIDEWALK	10 SY		
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	75 SY		
0032	2752000000-E	SP	GENERIC PAVING ITEM 8" X 6" ASPHALT CURB	3,178 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	14,300 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	750 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	25 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III MOD)	4 EA		
0037	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	26 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	96 EA		
0039	3360000000-E	863	REMOVE EXISTING GUARDRAIL	226 LF		
0040	3435000000-N	SP	GENERIC GUARDRAIL ITEM 25' CLEAR SPAN GUARDRAIL SECTIONS	8 EA		
0041	3435000000-N	SP	GENERIC GUARDRAIL ITEM ANCHOR GUARDRAIL POST ON BOX CULVERT	14 EA		
0042	3435000000-N	SP	GENERIC GUARDRAIL ITEM EXTRA LENGTH GUARDRAIL POST (9' STEEL)	325 EA		
0043	3566000000-E	867	WOVEN WIRE FENCE RESET	500 LF		
0044	3569000000-E	867	BARBED WIRE FENCE RESET	2,200 LF		
0045	3574000000-E	867	GENERIC FENCING ITEM MISC FENCE RESET	384 LF		
0046	3649000000-E	876	RIP RAP, CLASS B	850 TON		
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,210 SY		
0048	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0049	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	86,100 LF		
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	72,549 LF		
0051	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	180 LF		
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,000 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	533	EA	
0054	6000000000-E	1605	TEMPORARY SILT FENCE	37,150	LF	
0055	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	453	TON	
0056	6012000000-E	1610	SEDIMENT CONTROL STONE	214	TON	
0057	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0058	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500	LB	
0059	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2	TON	
0060	6030000000-E	1630	SILT EXCAVATION	2,450	CY	
0061	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,500	SY	
0062	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	5,600	SY	
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	1,200	LF	
0064	6071020000-E	SP	POLYACRYLAMIDE (PAM)	170	LB	
0065	6071030000-E	SP	COIR FIBER BAFFLES	1,200	LF	
0066	6084000000-E	1660	SEEDING & MULCHING	24	ACR	
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	500	LB	
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2	TON	
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	10	EA	

1016/Mar04/Q305169.5/D221685050000/E69

Total Amount Of Bid For Entire Project :

**Contract No**     **C202401**

**County (ies):**   **Wilkes**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General