

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	86,400 CY		
0007	0036000000-E	225	UNDERCUT EXCAVATION	8,031 CY		
0008	0038000000-E	SP	SHALLOW UNDERCUT	100 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
001C	0134000000-E	240	DRAINAGE DITCH EXCAVATION	815 CY		
0011	0141000000-E	240	BERM DITCH CONSTRUCTION	225 LF		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	17,370 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	590 SY		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0015	0199000000-E	SP	TEMPORARY SHORING	12,360 SF		
0016	0223000000-E	SP	ROCK PLATING	6,400 SY		
0017	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	9,200 CY		
0018	0241000000-E	SP	GENERIC GRADING ITEM GEOGRID REINFORCEMENT	850 SY		
0019	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	4,480 SY		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,430 TON		
0021	0335200000-E	SP	15" DRAINAGE PIPE	540 LF		
0022	0335300000-E	SP	18" DRAINAGE PIPE	476 LF		
0023	0335400000-E	SP	24" DRAINAGE PIPE	52 LF		
0024	0335500000-E	SP	30" DRAINAGE PIPE	92 LF		
002E	0335600000-E	SP	36" DRAINAGE PIPE	188 LF		
002E	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	5,540 LF		
0027	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	2,444 LF		
002E	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	720 LF		
002E	0448500000-E	SP	30" RC PIPE CULVERTS, CLASS IV	1,592 LF		
003C	0448600000-E	SP	36" RC PIPE CULVERTS, CLASS IV	1,160 LF		
0031	0986000000-E	SP	GENERIC PIPE ITEM 15" CS PIPE CULVERTS, 0.064" THICK	24 LF		
0032	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	376 LF		
0033	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	120 LF		
0034	0986000000-E	SP	GENERIC PIPE ITEM 66" RC PIPE CULVERTS, CLASS III	180 LF		
003E	0995000000-E	340	PIPE REMOVAL	1,145 LF		
003E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0037	1110000000-E	510	STABILIZER AGGREGATE	1,200 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1121000000-E	520	AGGREGATE BASE COURSE	10,380 TON		
003E	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
004C	1231000000-E	560	SHOULDER BORROW	2,136 CY		
0041	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	9,560 TON		
0042	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	9,890 TON		
0043	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,510 TON		
0044	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,687 TON		
004E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	850 TON		
004E	2022000000-E	815	SUBDRAIN EXCAVATION	191 CY		
0047	2033000000-E	815	SUBDRAIN FINE AGGREGATE	143 CY		
004E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	850 LF		
004E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	26 EA		
005C	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0051	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0052	2209000000-E	838	ENDWALLS	4 CY		
0053	2220000000-E	838	REINFORCED ENDWALLS	7 CY		
0054	2253000000-E	840	PIPE COLLARS	1 CY		
005E	2264000000-E	840	PIPE PLUGS	0.2 CY		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	151 EA		
0057	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	6 CY		
005E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	82 LF		
005E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	31 EA		
006C	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	12 EA		
0061	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0062	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	48 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	43 EA		
006E	2396000000-N	840	FRAME WITH COVER, STD 840.54	10 EA		
006E	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	9 EA		
0067	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	22 EA		
006E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	6,590 LF		
006E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	15,900 LF		
007C	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	800 LF		
0071	2580000000-E	846	CONCRETE VALLEY GUTTER	210 LF		
0072	2591000000-E	848	4" CONCRETE SIDEWALK	2,000 SY		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	58 EA		
0074	2612000000-E	848	6" CONCRETE DRIVEWAY	70 SY		
0075	2619000000-E	850	4" CONCRETE PAVED DITCH	340 SY		
0076	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	2,990 SY		
0077	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0078	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	2 EA		
0079	3030000000-E	862	STEEL BM GUARDRAIL	2,350 LF		
0080	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	175 LF		
0081	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	4 EA		
0082	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0083	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0084	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6 EA		
0085	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0086	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	1 EA		
0087	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	1,293 LF		
0088	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	108 EA		
0089	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	10 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	3578000000-N	SP	GENERIC FENCING ITEM STEEL PIPE GATE, 24' WIDE	1 EA		
0091	3628000000-E	876	RIP RAP, CLASS I	676 TON		
0092	3649000000-E	876	RIP RAP, CLASS B	307 TON		
0093	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	6,933 SY		
0094	4057000000-E	SP	OVERHEAD FOOTING	13 CY		
009E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,810 LF		
009E	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (69+50 -L-)	Lump Sum	L.S.	
0097	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
009E	4102000000-N	904	SIGN ERECTION, TYPE E	143 EA		
009E	4108000000-N	904	SIGN ERECTION, TYPE F	11 EA		
010C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	67 EA		
0101	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,246 SF		
0102	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	496 SF		
0103	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	477 SF		
0104	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
010E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
010E	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	60 DAY		
0107	4430000000-N	1130	DRUMS	533 EA		
010E	4435000000-N	1135	CONES	93 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	4445000000-E	1145	BARRICADES (TYPE III)	496	LF	
0110	4455000000-N	1150	FLAGGER	450	MD	
0111	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4	EA	
0112	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	4	EA	
0113	4480000000-N	1165	TMIA	2	EA	
0114	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,560	LF	
0115	4507000000-E	SP	WATER FILLED BARRIER	4,039	LF	
0116	4508000000-E	SP	RESET WATER FILLED BARRIER	2,149	LF	
0117	4510000000-N	SP	LAW ENFORCEMENT	120	HR	
0118	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,001	EA	
0119	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	19,481	LF	
0120	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	16,220	LF	
0121	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,997	LF	
0122	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	369	LF	
0123	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	777	LF	
0124	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	20	EA	
0125	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	157	EA	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	512	LF	
0127	4795000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") (IV)	24	LF	
012E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	256,837	LF	
0129	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	14,778	LF	
013C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,194	LF	
0131	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	184	EA	
0132	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	420	EA	
0133	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	35,032	LF	
0134	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,963	LF	
013E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	895	LF	
0136	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	245	EA	
0137	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	601	EA	
013E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	67	EA	
0139	4915000000-E	1264	7' U-CHANNEL POSTS	10	EA	
014C	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	10	EA	
0141	5325200000-E	1510	2" WATER LINE	38	LF	
0142	5325800000-E	1510	8" WATER LINE	512	LF	



County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0143	5327400000-E	1510	24" WATER LINE	4,805		
					LF	
0144	5536000000-E	1515	2" VALVE	1		
					EA	
014E	5540000000-E	1515	6" VALVE	3		
					EA	
014E	5546000000-E	1515	8" VALVE	9		
					EA	
0147	5559400000-E	1515	24" VALVE	11		
					EA	
014E	5571800000-E	1515	8" TAPPING VALVE	6		
					EA	
014E	5572600000-E	1515	16" TAPPING VALVE	2		
					EA	
015C	5589200000-E	1515	2" AIR RELEASE VALVE	2		
					EA	
0151	5648000000-N	1515	RELOCATE WATER METER	3		
					EA	
0152	5653200000-E	1515	2" DCV BACK-FLOW PREVENTOR	2		
					EA	
0153	5666000000-E	1515	FIRE HYDRANT	4		
					EA	
0154	5672000000-N	1515	RELOCATE FIRE HYDRANT	2		
					EA	
015E	5691300000-E	1520	8" SANITARY GRAVITY SEWER	732		
					LF	
015E	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2		
					EA	
0157	5775000000-E	1525	4' DIA UTILITY MANHOLE	5		
					EA	
015E	5776000000-E	1525	5' DIA UTILITY MANHOLE	4		
					EA	
0159	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	23		
					LF	
016C	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	42		
					LF	
0161	5810000000-E	1530	ABANDON 16" UTILITY PIPE	6,648		
					LF	
0162	5816000000-N	1530	ABANDON UTILITY MANHOLE	3		
					EA	
0163	5835900000-E	1540	20" ENCASEMENT PIPE	237		
					LF	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0164	5872100000-E	1550	TRENCHLESS INSTALLATION OF 20" IN SOIL	88	LF	
0165	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN & REBUILD MANHOLE	1	EA	
0166	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN MANHOLE & CONNECT PIPE	1	EA	
0167	5882000000-N	SP	GENERIC UTILITY ITEM TEMPORARY BY-PASS	2	EA	
0168	5882000000-N	SP	GENERIC UTILITY ITEM WATER METER ASSEMBLY	2	EA	
0169	5888000000-E	SP	GENERIC UTILITY ITEM 12" DI SANITARY GRAVITY SEWER	123	LF	
0170	5888000000-E	SP	GENERIC UTILITY ITEM 20" STEEL ENCASEMENT PIPE, 0.250" THICK, BY OPEN CUT	149	LF	
0171	5888000000-E	SP	GENERIC UTILITY ITEM 24" RESTRAINED JOINT DUCTILE IRON WATER LINE	1,934	LF	
0172	5888000000-E	SP	GENERIC UTILITY ITEM 6" RESTRAINED JOINT DUCTILE IRON WATER LINE	45	LF	
0173	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI SANITARY GRAVITY SEWER	116	LF	
0174	5888000000-E	SP	GENERIC UTILITY ITEM 8" RESTRAINED JOINT DUCTILE IRON SEWER	237	LF	
0175	5888000000-E	SP	GENERIC UTILITY ITEM 8" RESTRAINED JOINT DUCTILE IRON WATER LINE	1,167	LF	
0176	5888000000-E	SP	GENERIC UTILITY ITEM SEWER MANHOLE INSIDE DROP ASSEMBLY	5	LF	
0177	5900000000-E	SP	GENERIC UTILITY ITEM SELECT MATERIAL, CLASS VI	90	TON	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
017E	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON FITTINGS	51,231 LB		
017E	6000000000-E	1605	TEMPORARY SILT FENCE	15,700 LF		
018C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,140 TON		
0181	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,110 TON		
0182	6012000000-E	1610	SEDIMENT CONTROL STONE	2,015 TON		
0183	6015000000-E	1615	TEMPORARY MULCHING	31.5 ACR		
0184	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	850 LB		
018E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.75 TON		
018E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,700 LF		
0187	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	12 EA		
018E	6029000000-E	SP	SAFETY FENCE	2,000 LF		
018E	6030000000-E	1630	SILT EXCAVATION	4,145 CY		
019C	6036000000-E	1631	MATTING FOR EROSION CONTROL	24,000 SY		
0191	6037000000-E	SP	COIR FIBER MAT	115 SY		
0192	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	500 SY		
0193	6042000000-E	1632	1/4" HARDWARE CLOTH	2,560 LF		
0194	6045000000-E	SP	*** TEMPORARY PIPE (24")	55 LF		
019E	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0196	6071030000-E	SP	COIR FIBER BAFFLES	1,965	LF	
0197	6071050000-E	SP	*** SKIMMER (1-1/2")	19	EA	
0198	6084000000-E	1660	SEEDING & MULCHING	40	ACR	
0199	6087000000-E	1660	MOWING	20.5	ACR	
0200	6090000000-E	1661	SEED FOR REPAIR SEEDING	250	LB	
0201	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75	TON	
0202	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	500	LB	
0203	6108000000-E	1665	FERTILIZER TOPDRESSING	14.5	TON	
0204	6111000000-E	SP	IMPERVIOUS DIKE	435	LF	
0205	6114500000-N	SP	SPECIALIZED HAND MOWING	5	MHR	
0206	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36	EA	
0207	6120000000-E	SP	CULVERT DIVERSION CHANNEL	458	CY	
0208	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (1, 16")	14	EA	
0209	7060000000-E	1705	SIGNAL CABLE	6,205	LF	
0210	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	44	EA	
0211	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2	EA	
0212	7264000000-E	1710	MESSENGER CABLE (3/8")	2,109	LF	
0213	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	1,995	LF	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0214	7300000000-E	1715	UNPAVED TRENCHING (***** (2, 2")	30 LF		
0215	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	20 EA		
0216	7360000000-N	1720	WOOD POLE	4 EA		
0217	7372000000-N	1721	GUY ASSEMBLY	10 EA		
0218	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0219	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
022C	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1 EA		
0221	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,386 LF		
0222	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	13,610 LF		
0223	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	5 EA		
0224	7576000000-N	SP	METAL STRAIN SIGNAL POLE	12 EA		
022E	7613000000-N	SP	SOIL TEST	12 EA		
0226	7614100000-E	SP	DRILLED PIER FOUNDATION	84 CY		
0227	7636000000-N	1745	SIGN FOR SIGNALS	3 EA		
022E	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0229	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
023C	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	19 EA		
0231	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
0232	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS LIGHTNING ARRESTOR	1 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0233	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1 EA		
0234	7980000000-N	SP	GENERIC SIGNAL ITEM RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	2 EA		
<b>CULVERT ITEMS</b>						
023E	8126000000-N	414	CULVERT EXCAVATION, STA ***** (46 + 10.00-L-)	Lump Sum	L.S.	
023E	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	168 TON		
0237	8196000000-E	420	CLASS A CONCRETE (CULVERT)	294.4 CY		
023E	8245000000-E	425	REINFORCING STEEL (CULVERT)	41,362 LB		
<b>WALL ITEMS</b>						
023E	8801000000-E	SP	MSE RETAINING WALLS	4,921.75 SF		
024C	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	7,607 SF		
1356/Mar02/Q838315.35/D1015055336000/E240						
Total Amount Of Bid For Entire Project :						

**Contract No**     **C202086**

**County (ies):**   **Cumberland**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General