

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (33 + 10.00)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	650 CY		
0005	0038000000-E	SP	SHALLOW UNDERCUT	275 CY		
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	400 TON		
0009	0106000000-E	230	BORROW EXCAVATION	42,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	600 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0012	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	1,000 CY		
0013	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	510 SY		
0014	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	182 TON		
0015	0335200000-E	SP	15" DRAINAGE PIPE	24 LF		
0016	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	572 LF		
0017	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	56 LF		
0018	0986000000-E	SP	GENERIC PIPE ITEM 15" CS PIPE CULVERTS, 0.064" THICK	80 LF		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0986000000-E	SP	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS III	332 LF		
0020	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	40 LF		
0021	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	44 LF		
0022	0986000000-E	SP	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	184 LF		
0023	0986000000-E	SP	GENERIC PIPE ITEM 36" RC PIPE CULVERTS, CLASS III	148 LF		
0024	0992000000-E	SP	GENERIC PIPE ITEM 15" CS PIPE ELBOWS, 0.064" THICK	4 EA		
0025	0995000000-E	340	PIPE REMOVAL	415 LF		
0026	1110000000-E	510	STABILIZER AGGREGATE	100 TON		
0027	1121000000-E	520	AGGREGATE BASE COURSE	5,100 TON		
0028	1220000000-E	545	INCIDENTAL STONE BASE	650 TON		
0029	1275000000-E	600	PRIME COAT	30 GAL		
0030	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	1,170 SY		
0031	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	910 TON		
0032	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,490 TON		
0033	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,530 TON		
0034	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	420 TON		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
003E	2022000000-E	815	SUBDRAIN EXCAVATION	246.4 CY		
0037	2033000000-E	815	SUBDRAIN FINE AGGREGATE	184.8 CY		
003E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,100 LF		
003E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	33 EA		
004C	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	3 EA		
0041	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	18 LF		
004E	2209000000-E	838	ENDWALLS	5.7 CY		
004E	2264000000-E	840	PIPE PLUGS	0.09 CY		
0044	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	16 EA		
004E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.1 LF		
004E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0047	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	2 EA		
004E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
005C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	7 EA		
0051	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	1 EA		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	1 EA		
0053	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	380 LF		
0054	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,010 LF		
0055	2556000000-E	846	SHOULDER BERM GUTTER	70 LF		
0056	2591000000-E	848	4" CONCRETE SIDEWALK	950 SY		
0057	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	5 EA		
0058	2612000000-E	848	6" CONCRETE DRIVEWAY	25 SY		
0059	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	650 SY		
0060	3030000000-E	862	STEEL BM GUARDRAIL	762.5 LF		
0061	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0062	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0063	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0064	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0065	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0066	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0067	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0068	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	1,360 LF		
0069	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	90 EA		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	30	EA	
0071	3574000000-E	867	GENERIC FENCING ITEM 3 STRAND ELECTRIC FENCE RESET	340	LF	
0072	3628000000-E	876	RIP RAP, CLASS I	66	TON	
0073	3649000000-E	876	RIP RAP, CLASS B	211	TON	
0074	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,835	SY	
007E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	590	LF	
007E	4102000000-N	904	SIGN ERECTION, TYPE E	34	EA	
0077	4108000000-N	904	SIGN ERECTION, TYPE F	3	EA	
007E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1	EA	
007E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (F)	1	EA	
008C	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	1	EA	
0081	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	19	EA	
0082	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2	EA	
008E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	592	SF	
0084	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
008E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	220	SF	
008E	4430000000-N	1130	DRUMS	137	EA	
0087	4435000000-N	1135	CONES	53	EA	

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	4445000000-E	1145	BARRICADES (TYPE III)	280	LF	
008E	4455000000-N	1150	FLAGGER	960	MD	
009C	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	321	EA	
0091	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	8,883	LF	
0092	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,673	LF	
0093	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,828	LF	
0094	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	150	LF	
009E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	224	LF	
009E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	5	EA	
0097	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	31	EA	
009E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	440	LF	
009E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,540	LF	
010C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	551	LF	
0101	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	218	LF	
0102	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	20	EA	
0103	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	46	EA	

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	67 LF		
010E	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	400 LF		
010E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	80 LF		
0107	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	154 EA		
010E	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
010E	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
011C	5326600000-E	1510	16" WATER LINE	102 LF		
0111	5606000000-E	1515	2" BLOW OFF	1 EA		
0112	5810000000-E	1530	ABANDON 16" UTILITY PIPE	125 LF		
011E	6000000000-E	1605	TEMPORARY SILT FENCE	8,350 LF		
0114	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	770 TON		
011E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	910 TON		
011E	6012000000-E	1610	SEDIMENT CONTROL STONE	710 TON		
0117	6015000000-E	1615	TEMPORARY MULCHING	17.5 ACR		
011E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500 LB		
011E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3.75 TON		
012C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	550 LF		
0121	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	8 EA		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	6029000000-E	SP	SAFETY FENCE	825 LF		
0123	6030000000-E	1630	SILT EXCAVATION	2,700 CY		
0124	6036000000-E	1631	MATTING FOR EROSION CONTROL	16,800 SY		
0125	6037000000-E	SP	COIR FIBER MAT	90 SY		
0126	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	800 SY		
0127	6042000000-E	1632	1/4" HARDWARE CLOTH	1,225 LF		
0128	6070000000-N	SP	SPECIAL STILLING BASINS	6 EA		
0129	6071010000-E	SP	WATTLE	550 LF		
0130	6071020000-E	SP	POLYACRYLAMIDE (PAM)	131 LB		
0131	6071030000-E	SP	COIR FIBER BAFFLES	1,750 LF		
0132	6071050000-E	SP	*** SKIMMER (1-1/2")	7 EA		
0133	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0134	6084000000-E	1660	SEEDING & MULCHING	23 ACR		
0135	6087000000-E	1660	MOWING	10 ACR		
0136	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0137	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0138	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	375 LB		
0139	6108000000-E	1665	FERTILIZER TOPDRESSING	10 TON		
0140	6114500000-N	SP	SPECIALIZED HAND MOWING	22 MHR		
0141	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24 EA		



County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	7060000000-E	1705	SIGNAL CABLE	800 LF		
0143	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	9 EA		
0144	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	1 EA		
014E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	1 EA		
014E	7264000000-E	1710	MESSENGER CABLE (3/8")	500 LF		
0147	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,250 LF		
014E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	8 EA		
014E	7360000000-N	1720	WOOD POLE	4 EA		
015C	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0151	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0152	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0153	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1 EA		
0154	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,020 LF		
015E	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	3,300 LF		
015E	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	1 EA		
0157	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
015E	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
015E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	6 EA		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
016C	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0161	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1 EA		
0162	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS LIGHTNING ARRESTORS	1 EA		
0163	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEMS	1 EA		
<b>STRUCTURE ITEMS</b>						
0164	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (33 + 10.00-L-)	Lump Sum	L.S.	
0165	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (33 + 10.00-L-)	Lump Sum	L.S.	
0166	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	28.5 LF		
0167	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	18 LF		
016E	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	28.1 LF		
0169	8113000000-N	SP	SID INSPECTION	1 EA		
017C	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0171	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (33 + 10.00-L-)	Lump Sum	L.S.	
0172	8156000000-E	SP	CONCRETE WEARING SURFACE	4,212 SF		
0173	8161000000-E	420	GROOVING BRIDGE FLOORS	4,655 SF		
0174	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	61 CY		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
017E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (33+ 10.00-L-)	Lump Sum	L.S.	
017E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,829 LB		
0177	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,123 LB		
017E	8364000000-E	SP	HP12X53 STEEL PILES	270 LF		
017E	8475000000-E	460	TWO BAR METAL RAIL	199.37 LF		
018C	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" x 3'-5 1/2")	215.21 LF		
0181	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	305 TON		
0182	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	345 SY		
018E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0184	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
018E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,504.56 LF		

0841/Mar09/Q195975.08/D830552242000/E185

Total Amount Of Bid For Entire Project :

**Contract No**     **C202471**

**County (ies):**   **Mecklenburg**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General