

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (43 + 25.00)	Lump Sum	L.S.	
0006	0036000000-E	225	UNDERCUT EXCAVATION	5,000 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0106000000-E	230	BORROW EXCAVATION	43,700 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	4,160 CY		
0010	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	5,000 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	6,500 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	118 SF		
0013	0234000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS III	3,200 CY		
0014	0241000000-E	SP	GENERIC GRADING ITEM FABRIC FOR EMBANKMENT STABILIZATION	500 SY		
0015	0241000000-E	SP	GENERIC GRADING ITEM FILTER FABRIC FOR ROCK EMBANKMENTS	1,800 SY		
0016	0241000000-E	SP	GENERIC GRADING ITEM SECONDARY GEOGRID REINFORCEMENT	700 SY		
0017	0255000000-E	SP	GENERIC GRADING ITEM ROCK EMBANKMENTS	3,400 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0255000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS VI	1,800 TON		
001E	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	90 SY		
002C	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0021	0335200000-E	SP	15" DRAINAGE PIPE	84 LF		
0022	0335300000-E	SP	18" DRAINAGE PIPE	24 LF		
002E	0335400000-E	SP	24" DRAINAGE PIPE	96 LF		
0024	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
002E	0986000000-E	SP	GENERIC PIPE ITEM 18" DUCTILE IRON PIPE	75 LF		
002E	0995000000-E	340	PIPE REMOVAL	96 LF		
0027	1121000000-E	520	AGGREGATE BASE COURSE	1,377 TON		
002E	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
002E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,530 TON		
003C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,150 TON		
0031	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,510 TON		
0032	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	275 TON		
003E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500 TON		
0034	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
003E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0037	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
003E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
003E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
004C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0041	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0042	2556000000-E	846	SHOULDER BERM GUTTER	95 LF		
0043	3030000000-E	862	STEEL BM GUARDRAIL	3,312.5 LF		
0044	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
004E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0047	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,752 LF		
004E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	450 LF		
004E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
005C	3635000000-E	876	RIP RAP, CLASS II	240 TON		
0051	3649000000-E	876	RIP RAP, CLASS B	100 TON		
0052	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,125 SY		
0053	4079000000-N	903	SUPPORTS, BARRIER (SMALL)	1 EA		
0054	4082000000-E	903	SUPPORTS, WOOD	537 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4096000000-N	904	SIGN ERECTION, TYPE D	5 EA		
005E	4102000000-N	904	SIGN ERECTION, TYPE E	14 EA		
0057	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA		
005E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1 EA		
005E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
006C	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	1 EA		
0061	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	1 EA		
0062	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	21 EA		
006E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	615 SF		
0064	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	711 SF		
006E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
006E	4430000000-N	1130	DRUMS	85 EA		
0067	4435000000-N	1135	CONES	30 EA		
006E	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
006E	4450000000-N	1150	FLAGGER	4,800 HR		
007C	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0071	4480000000-N	1165	TMIA	2 EA		
0072	4485000000-E	1170	PORTABLE CONCRETE BARRIER	360 LF		
007E	4516000000-N	1180	SKINNY DRUM	60 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	179 EA		
0075	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	40 LF		
0076	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	46 LF		
0077	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	2 EA		
007E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	3 EA		
0079	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	13,408 LF		
008C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	37,887 LF		
0081	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	80 LF		
0082	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100 LF		
0083	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	4 EA		
0084	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	6 EA		
008E	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	24,421 LF		
0086	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,000 LF		
0087	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	76 EA		
008E	6000000000-E	1605	TEMPORARY SILT FENCE	30,500 LF		
0089	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	310 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	965	TON	
0091	6012000000-E	1610	SEDIMENT CONTROL STONE	835	TON	
0092	6015000000-E	1615	TEMPORARY MULCHING	19.5	ACR	
0093	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	400	LB	
0094	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.75	TON	
009E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	800	LF	
009E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	15	EA	
0097	6029000000-E	SP	SAFETY FENCE	19,000	LF	
009E	6030000000-E	1630	SILT EXCAVATION	620	CY	
009E	6036000000-E	1631	MATTING FOR EROSION CONTROL	20,000	SY	
010C	6037000000-E	SP	COIR FIBER MAT	15	SY	
0101	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	330	SY	
0102	6042000000-E	1632	1/4" HARDWARE CLOTH	1,900	LF	
0103	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	4,150	SY	
0104	6071010000-E	SP	WATTLE	100	LF	
010E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25	LB	
010E	6071030000-E	SP	COIR FIBER BAFFLES	1,900	LF	
0107	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
010E	6084000000-E	1660	SEEDING & MULCHING	18	ACR	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	6087000000-E	1660	MOWING	18	ACR	
0110	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	
0111	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75	TON	
0112	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	375	LB	
0113	6108000000-E	1665	FERTILIZER TOPDRESSING	11.25	TON	
0114	6114500000-N	SP	SPECIALIZED HAND MOWING	40	MHR	
0115	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27	EA	
0116	6123000000-E	1670	REFORESTATION	1.6	ACR	

STRUCTURE ITEMS

0117	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (43 + 25.00-L-)	Lump Sum	L.S.	
0118	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (43 + 25.00-L-)	Lump Sum	L.S.	
0119	8112730000-N	SP	PDA TESTING	7	EA	
0120	8112740000-N	SP	PDA ASSISTANCE	7	EA	
0121	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	115,886	SF	
0122	8161000000-E	420	GROOVING BRIDGE FLOORS	97,742	SF	
0123	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	630.4	CY	
0124	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (43 + 25.00-L-)	Lump Sum	L.S.	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012E	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	118,089 LB		
012E	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	3,231.885 LF		
0127	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	10,115.979 LF		
012E	8333000000-E	SP	16" PRESTRESSED CONC PILES	525 LF		
012E	8336000000-E	SP	20" PRESTRESSED CONC PILES	7,815 LF		
013C	8350000000-E	SP	24" PRESTRESSED CONC PILES	9,690 LF		
0131	8393000000-N	SP	PILE REDRIVES	123 EA		
0132	8475000000-E	460	TWO BAR METAL RAIL	6,684 LF		
0133	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" x 2'-6")	6,699.5 LF		
0134	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	317 TON		
013E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	353 SY		
013E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0137	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
013E	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (43+25.00-L-)	Lump Sum	L.S.	
013E	8744000000-N	SP	SOLAR ARRAY SUPPORT PLATFORM	Lump Sum	L.S.	
014C	8867000000-E	SP	GENERIC STRUCTURE ITEM PREDRILLING FOR PILES	360 LF		

Contract No **C202334**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)

+