

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	64,000 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (154+25)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	1,000 CY		
0008	0038000000-E	SP	SHALLOW UNDERCUT	100 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	50 TON		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	310 CY		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	9,420 SY		
0012	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	790 SY		
0013	0192000000-N	260	PROOF ROLLING	10 HR		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0015	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	200 CY		
0016	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	2,220 SY		
0017	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	710 TON		
0018	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,308 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,472 LF		
0020	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,076 LF		
0021	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	380 LF		
0022	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	176 LF		
0023	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	92 LF		
0024	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	164 LF		
0025	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	896 LF		
0026	0453000000-E	310	*** PIPE END SECTION (24")	1 EA		
0027	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0028	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	20 LF		
0029	0738000000-E	310	42" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	68 LF		
0030	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0031	0995000000-E	340	PIPE REMOVAL	516 LF		
0032	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0033	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	500 LB		
0034	1121000000-E	520	AGGREGATE BASE COURSE	11,000 TON		
0035	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1330000000-E	607	INCIDENTAL MILLING	500 SY		
0037	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	9,050 TON		
0038	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	6,990 TON		
0039	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,440 TON		
0040	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	720 TON		
0041	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	330 TON		
0042	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0043	2000000000-N	806	RIGHT OF WAY MARKERS	39 EA		
0044	2022000000-E	815	SUBDRAIN EXCAVATION	168 CY		
0045	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0046	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0047	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0048	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0049	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0050	2209000000-E	838	ENDWALLS	8 CY		
0051	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	63 EA		
0052	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	55 CY		
0053	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	50 LF		
0054	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	5 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7 EA		
0056	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	16 EA		
0057	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	20 EA		
0058	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	16 EA		
0059	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0060	2418000000-E	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	52 LF		
0061	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	22 EA		
0062	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	1 EA		
0063	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	5,420 LF		
0064	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	7,550 LF		
0065	2591000000-E	848	4" CONCRETE SIDEWALK	1,940 SY		
0066	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	34 EA		
0067	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	210 SY		
0068	2753000000-E	846	GENERIC PAVING ITEM 1'-6" CONCRETE CURB & GUTTER (LMS STANDARD)	4,340 LF		
0069	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0070	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING DROP INLET TO TBJB WITH MANHOLE COVER	1 EA		
0071	3030000000-E	862	STEEL BM GUARDRAIL	875 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
0073	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		
0074	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0075	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0076	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0077	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0078	3375000000-E	SP	REMOVE & STOCKPILE EXISTING GUARDRAIL	2,075 LF		
0079	3524000000-E	SP	VINYL COATED CHAIN LINK FENCE, *** FABRIC (72")	5,600 LF		
0080	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	460 EA		
0081	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	50 EA		
0082	3557000000-E	866	ADDITIONAL BARBED WIRE	200 LF		
0083	3628000000-E	876	RIP RAP, CLASS I	60 TON		
0084	3635000000-E	876	RIP RAP, CLASS II	135 TON		
0085	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0086	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,600 SY		
0087	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	240 SF		
0088	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	410 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	4102000000-N	904	SIGN ERECTION, TYPE E	38 EA		
0090	4142000000-N	907	STOCKPILE SUPPORT, OVERHEAD STRUCTURE	5 EA		
0091	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4 EA		
0092	4360000000-N	SP	GENERIC SIGNING ITEM STOCKPILE OVERHEAD REVERSIBLE LANE SIGNS	21 EA		
0093	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	472 SF		
0094	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	352 SF		
0095	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	89 SF		
0096	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0097	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0098	4430000000-N	1130	DRUMS	650 EA		
0099	4435000000-N	1135	CONES	145 EA		
0100	4445000000-E	1145	BARRICADES (TYPE III)	800 LF		
0101	4455000000-N	1150	FLAGGER	80 MD		
0102	4480000000-N	1165	TMIA	2 EA		
0103	4510000000-N	SP	LAW ENFORCEMENT	64 HR		
0104	4516000000-N	1180	SKINNY DRUM	100 EA		
0105	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,000 LF		
0106	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,780 LF		
0107	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	135 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,580	LF	
0109	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12	EA	
0110	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	32	EA	
0111	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	43,957	LF	
0112	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	150	LF	
0113	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	500	LF	
0114	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	16	EA	
0115	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	50	EA	
0116	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,200	LF	
0117	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	500	LF	
0118	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	201	EA	
0119	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	5	EA	
0120	6000000000-E	1605	TEMPORARY SILT FENCE	4,890	LF	
0121	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175	TON	
0122	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	195	TON	
0123	6012000000-E	1610	SEDIMENT CONTROL STONE	840	TON	
0124	6015000000-E	1615	TEMPORARY MULCHING	30	ACR	
0125	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,500	LB	

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	8 TON		
0127	6030000000-E	1630	SILT EXCAVATION	3,105 CY		
0128	6037000000-E	SP	COIR FIBER MAT	20 SY		
0129	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	7,760 SY		
0130	6042000000-E	1632	1/4" HARDWARE CLOTH	2,010 LF		
0131	6070000000-N	SP	SPECIAL STILLING BASINS	1 EA		
0132	6071030000-E	SP	COIR FIBER BAFFLES	400 LF		
0133	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0134	6071050000-E	SP	*** SKIMMER (3")	1 EA		
0135	6084000000-E	1660	SEEDING & MULCHING	30 ACR		
0136	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0137	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/COUNTDOWN)	4 EA		
0138	7060000000-E	1705	SIGNAL CABLE	900 LF		
0139	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	1 EA		
0140	7180000000-N	1706	BACKPLATE	1 EA		
0141	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	60 LF		
0142	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		
0143	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	475 LF		
0144	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	1,500 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0145	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0146	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	4 EA		
0147	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (1, 154+03)	Lump Sum	L.S.	
0148	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (2, 154+47)	Lump Sum	L.S.	
0149	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	23.2 CY		
0150	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	709.2 CY		
0151	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (154+25 -L-)	Lump Sum	L.S.	
0152	8217000000-E	425	REINFORCING STEEL (BRIDGE)	146,062 LB		
0153	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	2,878 LB		
0154	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" X 2'-8")	148 LF		
0155	8524000000-E	SP	*** CHAIN LINK FENCE (65")	131 LF		
0156	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0157	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,181.3 LF		
0158	8801000000-E	SP	MSE RETAINING WALLS	650 SF		

Contract No **C202388**

County (ies): **Cabarrus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General