

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+97.50-L-)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	2,500 CY		
0004	0038000000-E	SP	SHALLOW UNDERCUT	350 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	700 TON		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0009	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	2,500 CY		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	50 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0335200000-E	SP	15" DRAINAGE PIPE	144 LF		
0013	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	160 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	100 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	370 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
002C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	44 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		
0024	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3628000000-E	876	RIP RAP, CLASS I	4 TON		
0027	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	465 SY		
002E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	577 SF		
002E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	115 SF		
003C	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1 EA		
0031	4430000000-N	1130	DRUMS	5 EA		
0032	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,230 LF		
0034	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,230 LF		
003E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	940 LF		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	11	EA	
0037	6000000000-E	1605	TEMPORARY SILT FENCE	1,470	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70	TON	
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	400	TON	
0041	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	375	LF	
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7	EA	
004E	6029000000-E	SP	SAFETY FENCE	2,100	LF	
0047	6030000000-E	1630	SILT EXCAVATION	150	CY	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,500	SY	
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,900	LF	
005C	6071010000-E	SP	WATTLE	125	LF	
0051	6071020000-E	SP	POLYACRYLAMIDE (PAM)	30	LB	
0052	6071030000-E	SP	COIR FIBER BAFFLES	50	LF	
0053	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0054	6087000000-E	1660	MOWING	1	ACR	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
005E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
006C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0061	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+97.50-L-)	Lump Sum	L.S.	
0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+97.50-L-)	Lump Sum	L.S.	
006E	8112730000-N	SP	PDA TESTING	3 EA		
0064	8112740000-N	SP	PDA ASSISTANCE	3 EA		
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+97.50-L-)	Lump Sum	L.S.	
006E	8156000000-E	SP	CONCRETE WEARING SURFACE	7,870 SF		
0067	8161000000-E	420	GROOVING BRIDGE FLOORS	8,557 SF		
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	78.4 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+97.50-L-)	Lump Sum	L.S.	
007C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,262 LB		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8364000000-E	SP	HP12X53 STEEL PILES	950 LF		
0072	8387000000-E	SP	PP 18 X 0.50 GALVANIZED STEEL PILES	1,925 LF		
0073	8393000000-N	SP	PILE REDRIVES	38 EA		
0074	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	465.5 LF		
0075	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	390 TON		
0076	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	430 SY		
0077	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0078	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0079	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,787 LF		

1620/Apr06/Q66681.15/D381983180000/E79

Total Amount Of Bid For Entire Project :

Contract No **C202328**

County (ies): **Scotland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General